

Through - Parivesh Portal



दूर की सोच'

31st May, 2025

Ref: -PJL/ENV/2025-26/960

To.

Regional Director Ministry of Environment & Forests and Climate Change Regional Office, Western Region Kendriya Paryavaran Bhavan Link Road No. 3, E - 5, Ravi Shankar Nagar Bhopal – 462016

Subject: Submission of Six Monthly Environment Clearance Compliance report for Prism Cement Limited – Integrated ECof Unit-II & Limestone Mines (772.067 HA, 117.594 Ha and 99.416 Ha)

Reference: Environmental Clearance Letter No. F. J-11011/949/2007-IA. II(I), dated 22nd Sep 2008.

Dear Sir,

With reference to the above subject we are pleased to submit the six monthly Environment Clearance compliance report for the period October 2024 to March 2025 for EC granted vide your letter no. F. J-11011/949/2007-IA. II(I), dated 22nd Sep 2008, This report pertains to the compliance of condition stipulated the Environment clearance granted for the Integrated Prism Cement Unit –II and Limestone Mines (772.067 HA, 117.594 Ha and 99.416 Ha)

The compliance report has been prepared as per the stipulated conditions of the environmental clearance. All relevant supporting documents are enclosed herewith for your kind review and consideration.

We trust the report meets the necessary requirements and is in order.

Thank you.

Yours sincerely, For Prism Johnson Limited

Manoj Kumar Kashyap

Vice President

Enclosures: As above

PRISM JOHNSON LIMITED

(Cement Division - Unit II)





Compliance Report with Regard to Environment clearance by MoEFandCC vide letter no. J-11011/949/2007-IA-II(I) Date: 22.09.2008

S.No.	Conditions	Compliance Statu	s
A. Spe	ecific Conditions:		
1.	The gaseous and particulate matter emissions from various units shall conform to the standards prescribed by the Madhya Pradesh Pollution Control Board. At no time, particulate emissions from the cement plant including kiln, coal mill, and cement mill, cooler and captive power plant(CPP) shall not exceed 50 mg/Nm3.	The gaseous and particulate matter emissions from variounits conform to the standards prescribed by the Madhy Pradesh Pollution Control Board. The summary of the tereports along with comparison with standards is given the table below and the test reports are enclosed Annexure 1.	
	Continuous on-line monitors for particulate emissions shall be installed. Interlocking facility shall be provided in the pollution control equipment so that in the event of the pollution control equipment not	Ambient air qualit monitoring system	ent Air quality monitoring system for ty monitoring and Continuous emission in forparticulate emissions and gaseous bring from various units, have been
	working, the respective unit(s) is shut down automatically.	Particular	Location
	automatically.	AAQMS1	Near Steel Yard
		AAQMS2	Near Plant Main Gate
		AAQMS3	2 nd Band Mines
		AAQMS4	Mines Solar
		AAQMS5	Bagahai Mines
		control equipment control equipment be shut down auto The monitored da premises by the m	ta is displayed at the main gate of the eans of digital display board. AQMS, CEMS and display board is
2	Secondary fugitive emissions shall be controlled within the prescribed limits and regularly monitored	prescribed limit. Laboratory is enclo M/s Vibrant Techn no TC-11227 Dtd 2 has been renewed Dtd. 16/12/2024. Tas Annexure 3A.	emission is controlled and is well within The test reports of NABL accredited sed as Annexure 3. o Lab Pvt. Ltd having NABL certificate 20/12/2022 valid upto 19/12/2024 which till 19/12/2028 and CPCB recognition he copies of the certificates are enclosed monitoring is being undertaken by the
	Guidelines/Code of Practice issued by the CPCB in this regard should be followed. The company shall install adequate dust collection and extraction system to control fugitive dust emissions at material transfer points. Atomized water spray system with Reclaimer shall be installed in silo used for	project proponent is well within the pres All the guidelines in this regard to min Bag house/Bag filte to arrest the dust en dust extraction sys installed at each man dust emissions at m	in-house and the monitoring results are scribed limits of DISH. issued by the CPCB are being followed nimize the secondary fugitive emissions. ers, ESP have been installed in the plant hissions. Proper hood/skirt boards for the tem for the dust extraction system are atterial transfer points to control fugitive that the tem secondary fugitive that the dust extraction is stated to the dust extraction system are atterial transfer points.

the storage of ash. Covered conveyer belts shall be used to reduce fugitive emissions. Concreting of all the roads, water sprinkling system at limestone and coal handling area shall be ensured to reduce fugitive emissions

associated with the transfer points have been provided in the plant.

Concrete roads are provided within the plant and colony. Water spray through tankers is done on bare lands and WBM roads for limestone and coal handling areas.

Dense plantation on the periphery and within the plant and colony has been developed. Extensive plantation is done inside plant and mines.

In addition to the above we have installed Atomized permanent water sprinklers and water spraying arrangement in the haul road.

All the internal roads inside plant area are properly paved. Road sweeping machine is in place for cleaning if internal roads. (photographs of housekeeping attached in **Annexure 3B**).

All the five packers in the cement packing section are connected with bag filters. Separate bag filters with proper dust extraction system has been installed for auxiliary circuit of each packages.

Ambient air quality including ambient noise levels shall not exceed the standards stipulated under EPA or by the State authorities.

Ambient air quality including ambient noise levels do not exceed the standards stipulated under EPA or by the State authorities.

The parameters monitored during the period of April 24 to Mar'25 are found within the given stipulations.

The results of analysis for AAQM and Noise are enclosed **Annexure-4** and **Annexure 5.** and summary is given below:

	Summary of AAQ (Oct'24 to Mar'25)										
		PM 10	PM2.5	SO2	NOX	CO	PM 10	PM2.5	SO2	NOX	CO
Month	Particular	µg/М3	μg/M3	μg/M3	µg/М3	µg/М3	μg/М3	µg/М3	µg/М3	µg/М3	µg/М3
		Location -1 (guest house)					Location -2 (near stacker)				
	Min	51.91	25.08	12.22	20.65	BDL	54.77	28.43	13.93	23.04	BDL
	Max	54.82	30.15	13.71	23.54	BDL	59.68	33.35	15.03	25.91	BDL
monthly	Average	53.23	26.80	12.92	22.24	BDL	57.04	29.71	14.41	24.41	BDL
average (Oct'24 –	Particular	Lo	ocation -3 (near adm	in buildin	g)		Locatio	n -4 (steel	yard)	
Mar'25)	Min	54.63	27.63	12.77	21.22	BDL	53.91	25.48	11.49	19.11	BDL
	Max	58.44	31.61	13.70	23.61	BDL	56.12	32.16	14.23	23.80	BDL
	Average	56.40	29.06	13.35	22.64	BDL	54.90	27.65	12.40	21.26	BDL

Summary of AMBIENT NOISE LEVELS MONITORED (Oct'24 to Mar'25)							
Mandh	Logotion	Day Time Leq Value in dB(A)			Night Time Leq Value in dB(A)		
Month	Location	Min	Max	Average	Min	Max	Average
	Near Stacker	55.2	60.05	57.86	50.95	52.77	51.69
43.3	Near Guest house	50.9	57.37	54.85	46.72	51.05	49.22
monthly average (Oct'24 – Mar'25)	Near Steel Yard	51.02	61.27	54.68	47.65	53.22	49.28
	Near Admin Building	52.55	58.95	55.12	48.5	50.92	49.87

Monitoring of ambient air quality and shall be carried-out regularly in consultation with MPPCB and data for air emissions shall be submitted to the CPCB and MPPCB regularly.

The instruments used for ambient air quality monitoring shall be calibrated time to time.

Regular ambient air quality monitoring and noise level monitoring are done with the calibrated instruments. Ambient air quality and Ambient Noise levels does not exceed the standards stipulated under EPA or by the state authorities.

Calibration certificates are attached at -Annexure no. 6

4 Efforts shall be made to reduce impact of the transport of the raw materials and end products on the surrounding environment including agricultural land.

M/s Prism Johnson Limited has developed well defined method to reduce the Impact of transport of raw material and product on the surrounding environment and over agricultural land. Raw materials and end products are being transported in trucks covered by the tarpaulin and bulkers to reduce the effects of fugitive emission on the surrounding environment and agriculture land.

Raw materials and end products are transported within the plant premises with the help of closed conveyor belts to reduce impact of transport. Other measures adopted to reduce the impact of transport are as follows:

- 1. All the Roads inside the plant premises are concreted.
- 2. Water spraying with the help of water tanker is done in plant to control fugitive emission which can be caused by the movement of vehicles.
- 3. Raw materials and end products are transported within the plant premises with the help of closed conveyor belts to reduce impact of transport.
- 4. 121 No's Bag-filters have been installed to control fugitive emission.
- 5. Storage sheds are made to store material.
- 6. Dense plantation is done in Plant and Mines premises.























Rail transport system has also been used which also help to reduce impact on the environment.



5. Fly ash shall be utilized as per the provisions of Fly Ash Notification-1999, subsequently amended in 2003. Fly ash shall be stored in ash silo and 100% used in the cement manufacturing

Fly ash is being utilized as per the provisions of Fly Ash Notification 1999, subsequently amended in 2003.

Fly ash is being transported by the means of closed bulkers and it is stored in Silos and 100 % fly ash is used in cement manufacturing.

Consumption of fly ash is as follows:

Yearly Fly Ash Consumption				
Year Qty	(MT)			
2014-2015	907848			
2015-2016	848939			
2016-2017	810908			
2017-2018	701922			
2018-2019	855770			
2019-2020	808392			
2020-2021	906630			
2021-2022	795176			
2022-2023	923068			
2023-2024	1010363			
2024-2025	961246			

6. The company shall make the efforts to utilize the high calorific hazardous waste in the cement kiln and necessary provisions shall be made accordingly. The company shall keep the record of the waste utilized and shall submit the details to Ministry's Regional Office at Bhopal, CPCB and SPCB.

Permission for utilization of High calorific hazardous waste in the cement kiln has been taken.

Copy of same is enclosed as Annexure 07.

Record of the waste utilized is being maintained and is submitted to the Ministry's Regional Office at Bhopal, CPCB and SPCB. Details of hazardous waste used in (Apr'24-Mar'25) is as under:

Category	Waste Type	Total (MT)
I-28-28.6	Spent Solvent	27.34
Waste Mix Liquid	Waste Mix Liquid	3648.245
Waste Mix Solid	808.57	
Grand	4484.155	

7. Total water requirement shall not exceed 2500 m3/day.

Total per day water consumption for industrial purpose 410.68 m³/day, water usage for domestic purpose in new colony is 259.24 m³/day and usage for horticulture is 263.46 m³/day (this water generated is treated with the help of STP having capacity of 600 KLD and the treated water is being used for the development of green belt).

The water consumption figures of the last six month is summarized below:

Month	Unit-II	Colony	STP water recycled
Oct'24	14059	9299	10537
Nov'24	10733	8222	7382
Dec'24	1369	8618	5597
Jan'25	13014	8931	5365
Feb'25	16723	5718	9073
March'25	18846	6394	9996
Total (KL)	74744	47182	47950
per day average (KL)	410.68	259.24	263.46

The treated wastewater from STP and utilities shall be reutilized for green belt development and other plant related activities i.e. Cooling and dust suppression in raw material handling area etc., after necessary treatment.

'Zero' discharge shall be strictly adopted and no effluent from the process shall be discharged outside the premises. STP of capacity 600 KLD has been installed to treat the domestic waste water generated and the treated waste water is being utilized for green belt development, dust suppression and cooling and the sludge waste so generated from the sewage treatment plant is used as manure in plantation.

No effluent discharge from the plant premises is there and has maintained the Zero discharge.

The analysis of STP outlet water is done by M/s Vibrant Techno Lab Pvt. Ltd having NABL certificate no TC-11227 Dtd 20/12/2022 valid upto 19/12/2024 which has been renewed till 19/12/2028 and CPCB recognition Dtd. 16/12/2024. The copies of the certificates are enclosed as **Annexure 3A.**

Analysis of treated water is enclosed as Annexure 8.




Figure: Sewage Treatment Plant

8	Rainwater harvesting measures shall be adopted for the augmentation of ground water at cement plant, colonyand mine site.	Rain water harvesting measures have been implemented in plant premises as well in Mines and nearby villages. Details of water harvesting measures are mentioned below: 1. Water harvesting pond of capacity 13 Lac m³ has been constructed in Mines area.
		 2. There are 12 Nos of Roof top rain water harvesting structures inplant premises listed below: MRSS building Project Office building School Building. Cement Mill Unit II Load Center Cooler load Center of Unit I Cooler load Center of Unit II Store building. New security barrack Duratech shed Packing plant Unit-1
		 Packing plant Unit-2 Mines workshop Recharge Bore Hole for Recharging the Ground Water - 22 Nos.
		4. Deepening of Ponds at Mankahari and Bamhauri village with Hume pipe and ground water recharge system.5. Construction of water reservoir at Baghai village for
		waterconservation. 6. In the FY24-25 two new rain water harvesting structure constructed at Colony Cafeteria and Behind B-Type. (photographs attached).
		Photographs of rain water Harvesting Structure is enclosed as Annexure 09 .
	Besides, company must also harvest the rain water from the roof tops and storm water drains to recharge the ground water	There are 12 Nos of Roof top rain water harvesting structures inplant premises These are: 1. MRSS building 2. Project Office building 3. School Building. 4. Cement Mill Unit II Load Center 5. Cooler load Center of Unit I 6. Cooler load Center of Unit II 7. Store building. 8. New security barrack 9. Duratech shed 10. Packing plant Unit-1 11. Packing plant Unit-2 12. Mines workshop 3 More RWH structures are under progress. Filters have been installed at roof top drain so as to filter out the dust, grits solid contents into bore-wells.
	The company must also collect rain water in the mined out pits of captive lime stonemine and use the same water for the various activities of the project to avoid fresh water requirement.	The company collects rain water in the mined out pits of captive lime stone mine and use the same water for the various activities. The water is used for various activities i.e. spraying On haul roads, crusher hopper, green belt development etc. Rain water harvesting pond with capacity of 13 lac m3 has been developed and the harvested water is used for various purpose which helps conservation of fresh ground

		water.
	The company shall construct the rain water harvesting and ground water recharge structures outside the plant premises also in consultation with local gram panchayat and Village heads to augment the ground water level.	Rain water Harvesting structures have been measures have been implemented in nearby villages are also. Some of them are as follows: 1. Deepening of Ponds at Mankahari and Bamhauri village with Hume pipe and ground water recharge system.
	An action plan shall be submitted to Ministry's Regional Office at Bhopal within 3months from date of issue of this letter.	2. Construction of water reservoir at Baghai village for water conservation.Ground water recharge structure along with recharge details is enclosed as Annexure 10.
9.	The project proponent shall modify the mine plan of the project at the time of seeking approval for the next mining scheme from the Indian Bureau of Mines so as to reduce the area for external over burden dump by suitably increasing the height of the dumps with proper terracing. It shall be ensured that the overall slope of the dump does not exceed 28°.	We have obtained approval of further Schemes of mining for the leases of PCL as follows: 1. 772.067 ha (Hinauti and Sijahata) vide IBM letter no MP/Satna/ Limestone/RMP-39/2019-20 Dt.31.03.2020, 2. 99.416 ha (Hinauti and Sijahata) vide IBM letter no MP/Satna/ Limestone/RMP-44/17-18Dt. 27.04.2017 3. 512.317ha (Baghai) vide IBM letter no MP/Satna/Limestone/RMP57/2020-21 Dt.09.04.2021 and 4. 117.594 ha (Mendhi) vide IBM letter no MP/Satna/ Limestone M.Sch-6/16-1 Dt. 04.11.2016 by the Indian Bureau of Mines. Copy of approval letter is enclosed as Annexure 11. Dump height and slope has been maintained as per guidelines. The details are enclosed as Annexure 12.
10	Top soil if any, shall be stacked with proper slope at earmarked site(s) only with adequate measures and should be used for reclamation and rehabilitation of mined out areas.	Top soil generated during mining is stacked separately and used for reclamation of mined out area by spreading it over the waste rock after backfilling. The top soil is being used as per the approved Scheme of Mining for rehabilitation purposes. The soil dumps are adequately protected by plantation to control soil erosion and maintain soil fertility.
11	The project proponent shall ensure that no natural water course shall be obstructed due to any mining and plant operations	The Surface water bodies in area are observed as Tamas River which is adjacent to the Hinauti and Sijhata Limestone Mine in North direction. The Magardaha nalla is located outside the lease area in thewestern side. Magardaha nalla ultimately joins the Tamas River. NarNala falls outside the lease area and flanks the Baghai mining lease from the western side. No natural water course is obstructed due to mining and plant operations. The company is taking following measures for Protection of the Tamas River, Magardaha Nala and NarNala (natural water course) which is adjacent to the Hinouti Sijhata and Baghai Limestone Mine in North East and west direction respectively. • Solid barrier of minimum 60 m width has been made from the river bank to avoid the flow of surface run

	The company shall make the plan for protection of the natural water course passing nearby mine area and submit to the Ministry's Regional Office at Bhopal.	off to the River. • Garland drains made along the slope of dumps. • Rain water is channelized to a Settling Tank to eliminate silting of river and then discharged in natural drainage course. • Plantation has been done all along inside safety barrier of Tamas River. • Proper landscape has been developed near the River bank to avoid erosion. There is no proposal for diversion/obstruction/modification of any natural water course during mining activity. The proposal for natural water course protection passing nearby mines area is submitted. Copy is enclosed as Annexure 13.
12	The inter burden and other waste generated shall be stacked at earmarked dump site(s) only and should not be kept active for long period.	The inter burden and waste generated during mining has been stacked at earmarked dump site as per approved mining plan. Dumps have been stabilized simultaneously by planting local species and bushes i.e. Bouganvilliea, karanj, Alstonia, Neem etc. In FY 2024-25 total 25,250 number of plantation has been done in Mines area and 10016 no. of plantation has been done in plant and colony premises. In addition to the above under CSR activities, 5200 number of plantation done in nearby village area. As on date the plant and colony premises have been vegetated with the area more than 34% of the total area. Total 25.33acre area has been developed as green lawn and 79.82acre area has been covered with variety of tree plantation of local varieties.
	The total height of the dumps shall not exceed 30 m in three terraces of 10 m each and the overall slope of the dump shall be maintained to 28. The inter burden dumps should be scientifically vegetated with suitable native species to prevent erosion and surface run off.	The total height of the dumps is not exceeding then 30 m and the slope of the dumps are maintained at 28°. Details regarding dumps is enclosed as Annexure 12 .
	Monitoring and management of rehabilitated areas should continue until the vegetation becomes self- sustaining.	Monitoring and management of rehabilitated areas will becontinued until the vegetation becomes self-sustaining.

	Compliance status should be submitted to the Ministry of Environment and Forests and its Regional Office, Bhopal on six monthly bases.	Compliance status is submitted on regular basis to Ministry of Environment and Forests and its Regional Office, Bhopal. Last EC Compliance was submitted vide letter no. PJL/ENV/2024/888 dated 30.11.24.
13	The void left unfilled shall be converted into water body.	Agreed. A Rain water harvesting reservoir has been already developed which is having capacity of 13 lakh Cubic meter. The accumulated water is used for industrial purpose at mine and cement plant. Proper landscaping is done around the water body.
	The higher benches of excavated void/mining pit shall be terraced and plantation to be done to stabilize the slopes. The slope of higher benches shall be made gentler for easy accessibility by local people to use the water body.	Mined out pit has been terraced and the gentle slope is stabled and planted with adequate vegetation of local species.
	Peripheral fencing shall be carried out along the excavated area.	Fencing is being done around the periphery of Mines excavated area. Bagahai, Machya Pradosh, India Untarred Road, Bagahai, Machya Pradosh, ABB111, India Lata-Sos0524 Long 81-04-35227 12/01/24 GMT05:30
14	Catch drains and siltation ponds of appropriate size should be constructed for the working pit, inter-burden and mineral dumps to arrest flow of silt and sediment.	Approximately 720 m. of Catch drains along dumps and 02 siltation ponds of appropriate size have been constructed. The catch drains are for inter-burden and Mineral dumps to arrest flow of silt and sediment. Garland drain along lease boundaries of 3.0 Km (cumulative in two locations) has been constructed. Check dams have been made at regular intervals in garland drains tohinder the flow of rain water and to arrest the silt.






		Figure 1 and
		Bagahai, Madhya Pradesh, India Unnamed Bad, Bagahai, Madhya Pradesh 485111, India Lat 24.560574 Long 81.04277 12/01/24 GMT+05:30
	The water so collected should be utilized for watering the mine area, roads, green belt development etc. The drains should be regularly de-silted, particularly after monsoon, and maintained properly.	Complying with. The water so collected is being utilized for watering of Mine area, Green belt development etc. The drains are regularly de- silted, particularly after monsoon, and maintained properly.
15	Garland drain of appropriate size, gradient and length shall be constructed for both mine pit and inter-burden dumps and sump capacity should be designed keeping 50% safety margin over and above peak sudden rainfall (based on 50 years data) and maximum discharge in the area adjoining the mine site. Sump capacity should also provide adequate retention period to allow propersettling of silt material. Sedimentation pits should be constructed at the corners of the garland drains and de-silted at regular intervals.	Garland drain having dimension of cumulative length of 3.0 Km, a width of 2.0 to 3 meters and depth of 0.75 to 1.2 meter. It is having appropriate gradient following Natural contour. Sump size of length 25m x width 15m and depth 4m. has been constructed along the garland drain. One additional siltation ponds has been constructed. It is having a capacity of 50% safety margin to accommodate over and above peak sudden rainfall and maximum Discharge in the area. Garland drains and de-siltation ponds are de-silted at regular intervals, especially after monsoon.
16	Dimension of the retaining wall at the toe of inter-burden dumps and inter-burden benches within the mine to check run-off and siltation should be based on the rain fall data.	Retaining walls and siltation and toe drains are maintained to check runoff and siltation.
17	Regular monitoring of ground water level and quality should be carried out by establishing a network of existing wells and constructing new piezometers at suitable	Regular monitoring of ground water level and quality is being carriedout by the means of constructed Piezometers at the site in and around Project area. Frequency of monitoring is four times a year- pre-monsoon

	locations by the project proponent in and around project area in consultation with Regional Director, Central Ground Water Board. The frequency of monitoring should be four times a year- pre-monsoon (April / May), monsoon (August), post monsoon (November), and winter (January). Data thus collected shall be sent at regular intervals to Ministry of Environment and Forests and its Regional Office at Bangalore, Central Ground Water Authority and Central Ground Water Board.	(April / May), monsoon (August), post monsoon (November) and winter (January). The monitoring results for Ground Water Quality and water level is being submitted to the MoEF, New Delhi, Regional Office of MoEF, Bhopal, Central Ground Water Authority, New Delhi, Central Ground Water Board, Bhopal on regular basis. Analysis report is enclosed as Annexure 14(a)and(b).
18	Blasting operation should be carried out only during the daytime.	Complying with. Blasting operations are carried out during the day time only.
	Controlled blasting shall be practiced. The mitigative measures for control of ground vibrations and to arrest fly rocks and boulders shall be implemented	Controlled blasting is carried out according to the recommendation of Central Institute of Mining and Fuel Research. The salient recommendations are given below: • The AOP has been recorded within prescribed limits All the recorded data (blast vibrations, air overpressures and fly rocks) were well within the safe limit at the houses/structures concerned. The dominant peak frequencies of ground vibrations were in the range of 11.4 to 129 Hz. FFT analysis of blast vibration frequencies confirmed that concentration of frequencies is in band of 13.3-40.3 Hz. So, the safe level of vibration has been taken as 10 mm/s for the safety of houses/structures of the surrounding villages as per DGMS standard. • Propagation equation for the prediction of blast vibration has been established and is given as Equation 1. The permissible explosive weight per delay may be computed from the Equation to contain vibration within safe limits for distances of houses/ structures concerned. For convenience, the recommended explosives weight per delay has been computed and is given in Table A3. • The delay interval between the holes in a row should be 17 ms whereas between the rows, it should be 65 ms or more depending upon the number of rows and effective burden. If the numbers of rows are more than two, the delay interval between rows should be increased by 15% in successive rows. • It is recommended that the existing Nonel initiation systemshould be continued in the Blasting operations and Electronic initiation systems should be practiced on the benches near to the structures for more precise and accurate delay design. The sub-grade drilling should be 0.3 to 0.5 m for a blast holedepth of 6 to 7 m and should be initiated from the Bottom of the hole. • It is advisable to use blasting mate with sand bags in sensitive area to ensure any non ejection of fly rocks. For this Nonel as well as electronic system may be used as an Initiation system. Each blast is monitored for vibrations with Minimate and Noise seismographs.

		Vibration report is enclosed as A	Annexure 15.
19	The project proponent shall adopt wet drilling.	Complying with Regular wet drilling is practiced	d.
20	As proposed, green belt should be developed in 33% in and around the plant as per the CPCB guidelines.	In FY 2024-25 total 25250 num done in Mines area and 10016 been done in plant and colony p In addition to the above under of plantation done in nearby vil	number of plantation has remises. CSR activities, 5200 number
21	All the recommendations of the Corporate Responsibility for Environmental Protection (CREP) shall be strictly followed.	Action Plan Cement Plant, which are not complying with notified standards shall do the following to meet the standards. Augmentation of existing Air Pollution Control Devices: by July 2003 Replacement of existing Air Pollution Control devices: by July 2003. Cement plants located in the critically polluted or urban areas (including 5 Km distance outside urban boundary) will meet 100 Mg/Nm3 limit of particulate matter by December 2004 and continue working to reduce the emission of the particulate to 50 mg/Nm3.	Complied with. Complied with. We are achieving the PM emission norms within 30 mg/Nm3.
		The new cement kilns to be accorded NOC/	Complied.

Environmental Clearance	
w.e.f 01.04.2003 will meet	
the limit of 30 mg/Nm3 for	
particulate matter emissions.	
CPCB will evolve load based	
standards by December 2003.	
CPCB and NCBM will evolve	Not applicable.
SO2and NOx emission	
standards by June 2004	
The cement industries will	Complied
control fugitive emissions	Bag Filters installed
from all the raw material and	at all Material transfer points, Water
products storage and transfer points by December 2003.	spraying regularly on
However, the feasibility for the	haul roads.
control of fugitive emissions	naui ivaus.
from limestone and coal	
storage areas will be decided	91
by the National Task Force	
(NTF). The NTF shall	
submit its recommendations	
within three months.	
CDCD VCDV DVC	
CPCB, NCBM, BIS and	We are using pet coke.
Oil	
refineries will jointly prepare the policy on use of	
petroleum coke as fuel in	
cement kiln by July 2003	
After performance evaluation	Installed continuous
of various types of	monitoring systems
continuous monitoring	(CEMS) in all process
equipment and feedback from	stack.
the industries and equipment	suck.
manufacturers, NTF will	
decide feasible unit	
operations/sections for	
installation of continuous	
monitoring equipment. The	
industry will install the	
continuous monitoring	
systems (CMS) by December	
2003.	
Trippings in kiln ESP to be	Complied.
minimized by July 2003 as per	
the recommendation of NTF	
Industries will submit the	We are using the
target date to enhance the	AFR waste material
utilization of waste material	in our kiln.
by April 2003.	
NCBM will carry out a	Not Applicable
study on hazardous waste	
utilization in cement kiln	
by December 2003	
Cement industries will carry	Agreed.
out feasibility study and	

		submit target dates to CPCB for co-generation of power by July 2003
22	Vehicular emissions should be kept under control and regularly monitored. Measures shall be taken for maintenance of vehicles used in mining operations and in transportation of mineral. The vehicles should be covered with a tarpaulin and shall not be overloaded.	Vehicular emission is kept under control. Regular maintenance of all vehicles is done as per manufacturer's maintenance schedule i.e. changing of timely diesel filters, calibration of Fuel pump, overhauling of engines etc. No vehicle without valid PUC is allowed inside the plant and mines area. The vehicles engaged in transportation of minerals outside the core zone are provided with tarpaulin and no overloading is allowed.
23	Digital processing of the entire lease area using remote sensing technique should be done regularly once in three years for monitoring land use pattern and report submitted to Ministry of Environment and Forests and its Regional Office, Bhopal	Complying with. The Digital processing is being carried out once in every three years. Digital processing report of entire lease area using remote sensing technique is being done and copy of same has been submitted to MoEFandCC and its Regional office. Copy is enclosed as Annexure 16.
24	A Final Mine Closure Plan along with details of Corpus Fund should be submitted to the Ministry of Environmentand Forests 5 years in advance of final mine closure, for approval.	The details of the Final Mine Closure Plan along with details of Corpus Fund shall be submitted to the Ministry of Environment and Forests as desired. Rule No 24(1) of MCDR 2017, which deals with final mine closure plan, mandates the Lessee to get the final mine closure plan approved from Indian Bureau of Mines 2 years in advance of the final mine closure. We as PP will adhere to the requirement of the said Rule.
25	The company shall comply with all the commitments made during public hearing on 22 nd May, 2008.	Adhering to the given condition we will strictly Comply with all the commitments made during public hearing on 22 nd May, 2008. The public hearing comments are enclosed as Annexure 17 .
		The Company is fully committed in implementing all the commitments. Playgrounds are being developed in all nearby villages. Toilets roads etc. are being constructed. Significant work has been carried out in health care infrastructure development Education, vocational training, etc. few photographs in respect of the compliances undertaken are being attached.
	B. Gene	eral Condition:
1	The project authority shall adhere to the stipulations made by State Pollution Control Board (SPCB) and State Government.	Cement plant and all the mining operation are carried out with validconsent under air and water act issued by SPCB. The copy of consent is enclosed as Annexure-18 .
2	No further expansion or modification of the plant shall be carried out without prior approval of this Ministry	stipulated annual limits stipulated by MOEFCC, further expansion or modification will be carried only after obtaining the permission from Ministry.
3	At least four ambient air quality monitoring stations shall be established in the down wind direction as well as where maximum ground level concentration of SPM, SO2 and NOx are anticipated in consultation with the SPCB	We have established 05 nos. of AAQ monitoring stations in and around the plant and mines as mentioned in condition number 03 under specific condition for monitoring of ambient air quality of the area. Ambient air quality and stack emission is regularly monitored and reports are submitted to the MoEF / SPCB and CPCB. Ambient air Quality reports

are enclosed as Annexure-4 Stack emission reports are enclosed as Annexure-1. Data on ambient air quality and stack Complying with. emissions shall be regularly submitted to Data on ambient air quality and stack emissions are being this Ministry including its Regional Office regularly submitted to state PCB. Latest copy attached in and SPCB /CPCB once in six months. Annexure 19. 4 No industrial wastewater is generated as the cement plant Industrial waste water shall be properly is operated on dry process. collected and treated so as to conform to the standards prescribed under GSR 422(E) For domestic wastewater, there is a sewage treatment plant dated 19thMay,1993 and with capacity of 600 KLD. 31stDecember,1993 or as amended from time to time. The treated waste water shall be utilized for plantation purpose. Contaminated water generated due to washing of equipment is passed though grease and oil trap tank having separation chambers and pumping arrangement. A state of the art ceramic membrane based automated Oil and Grease trapping unit with 5KLD capacity is installed for separation of oil and grease particles from water, prime mover has been provided. The oil and grease is skimmed and kept in sealed barrels for further disposal to authorized vendors. The strained out water left in the tank is stored in tanks, and is re-used for washing of HEMM. Detailed Report of treated effluent by NABL and MOEF accredited lab is attached. The analysis is done by M/s Vibrant Techno Lab Pvt. Ltd having NABL certificate no TC-11227 Dtd 20/12/2022 valid upto 19/12/2024 which has been renewed till 19/12/2028 and CPCB recognition Dtd. 16/12/2024.

		STP treated water analysis report is enclosed as Annexure 8. Mines workshop treated water Analysis Report is enclosed
		as Annexure 20.
5	The overall noise levels in and around the plant area shall be kept well within the standards [85 dB(A)] by providing noise control measures including acoustic hoods, silencers, enclosures etc. on all sources of noise generation.	The overall noise level is within threshold limit of 85 dB(A). To arrest the noise levels all equipment are equipped with acoustic hoods, silencer, enclosures etc. besides that operators have been provided with PPE. Green belt is developed along the plant and mining area to minimize the noise pollution.
	The ambient noise levels shall conform to the standards prescribed under Environmental (Protection) Act,1986 Rules,1989 viz. 75 dB(A) (day time) and 70 dP(A) (night time)	Ambient Noise levels are maintained well within the prescribed norms under Environmental (Protection) Act, 1986 Rules, 1989. Noise Monitoring report is enclosed as Annexure 5 .
	dB(A) (night time). Proper housekeeping and adequate occupational health programs shall be taken up. Occupational Health Surveillance programme shall be done on a regular basis and records for at least30-40	We have already conducted various health surveillance programs whose records are maintained properly. Also sufficient preventive measures are adopted during the plant and mining operation to avoid direct exposure to dust etc.
	years. The programme shall include lung function and sputum analysis maintained properly tests once in six months. Sufficient preventive measures shall be adopted to avoid direct exposure to dust etc	 Occupational Health Survey (OHS) a) Periodical Medical Examinations are conducted of each employee by outside specialists once in every 5 years. Under this scheme each employee undergoes Pathological tests, blood group test, chest X-Rays, Audiometry tests, eye test etc. once every 5 years. Proper records of such tests are maintained. Nota single case of any occupational disease has so far been detected in our mines/plant. – Sample medical examination note is displayed. b) Welfare Amenities: A well-equipped Dispensary has been provided with

			of Ambulance, Patholog	ical Laboratoryand X-
		Ray, and	Audiometry etc.	
		0.110		•
		OHC report	s are enclosed as Annex u	ıre 21.
8	The company shall undertake eco-		grams per training to e	
	development measures including	•	velfare has been taken	1 7
	community welfare measures in the project		ial, educational, healthc	
	area.		we been taken by the com	
		Annexure 22	R Activities of year 2024	-25 are enclosed as
9	The project proponent shall also comply		ctly adhering with the ex	nvironment protection
	with all the environmental protection		s stipulated in approved	
	measures and safeguards recommended in the EIA/EMP.		d measures of EMP are n	
	the ELFA EIVII.		Check List of EMP co	mpliance
			AIR QUALITY MANA	
			e/Bag filters, ESP have	been installed in the
			rest the dust emissions.	OTT 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
		_	are the details of APC	CE installed with its
		respective u	Location	Name of APCE
		1	Raw Mill / Kiln	RABH
		2	Coal Mill	Bag House
		3	Cement Mill 1	Bag House
		4	Cement Mill 2	Bag House
		5	Clinker Cooler	ESP
			the dust emissions 121	
			with the transfer points	•
		the plant.	1	1
		✓ Dry fly a	sh is pneumatically un	loaded in completely
			nner and stored into fly	ash silo from closed
			ntaining fly ash	
			ransportation is also done	e in completely closed
		manner.	1 1 1,	. 1.1 6 12 1 .
			ernal roads are paved to c	
			due to vehicular moven transportation is done	
			Belt conveyors are cov	
			ist generation.	ered to minguie the
			other raw materials are st	ored in covered sheds
			nkling is done at crusher	
		conveyor	from crusher to stacker	
			nsfer points are connecte	
			nkling is being done on l	
			through dedicated water	
			ng is practiced to control	
			face with dozer before be is done by coarse mater	
		emission.	is done by coarse mater	man to avoid mile dust
			le delayed blasting is ad	onted
			ay is done while load	
			and also water sprinkling	
		dump hop		o
			loading of vehicles use	d in transportation of
<u> </u>		- Opullium	Todding of venicles use	a in nansportation of

- limestone from quarry to crusher.
- ✓ Water sprinkling on haul road.
- ✓ Vehicles having valid PUC certificate are only allowed to ply inside mines premises.
- ✓ Water spray system has been installed at crusher dump hopper.
- ✓ Bag filters of 50000 M3 capacity have been installed at both the crushers.
- ✓ Dense canopy plantation is in practice.
- ✓ Around 41766 saplings have been commonly planted during 2024-25 in all the plant colony and mines including CSR of the company.

NOISE and GROUND VIBRATION MANAGEMENT:

- ✓ Regular maintenance and lubrication of machinerie.
- ✓ Personnel engaged in heavy noise area are equipped with all required PPEs.
- ✓ Ambient noise level is regularly monitored.

WATER MANAGEMENT:

- ✓ Water reservoir of capacity 13 Lac M³ has been made in mines area. Rain water collected into other abandoned mines pit and working mines is pumped into main water reservoir. This reservoir serves as main recharge source for the area.
- ✓ Rain water is channelized to a Settling Tank to eliminate silting of water body.
- ✓ Surface water quality in mines area is monitored and the report is submitted regularly.
- ✓ Ground water level and quality of plant and mines area are monitored and the report is submitted regularly.
- ✓ Rain water accumulated in mine pits is used for plant operation, to reduce the ground water consumption.
- ✓ No process waste is generated from plant and mines. For treatment of domestic waste water of colony a Sewage treatment plant of 600 KLD capacity is established. Treated waste water of STP is utilized for gardening purpose.
- ✓ Contaminated water generated due to washing of equipment is passed though grease and oil trap tank having separation chambers and pumping arrangement. For separation of oil and grease particles from water, prime mover has been provided. The oil and grease is skimmed and kept in sealed barrels for further disposal to authorized vendors.

SOLID WASTE MANAGEMENT:

- ✓ Soil and waste rock generated from mines is stacked separately at earmarked sites and used for back filling and rehabilitation of back filled area.
- ✓ Biomass generated from dressing of lawns and trimming of plants inside plant and mines is burnt in kiln after its is dried.
- ✓ Plastic waste (as wrapping material, discarded tarpaulin etc and collected from municipal area) having high calorific values is also burnt in kiln
- ✓ Solid waste generated in plant is collected at designated locations and disposed of scientifically.

ENT plant is covered to the above, ning lease areas plan.
nent related to agement action e qualifications o environment is enclosed as
:
l cost and the protection are a carmarked for EL.
officer(s) of the requisite data/
onitored data is finistry / CPCB was submitted 30.11.2024. a are submitted
equisite data/ onitored data is linistry / CPCB was submitted 30.11.2024.
ponitored data is linistry / CPCB was submitted 30.11.2024. In are submitted the U-II
ponitored data is finistry / CPCB was submitted 30.11.2024. The are submitted by U-ll Date
requisite data/ ponitored data is linistry / CPCB was submitted 30.11.2024. a are submitted b U-ll Date 29.12.2011
onitored data is linistry / CPCB was submitted 30.11.2024. In a are submitted Date 29.12.2011 16.07.2012
ponitored data is dinistry / CPCB was submitted 30.11.2024. In are submitted Date 29.12.2011 16.07.2012 08.01.2013
ponitored data is linistry / CPCB was submitted 30.11.2024. In a are submitted Date 29.12.2011 16.07.2012 08.01.2013 16.05.2013
requisite data/ ponitored data is finistry / CPCB was submitted 30.11.2024. The are submitted by the U-II Date 29.12.2011 16.07.2012 08.01.2013 16.05.2013 04.01.2014 14.07.2014 17.03.2015
requisite data/ ponitored data is linistry / CPCB was submitted 30.11.2024. The are submitted by the U-II pate 29.12.2011 16.07.2012 08.01.2013 16.05.2013 04.01.2014 14.07.2014 17.03.2015 02.09.2015
requisite data/ ponitored data is finistry / CPCB was submitted 30.11.2024. The are submitted by the U-II Date 29.12.2011 16.07.2012 08.01.2013 16.05.2013 04.01.2014 14.07.2014 17.03.2015
1 1 1 1 1 1 1

2017

PCL/ENV/2017/26

PCL/ENV/2017/67

PCL/ENV/2017/67

07.03.2017

14.08.2017

10.03.2018

		2018	PCL/ENV/2018/52	27.08.2018			
			PCL/ENV/2019/100	14.01.2019			
		2019	PCL/ENV/2019	15.06.2019			
			PCL/ENV/2019/186	02.12.2019			
		2020	PCL/ENV/2020/230	01.06.2020			
			PCL/ENV/2020/292	01.12.2020			
		2021	PJL/ENV/2021/360	01.06.2021			
			PJL/ENV/2021/426	01.12.2021			
		2022	PJL/ENV/2022/505	01.06.2022			
		2022	PJL/ENV/2022/576	01.12.2022			
		2023	PJL/ENV/2023/666	01.06.2023			
		2023	PJL/ENV/2023/746	01.12.2023			
		2024	PJL/ENV/2024/809	16.05.2024			
		2024	PJL/ENV/2024/888	30.11.2024			
13	The Project Authorities shall inform the		of the intimation of the finance	cial closure Of the			
	Regional Office as well as the Ministry, the date of financial closure and final approval	project is	enclosed as Annexure-25 .				
	of the project by the concerned authorities						
	and the date of commencing the land						
	development work.						
14	No change in mining technology and scope of working shall be made without	Agreed. There will not be any change in the calendar plan includi					
	prior approval of the Ministry of		n, quantum of limestone and wa				
	Environment and Forests.		oneuvation, quantum or minescone and waste shair or made.				
	No change in the calendar plan including						
	excavation, quantum of limestone and waste shall be made.						
15	Measures should be taken for control of	\mathcal{E}					
	noise levels below 85dB (A) in the work environment. Workers engaged in operations of HEMM etc. should be		Workers and employees are provided with earmuffs and				
	provided with ear plugs/muffs.	necessary	FFLS.				
16	Industrial waste water (workshop and waste	No indust	rial wastewater is generated as	the cement plant			
	water from the mine) should be properly		d on dry process.	4 4 1 4			
	collected, treated so as to conform to the standards prescribed under GSR 422		stic wastewater, there is a sewage te-of -art technology. It has the				
	(E)dated 19thMay, 1993 and 31st		wastewater of 600 KLPD.	capacity to acut			
	December 1993 or as amended from time to						
	time. Oil and grease trap should be installed before discharge of workshop effluents.						
	before discharge of workshop efficients.	chambers and pumping arrangement. For separation of oil and grease particles from water, prime mover has been					
		provided.	and kept in sealed				
17			r further disposal to authorized v				
17	Personnel working in dusty areas should wear protective respiratory devices and			been provided to			
	they should also be provided with		ry devices have been used by th	e persons working			
	adequate training and information on	in dusty a	reas.				
	observe any contractions due to exposure		f job they are engaged in.	T			
safety and health aspects. Occupational health surveillance program of the workers should be undertaken periodically to		Personal j workers a information	protective equipment's are being nd they are given adequate train on regarding safety and health a	ning and			

to dust and take corrective measures, if needed.

The list of PPEs issued from Oct24 – Mar25 is given below:

Total PPE's issued in Plant dusty area			
Material	Qty.	Amount in Rs.	
COTTON DUST MASK,			
VENUS 410.	8252	119654	
GOGGLE SAFETY WHITE			
GLASS PVC, .	1549	46472	
HAND GLOVE - LEATHER			
and CANVAS 14".	704	24640	
HAND GLOVE - LEATHER			
and CANVAS 18".	1100	45100	
HAND GLOVES 14" FOR			
WELDER/GAS CUTTER .	66	16864	
HAND GLOVES 14"-HEAT			
RESISTANT UPTO400°C .	4	1980	
HAND GLOVES COTTON			
14,DOUBLE SIDE DOTTED .	1492	20142	
NITRILE COATED GLOVES			
NBR/721 WG-FT.	5821	195151	
PLUG EAR MAKEBIRLA -3M			
	5	40	
SAFETY HELMET BLUE			
COLOUR,KARAM/ UDYOGI .	26	3666	
SAFETY HELMET ORANGE			
(SHELMET BRAND) .	13	1441	
SAFETY HELMET WHITE,			
KARAM / UDYOGI .	10	1930	
SHOE BLACK LEATHER .	433	345381	
Grand Total		822461	

Total PPE's issued in Mines area From Jan'2024 – DEC'2024			
Material	Qty.	Amount in Rs.	
Dust Mask	175	2665.25	
Goggle Safety Glass PVC,	65	3303.95	
Hand Gloves	165	5643	
Helmet Industrial Safety	60	6900	
Jacket fluorescent High Visibility Wear	195	24765	
Plug Ear muff	275	2200	
Safety Shoes	350	356300	
TOTAL		401777.20	

Adequate training on safety and health awareness has been given by experts at VT center. Details of Vocational Training; VT are given below:

Training programme executed during Oct'24 – Mar'25

PARTICULARS	Nos of Participants	Grade
Electrical Safety	59	Staff-24 Worker-30and apprentice -05

		1 1		1
		Environment and its Pollution Control	14	Staff -13 apprentice-01
		First Aid (Classroom)	51	Staff-16 and Worker-30and apprentice -05
		Fire Fighting	69	Staff-14andWorker-50and apprentice-05
		Safe practice and use of explosive in mines by external AUDITOR (shri GK PRADHAN)	34	Staff-11andWorker-10and apprentice-04 and Contractor- 09
		Drilling and blasting	16	Staff-04andWorker-12
		Road safety week and defensive driving	26	Staff-12 and Worker-12and apprentice -02
		Mines Vocational Training	102	Staff-10andWorker-28 andcontractor-59and apprentice- 05
		Survey knowledge and mine plans	26	Staff -25 and apprentice-01
		HEMM operator safe loading and unloading training	11	Staff -11
		Quality control and Raw mix	16	Staff -15 and apprentice-01
		HIRA (HAZARD IDENTIFICATION AND RISK ASSESSMENT)	8	Staff -05and apprentice 03
		Mine plans and Review	32	Staff -32
		Total Participant		464
		the safety of me departmental talks ar	re made to n and m nd instruction g is also o	educate the workers about nachines through regular ons, vocational training etc. rganized on every first day
		Periodical Medical employee by outsid Under this scheme e tests, blood group test est etc. once every 5 maintained. Not a si	Examination Examination Examination III Section Examination Examin	ons are conducted of each sts once in every 5 years. yee undergoes Pathological Rays, Audiometry tests, eye per records of such tests are of any occupational disease
18	The project authorities shall inform to the Regional Office located regarding date of financial closures and final approval of the project by the concerned authorities and the date of start of land development work.	closure of the proje	ce was in ect. The co	formed regarding financial opy of the intimation of the is enclosed as Annexure-25 .
19	A copy of clearance letter will be marked to concerned Panchayat / local NGO, if any, from whom suggestion / representation, if any, was received while processing the proposal.	Complied.		

20	State pollution control board should	
	display a copy of the clearance letter at the	
	Regional Office, District Industry Centre	
	andCollector's office/ Tehsildar's office	
	for 30 days.	
21	The project authorities shall advertise at	Complied.
	least in two local newspapers widely	The advertisement regarding issuance of Environment
	circulated, one of which shall be in the	clearance and the copy of same is available at State Pollution
	vernacular language of the locality	Control Board and also at web site of the Ministry of
	concerned, within 7 days of the issue of the	Environment and Forests at "http://envfor.nic.in" was given
	clearance letter informing that the project	in two newspapers i.e. Nav swadesh and Desh Bandhu on
	has been accorded environmental clearance	25.09.2008.
	and a copy of the clearance letter is	
	available with the State Pollution Control	Copy of advertisement is enclosed as Annexure 26.
	Board and also at web site of the Ministry	
	of Environment and Forests at	
	"http://envfor.nic.in" and a copy of the	
	same shall be forwarded to the	
	Regional Office of this Ministry.	





Name & Address of Party:

Sample Collected

VTL/S/01

M/s PRISM JOHNSON LIMITED Village- Mankahari, Tehsil- Rampur

Baghelan, Dist.-Satna (M.P.)

Report No.: Format No.: VTL/S/2501250001

7.8 F-03

Party Reference No.:

NIL

Report Date:

30/01/2025

Period of Analysis:

25/01/2025-30/01/2025

Receipt Date: 25/01/2025

Sample Description:

STACK EMISSION MONITORING

VTL Team

Date & Time of Sampling 18/01/2025

Location Cement Mill -II (Unit-II) Stack Attach To **Bag Filter**

Sampling duration (Minutes) 57 Min. (10:00 to 10:57 Hrs.)

Make Of Stack MS

Stack Diameter 0.96 M. Stack Height 36.0 M.

Instrument calibration status Calibrated Clear Sky Meteorological Condition status Ambient Temperature - Ta (°C) 19 Temperature of Stack Gases - Ts (°C) 108

Velocity of Stack Gases (m/sec.) 8.38 Flow rate of PM (LPM) 28 Sampling condition Isokinetic

Flow rate of Flue Gas 18.34 (Nm3/sec) Moisture

7.21 % Cross Sectional Area of Stack 0.72 (M2)

Method of Sampling IS-11255 & EPA

RESULTS

S. No.	Parameter	Test Method	Results	Units	Limits
1.	Particulate Matter (PM)	IS: 11255 (P-1) : 1985,RA 2019	18.15	mg/Nm3	30

End of the Report-----





RK Yadav Lab Incharge Authorized Signatory

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





TC-11227

Sample Number:

Name & Address of Party:

VTL/S/02

M/s PRISM JOHNSON LIMITED Village- Mankahari, Tehsil- Rampur

Baghelan, Dist.-Satna (M.P.)

Report No.:

VTL/S/2501250002

Format No.: Party Reference No.:

NIL

Report Date:

30/01/2025

7.8 F-03

Period of Analysis:

25/01/2025-30/01/2025

Receipt Date:

25/01/2025

Sample Description:

STACK EMISSION MONITORING

Sample Collected

Date & Time of Sampling

Location

Stack Attach To

Sampling duration (Minutes)

Make Of Stack

Stack Diameter Stack Height

Instrument calibration status Meteorological Condition status

Ambient Temperature - Ta (°C) Temperature of Stack Gases - Ts (°C) Velocity of Stack Gases (m/sec.)

Flow rate of PM (LPM) Sampling condition

Flow rate of Flue Gas Moisture

Cross Sectional Area of Stack

Method of Sampling

VTL Team

18/01/2025

Cement Mill -I (Unit-II)

Bag Filter

54 Min. (11:00 to 11:54 Hrs.)

MS

1.0 M.

49.0 M.

Calibrated Clear Sky

20 99

8.66

30

Isokinetic

5.85 (Nm3/sec)

7.46%

0.785 (M2)

IS-11255 & EPA

RESULTS

S. No.	Parameter	Test Method	Results	Units	Limits
1.	Particulate Matter (PM)	IS: 11255 (P-1) : 1985,RA 2019	17.33	mg/Nm3	30



RK Yadav Lab Incharge Authorized Signatory

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





Sample Number:

Name & Address of Party:

VTL/S/03

M/s PRISM JOHNSON LIMITED Village- Mankahari, Tehsil- Rampur

Baghelan, Dist.-Satna (M.P.)

Report No.: Format No.: VTL/S/2501250003

7.8 F-03

NIL

30/01/2025

25/01/2025-30/01/2025

Receipt Date:

Report Date:

Party Reference No.:

Period of Analysis:

25/01/2025

Sample Description:

STACK EMISSION MONITORING

Sample Collected Date & Time of Sampling

Location

Stack Attach To

Sampling duration (Minutes)

Make Of Stack

Stack Diameter

Stack Height Instrument calibration status

Meteorological Condition status Ambient Temperature - Ta (°C)

Temperature of Stack Gases - Ts (°C) Velocity of Stack Gases (m/sec.)

Flow rate of PM (LPM)

Sampling condition Flow rate of Flue Gas

Moisture

Cross Sectional Area of Stack

Method of Sampling

VTL Team

18/01/2025

Coal Mill (Unit-II)

Bag Filter

51 Min. (12:00 to 12:51 Hrs.)

2.24 M.

65.0 M.

Calibrated

Clear Sky

19 76

8.67

32

Isokinetic

37.558 (Nm3/sec)

5.65 %

3.94 (M2)

IS-11255 & EPA

RESULTS

S. No.	Parameter	Test Method	Results	Units	Limits
1.	Particulate Matter (PM)	IS: 11255 (P-1) : 1985,RA 2019	18.04	mg/Nm3	30

End of the Report--



RK Yadav Lab Incharge Authorized Signatory

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





TC-11227

Sample Number:

Name & Address of Party:

VTL/S/04

M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur

Baghelan, Dist.-Satna (M.P.)

Report No.: Format No.:

Party Reference No.:

VTL/S/2501250004

7.8 F-03

NIL

30/01/2025 25/01/2025-30/01/2025

Sample Description:

STACK EMISSION MONITORING

Report Date: Period of Analysis: Receipt Date:

25/01/2025

Sample Collected Date & Time of Sampling

Location

Stack Attach To

Sampling duration (Minutes)

Make Of Stack

Stack Diameter Stack Height

Instrument calibration status **Meteorological Condition status**

Ambient Temperature - Ta (°C) Temperature of Stack Gases - Ts (°C) Velocity of Stack Gases (m/sec.)

Flow rate of PM (LPM) Sampling condition Flow rate of Flue Gas

Moisture

Cross Sectional Area of Stack

Method of Sampling

VTL Team

19/01/2025

Cooler (Unit-II)

42 Min. (10:00 to 10:42 Hrs.)

MS

4.50 M.

50.0 M.

Calibrated Clear Sky

20

141 12.53

39

Isokinetic

117.61 (Nm3/sec)

6.16 %

15.89 (M2) IS-11255 & EPA

RESULTS

S. No.	Parameter	Test Method	Results	Units	Limits
1.	Particulate Matter (PM)	IS: 11255 (P-1) : 1985,RA 2019	15.33	mg/Nm3	30

End of the Report----



RK Yadav Lab Incharge **Authorized Signatory**

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified







Name & Address of Party:

VTL/S/05

M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur

Baghelan, Dist.-Satna (M.P.)

Report No.: Format No.:

Report Date:

VTL/S/2501250005

7.8 F-03

NIL

30/01/2025

Sample Description:

STACK EMISSION MONITORING

Period of Analysis: Receipt Date:

Party Reference No.:

25/01/2025-30/01/2025

25/01/2025

Sample Collected

Date & Time of Sampling

Location

Stack Attach To

Sampling duration (Minutes)

Make Of Stack

Stack Diameter Stack Height

Instrument calibration status Meteorological Condition status

Ambient Temperature - Ta (°C) Temperature of Stack Gases - Ts (°C) Velocity of Stack Gases (m/sec.)

Flow rate of PM (LPM)

Sampling condition Flow rate of Flue Gas

Moisture

Cross Sectional Area of Stack

Method of Sampling .

VTL Team

19/01/2025

Raw Mill & Kiln Stack Unit-II

Bag Filter

45 Min. (11:00 to 11:45 Hrs.)

MS .

4.75 M.

110.0 M.

Calibrated Clear Sky

21

101

10.53

36

Isokinetic

216.536 (Nm3/sec)

5.12 %

17.71 (M2)

IS-11255 & EPA

RESULTS

S. No.	Parameter	Test Method	Results	Units	Limits
1.	Particulate Matter (PM)	IS: 11255 (P-1) : 1985,RA 2019	19.23	mg/Nm3	30
2.	Sulphur Dioxide (SO2)	IS: 11255 (P-2) : 1985,RA 2019	15.92	mg/Nm3	700
3.	Oxide of Nitrogen (NO2)	IS: 11255 (P-7) : RA 2017	565.0	mg/Nm3	800

--End of the Report-----





RK Yadav Lab Incharge Authorized Signatory

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified


Display Board







AAQMS Panel



Desktop showing monitoring data



AAQMS Station



Continuous Emission Monitoring System Panel



LED Display of emission parameters at Main Gate of premises



Continuous Air Quality Monitoring Station



Continuous Stack Emission Monitoring Station





Sample Number: VTL/FD/01

Name & Address of the Party

M/s PRISM JOHNSON LIMITED

Report No.

: VTL/FD/2501250001/A

- 7.8 F-02 Format No Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No

: NIL

Satna (M.P.)

Report Date

: 30/01/2025

Period of Analysis Receipt Date

: 25/01/2025-30/01/2025 : 25/01/2025

Sample Description

: Fugitive Dust Emission Monitoring

General Information :-

Sampling Location

: Near Lime stone Handling (Raw Material Handling)

Sample Collected By Sampling Equipment used

VTL Team

HVS VTL/HVS/01

Instrument Code Coordinates

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

: 18/01/2025

Time of Monitoring

: 10:00 to 18:00 Hrs.

Ambient Temperature (°C)

Min 16°C Max 25°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

Lab STP: VTL/STP/02

Sampling Duration

: 8 Hrs.

Parameter Required

: As per Work Order

S.No.	Parameters	Test Methods	Results	Units
1	Suspended Particulate Matter (as SPM)	VTL/STP/02/STP/01	1290.0	µg/m3

"End of Report"





RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

9 SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





Sample Number : VTL/FD/02

Name & Address of the Party :

M/s PRISM JOHNSON LIMITED

Report No.

: VTL/FD/2501250002/A

Format No : 7.8 F-02

Satna (M.P.)

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL : 30/01/2025

Report Date

: 25/01/2025-30/01/2025

Period of Analysis Receipt Date

: 25/01/2025

Sample Description

: Fugitive Dust Emission Monitoring

General Information :-

Sampling Location

: Near Coal Yard

Sample Collected By

VTL Team

Sampling Equipment used

HVS

Instrument Code

VTL/HVS/02

Coordinates

Meteorological condition during monitoring

: Clear Sky

Date of Monitoring

: 18/01/2025

Time of Monitoring

: 10:30 to 18:30 Hrs.

Ambient Temperature (°C)

: Min 17°C Max 25°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

: Lab STP: VTL/STP/02

Sampling Duration

: 8 Hrs.

Parameter Required

: As per Work Order

S.No.	Parameters	Test Methods	Results	Units
1	Suspended Particulate Matter (as SPM)	VTL/STP/02/STP/01	1470.0	µg/m3

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601









Sample Number: VTL/FD/03

Name & Address of the Party

Report No.

: VTL/FD/2501250003/A

M/s PRISM JOHNSON LIMITED

Format No

· 7.8 F-02

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL Satna (M.P.)

Report Date

: 30/01/2025

Period of Analysis

: 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: Fugitive Dust Emission Monitoring

General Information :-

Sampling Location

: Near Packing Plant Unit-I

Sample Collected By

VTL Team

Sampling Equipment used

HVS

Instrument Code

VTL/HVS/01

Coordinates

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

: 19/01/2025

Time of Monitoring

: 10:00 to 18:00 Hrs.

Ambient Temperature (°C)

Min 13°C Max 19°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

Lab STP: VTL/STP/02

Sampling Duration

: 8 Hrs.

Parameter Required

: As per Work Order

S.No.	Parameters	Test Methods	Results	Units
1	Suspended Particulate Matter (as SPM)	VTL/STP/02/STP/01	810.0	μg/m3

End of Report





RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





Sample Number: VTL/FD/04

Name & Address of the Party

Report No.

: VTL/FD/2501250004/A

M/s PRISM JOHNSON LIMITED

Format No Party Reference No : NIL

- 7.8 F-02

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

Report Date

: 30/01/2025

Period of Analysis : 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: Fugitive Dust Emission Monitoring

General Information :-

Sampling Location

: Near Packing Plant Unit-II

Sample Collected By

VTL Team **HVS**

Sampling Equipment used Instrument Code

VTL/HVS/02

Coordinates

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

: 19/01/2025

Time of Monitoring

10:30 to 18:30 Hrs.

Ambient Temperature (°C)

: Min 14°C Max 19°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

: Lab STP: VTL/STP/02

Sampling Duration

: 8 Hrs.

Parameter Required

: As per Work Order

S.No.	Parameters	Test Methods	Results	Units
1	Suspended Particulate Matter (as SPM)	VTL/STP/02/STP/01	785.0	μg/m3

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





Sample Number : VTL/FD/05

Name & Address of the Party :

M/s PRISM JOHNSON LIMITED

Report No.

: VTL/FD/2501250005/A

: 7.8 F-02 Format No Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL

Period of Analysis

: 30/01/2025

Satna (M.P.)

Report Date

: 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: Fugitive Dust Emission Monitoring

General Information :-

Sampling Location

: Near Cement Mill Unit-I

Sample Collected By

VTL Team

Sampling Equipment used

HVS

Instrument Code

VTL/HVS/01

Coordinates

Meteorological condition during monitoring

: Clear Sky

Date of Monitoring

: 20/01/2025

Time of Monitoring

: 10:00 to 18:00 Hrs.

Ambient Temperature (°C)

: Min 17°C Max 24°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

Lab STP: VTL/STP/02

Sampling Duration

: 8 Hrs.

Parameter Required

: As per Work Order

S.No.	Parameters	Test Methods	Results	Units	
1	Suspended Particulate Matter (as SPM)	VTL/STP/02/STP/01	967.0	µg/m3	

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





Sample Number : VTL/FD/06

Name & Address of the Party

M/s PRISM JOHNSON LIMITED

Report No.

: VTL/FD/2501250006/A

7.8 F-02 Format No Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No

: NIL

Satna (M.P.)

Report Date

: 30/01/2025

Period of Analysis

: 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: Fugitive Dust Emission Monitoring

General Information :-

Sampling Location

: Near Cement Mill Unit-II

Sample Collected By

VTL Team

Sampling Equipment used Instrument Code

HVS VTL/HVS/01

Coordinates

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

21/01/2025

Time of Monitoring

: 10:00 to 18:00 Hrs.

Ambient Temperature (°C)

Surrounding Activity

Min 21°C Max 29°C

Human, Vehicular & Plant Activities Lab STP: VTL/STP/02

Method of Sampling Sampling Duration

: 8 Hrs.

Parameter Required

: As per Work Order

S.No.	Parameters	Test Methods	Results	Units
1	Suspended Particulate Matter (as SPM)	VTL/STP/02/STP/01	1035.0	µg/m3

End of Report*





RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





National Accreditation Board for **Testing and Calibration Laboratories**

CERTIFICATE OF ACCREDITATION

VIBRANT TECHNO LAB PRIVATE LIMITED

has been assessed and accredited in accordance with the standard

ISO/IEC 17025:2017

"General Requirements for the Competence of Testing & Calibration Laboratories"

for its facilities at

PLOT NO.SC-40, 3RD FLOOR, NARAYAN VIHAR S, AJMER RAOD, JAIPUR, RAJASTHAN, INDIA

in the field of

TESTING

Certificate Number:

TC-11227

Issue Date:

20/12/2024

Valid Until:

19/12/2028

This certificate remains valid for the Scope of Accreditation as specified in the annexure subject to continued satisfactory compliance to the above standard & the relevant requirements of NABL. (To see the scope of accreditation of thislaboratory, you may also visit NABL website www.nabl-india.org)

Name of Legal Entity: VIBRANT TECHNO LAB PRIVATE LIMITED

Signed for and on behalf of NABL



N. Venkateswaran **Chief Executive Officer**



Electrostatic precipitator



Reverse air bag house



Truck mounted vacuum cleaner



Road sweeping machine



Fog Cannon machine at different plant location









Tree Cover in Plant





Sample Number: VTL/AA/01

: M/s PRISM JOHNSON LIMITED

Report No.

: VTL/A/2501250001/A

Name & Address of the Party

- 7.8 F-02 Format No

Satna (M.P.)

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL : 30/01/2025

Report Date

Period of Analysis

: 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: AMBIENT AIR QUALITY MONITORING

General Information:-

Sampling Location

Near Guest House

Sample Collected By

VTL Team

Instrument Code

VTL/RDS/FPS/01

Coordinates

81.007674 & 24.5591

Meteorological condition during monitoring

: Clear Sky

Date of Monitoring

18/01/2025 To 19/01/2025

Time of Monitoring

: 09:00 to 09:00 Hrs.

Ambient Temperature (°C)

: Min.8°C Max 25°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

IS:5182

Sampling Duration Parameter Required

24 Hrs. : As per work order

S.No.	Parameters	Test Method	Results	Units	NAAQS 2009 (Limits)
1	Particulate Matter (as PM10)	IS:5182 (Part- 23)-2006 RA 2022	72.41	µg/m³	100
2	Particulate Matter (as PM2.5)	IS 5182(Part- 24): 2019	41.95	µg/m³	60
3	Nitrogen Dioxide (as NO2)	IS:5182 (P- 6)-2006, RA.2022	21.48	µg/m³	80
4	Sulphur Dioxide (as SO2)	IS 5182 (Part 2): Sec 1 : 2023	13.66	µg/m³	80
5	Carbon Monoxide (as CO)	IS:5182 (P- 10)-1999, RA. 2019 (NDIR)	0.72	mg/m³	4

*BLQ-Below Limit Of Quantification, **LOQ-Limit Of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signator



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

9 SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

3 0141-2954638

M bd@vibranttechnolab.com





Sample Number : VTL/AA/02 Report No.

: VTL/A/2501250002/A

Name & Address of the Party

: M/s PRISM JOHNSON LIMITED

: 7.8 F-02 Format No

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No

: NIL

Satna (M.P.)

Report Date : 30/01/2025

Period of Analysis

: 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: AMBIENT AIR QUALITY MONITORING

General Information:-

Sampling Location

Near Admin Building

Sample Collected By

VTL Team

Instrument Code

VTL/RDS/FPS/02

Coordinates

: 81.006746 & 24.566037

Meteorological condition during monitoring

: Clear Sky

Date of Monitoring

: 18/01/2025 To 19/01/2025

Time of Monitoring

: 09:15 to 09:15 Hrs.

Ambient Temperature (°C)

: Min.8°C Max 25°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

: IS:5182

Sampling Duration

24 Hrs.

Parameter Required

: As per work order

S.No.	Parameters	Test Method	Results	Units	NAAQS 2009 (Limits)
1	Particulate Matter (as PM10)	IS:5182 (Part- 23)-2006 RA 2022	66.89	µg/m³	100
2	Particulate Matter (as PM2.5)	IS 5182(Part- 24): 2019	39.25	μg/m³	60
3	Nitrogen Dioxide (as NO2)	IS:5182 (P- 6)-2006, RA.2022	22.87	µg/m³	80
4	Sulphur Dioxide (as SO2)	IS 5182 (Part 2): Sec 1 : 2023	8.97	μg/m³	80
5	Carbon Monoxide (as CO)	IS:5182 (P- 10)-1999, RA. 2019 (NDIR)	0.73	mg/m³	4

*BLQ-Below Limit Of Quantification, **LOQ-Limit Of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1





Sample Number:

Report No.

: VTL/A/2501250003/A

Name & Address of the Party

: M/s PRISM JOHNSON LIMITED

Format No

7.8 F-02

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL

Satna (M.P.)

Report Date

: 30/01/2025

Period of Analysis Receipt Date

: 25/01/2025-30/01/2025 : 25/01/2025

Sample Description

: AMBIENT AIR QUALITY MONITORING

General Information:-

Sampling Location Sample Collected By Near Stacker

Instrument Code

VTL Team VTL/RDS/FPS/03

Coordinates

81.001108 & 24.560603

Meteorological condition during monitoring

: Clear Sky

Date of Monitoring

18/01/2025 To 19/01/2025

Time of Monitoring

: 09:30 to 09:30 Hrs.

Ambient Temperature (°C)

: Min.8°C Max 25°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling Sampling Duration

IS:5182 24 Hrs.

Parameter Required

: As per work order

Parameters	Test Method	Results	Units	NAAQS 2009 (Limits)
Particulate Matter (as PM10)	IS:5182 (Part- 23)-2006 RA 2022	69.46	µg/m³	100
Particulate Matter (as PM2.5)	IS 5182(Part- 24): 2019	37.82	µg/m³	60
Nitrogen Dioxide (as NO2)	IS:5182 (P- 6)-2006, RA.2022	18.91	μg/m³	80
Sulphur Dioxide (as SO2)	IS 5182 (Part 2): Sec 1 : 2023	11.97	µg/m³	80
Carbon Monoxide (as CO)	IS:5182 (P- 10)-1999, RA. 2019 (NDIR)	0.64	mg/m³	4
	Particulate Matter (as PM10) Particulate Matter (as PM2.5) Nitrogen Dioxide (as NO2) Sulphur Dioxide (as SO2)	Particulate Matter (as PM10) IS:5182 (Part- 23)-2006 RA 2022 Particulate Matter (as PM2.5) IS 5182(Part- 24): 2019 Nitrogen Dioxide (as NO2) IS:5182 (P- 6)-2006, RA.2022 Sulphur Dioxide (as SO2) IS 5182 (Part 2): Sec 1 : 2023	Particulate Matter (as PM10) IS:5182 (Part- 23)-2006 RA 2022 69.46 Particulate Matter (as PM2.5) IS 5182(Part- 24): 2019 37.82 Nitrogen Dioxide (as NO2) IS:5182 (P-6)-2006, RA.2022 18.91 Sulphur Dioxide (as SO2) IS 5182 (Part 2): Sec 1 : 2023 11.97	Particulate Matter (as PM10) IS:5182 (Part- 23)-2006 RA 2022 69.46 μg/m³ Particulate Matter (as PM2.5) IS 5182(Part- 24): 2019 37.82 μg/m³ Nitrogen Dioxide (as NO2) IS:5182 (P- 6)-2006, RA.2022 18.91 μg/m³ Sulphur Dioxide (as SO2) IS 5182 (Part 2): Sec 1 : 2023 11.97 μg/m³

^{*}BLQ-Below Limit Of Quantification, **LOQ-Limit Of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signa



Page No. 1/1





Sample Number :

Report No.

: VTL/A/2501250004/A

Name & Address of the Party

M/s PRISM JOHNSON LIMITED

: 7.8 F-02 Format No Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No

Satna (M.P.)

: 30/01/2025

Report Date Period of Analysis

: 25/01/2025-30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: AMBIENT AIR QUALITY MONITORING

General Information:-

Sampling Location

Near Crusher Unit-II

Sample Collected By

: VTL Team

Instrument Code

: VTL/RDS/FPS/04

Coordinates

: 80.997380 & 24.561715

Meteorological condition during monitoring

: Clear Sky

Date of Monitoring

: 18/01/2025 To 19/01/2025

Time of Monitoring

: 09:45 to 09:45 Hrs.

Ambient Temperature (°C)

: Min.8°C Max 25°C

Surrounding Activity

: Human, Vehicular & Plant Activities

Method of Sampling

: IS:5182

Sampling Duration

: 24 Hrs.

Parameter Required

: As per work order

S.No.	Parameters	Test Method	Results	Units	NAAQS 2009 (Limits)
1	Particulate Matter (as PM10)	IS:5182 (Part- 23)-2006 RA 2022	84.56	µg/m³	100
2	Particulate Matter (as PM2.5)	IS 5182(Part- 24): 2019	47.24	µg/m³	60
3	Nitrogen Dioxide (as NO2)	IS:5182 (P- 6)-2006, RA.2022	25.37	µg/m³	80
4	Sulphur Dioxide (as SO2)	IS 5182 (Part 2): Sec 1 : 2023	14.23	µg/m³	80
5	Carbon Monoxide (as CO)	IS:5182 (P- 10)-1999, RA. 2019 (NDIR)	0.82	mg/m³	4

^{*}BLQ-Below Limit Of Quantification, **LOQ-Limit Of Quantification

End of Report







RK Yadav Lab Incharge **Authorized Signatory**



Page No. 1/1





Experience the unimagine Sample Number : VTL/AN/01

Report No.

: VTL/N/2501250001/A

Name & Address of the Party

: M/s PRISM JOHNSON LIMITED

Format No

· 7.8 F-04

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

Party Reference No : NIL

Report Date

: 30/01/2025

Receipt Date

: 25/01/2025

Sample Description Scope of Monitoring : Ambient Noise Level Monitoring

Sampling Duration

: 24 Hrs.

: Regulatory Requirment

Sample Collected

: VTL Team

Protocol Used

: IS 9989

Instrument

Calibrated

Instrument Used

: SLM

Calibration Status

General Information:-

Sampling Location

Near Guest House

Instrument Code

VTL/SLM/01

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

18/01/2025 To 19/01/2025

Time of Monitoring

06:00 to 06:00 Hrs.

Ambient Temperature (°C)

Min.8°C Max 25°C

Surrounding Activity

: Human, Vehicular & Other Activities

Parameter Required

: As per Work Order

Coordinates

S.No.	Test Parameters	Protocol	Test Res	sult dB(A)
			Day Time	Night Time
1	Noise Level (Leq)	IS 9989 - 1981 RA:2020	54.3	43.8

Ambient Noise Quality Standards as per Noise Pollution (Regulation and Control) Rules, 2000

Area Code	Category of Area/Zone	Limits i	n dB(A) Leq*
		Day Time	Night Time
A	Industrial area	75	70
В	Commercial area	65	55
С	Residential area	55	45
D	Silence Zone	50	40

^{1.} Day Time is from 6.00 AM to 10.00 PM.

Note: Mixed categories of areas be declared as one of the four above mentioned categories by the competent Authority and the corresponding standards shall apply

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



^{2.} Night Time is reckoned between 10.00 PM to 6.00 AM.

^{3.} Silence Zone is defined as an area up to 100 m around premises of Hospitals, Educational and Courts. Use of vehicle horn, Loudspeaker and bursting of crackers is banned in these zones.





Experience the unimagina Sample Number : VTL/AN/02

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

: VTL/N/2501250002/A

Format No Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Report No.

: 7.8 F-04

Satna (M.P.)

Party Reference No Report Date

: 30/01/2025

Receipt Date

: 25/01/2025

Sample Description

: Ambient Noise Level Monitoring

Sampling Duration

: 24 Hrs.

: NIL

Scope of Monitoring

: Regulatory Requirment

Sample Collected

: VTL Team

Protocol Used

: IS 9989

Instrument Used

: SLM

Instrument Calibration Status Calibrated

General Information:-

Sampling Location

Near Admin Building

Instrument Code

VTL/SLM/02

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

18/01/2025 To 19/01/2025

Time of Monitoring

06:00 to 06:00 Hrs.

Ambient Temperature (°C)

Surrounding Activity

Min.8°C Max 25°C Human, Vehicular & Other Activities

Parameter Required

: As per Work Order

Coordinates

S.No.	Test Parameters	Protocol	Test Re	sult dB(A)
			Day Time	Night Time
1	Noise Level (Leq)	IS 9989 - 1981 RA:2020	56.9	45.1

Ambient Noise Quality Standards as per Noise Pollution (Regulation and Control) Rules, 2000

Area Code	Category of Area/Zone	Limits	in dB(A) Leq*
		Day Time	Night Time
A	Industrial area	75	70
В	Commercial area	65	55
С	Residential area	55	45
D	Silence Zone	50	40

^{1.} Day Time is from 6.00 AM to 10.00 PM.

Note: Mixed categories of areas be declared as one of the four above mentioned categories by the competent Authority and the corresponding standards shall apply "End of Report"







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1



Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



2 0141-2954638



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

Vibrant Techno Lab Pvt. Ltd.

^{2.} Night Time is reckoned between 10.00 PM to 6.00 AM.

^{3.} Silence Zone is defined as an area up to 100 m around premises of Hospitals, Educational and Courts. Use of vehicle horn, Loudspeaker and bursting of crackers is banned in these zones.







Sample Number : VTL/AN/03

Report No.

: VTL/N/2501250003/A

Name & Address of the Party

: M/s PRISM JOHNSON LIMITED

Format No

: 7.8 F-04

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

Party Reference No · NIL Report Date

: 30/01/2025

Sample Description

: Ambient Noise Level Monitoring

Receipt Date

: 25/01/2025

Scope of Monitoring

: Regulatory Requirment

Sampling Duration

: 24 Hrs.

Protocol Used

Sample Collected

: VTL Team

: IS 9989

Instrument

Instrument Used

: SLM

Calibration Status

· Calibrated

General Information:-

Sampling Location

: Near Stacker

Instrument Code

: VTL/SLM/03

Meteorological condition during monitoring

Clear Sky

Date of Monitoring

: 18/01/2025 To 19/01/2025

Time of Monitoring

06:00 to 06:00 Hrs.

Ambient-Temperature (°C)

Min.8°C Max 25°C

Surrounding Activity

: Human, Vehicular & Other Activities

Parameter Required

: As per Work Order

Coordinates

S.No.	Test Parameters	Protocol	Test Result dB(A)	
	9		Day Time	Night Time
1	Noise Level (Leq)	IS 9989 - 1981 RA:2020	51.7	44.9

Ambient Noise Quality Standards as per Noise Pollution (Regulation and Control) Rules, 2000

Area Code	Category of Area/Zone	Limits	Limits in dB(A) Leq*		
		Day Time	Night Time		
A	Industrial area	75	70		
В	Commercial area	65	55		
С	Residential area	55	45		
D	Silence Zone	50	40		

^{1.} Day Time is from 6.00 AM to 10.00 PM.

these zones.

Note: Mixed categories of areas be declared as one of the four above mentioned categories by the competent Authority and the corresponding standards shall apply

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



3 0141-2954638

^{2.} Night Time is reckoned between 10.00 PM to 6.00 AM.

^{3.} Silence Zone is defined as an area up to 100 m around premises of Hospitals, Educational and Courts. Use of vehicle horn, Loudspeaker and bursting of crackers is banned in





Sample Number : VTL/AN/04

Report No.

: VTL/N/2501250004/A

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Format No

7.8 F-04

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

Party Reference No Report Date

: NIL

Receipt Date

: 30/01/2025 : 25/01/2025

Sample Description

: Ambient Noise Level Monitoring

Sampling Duration

: 24 Hrs.

Scope of Monitoring

: Regulatory Requirment

Sample Collected

: VTL Team

Protocol Used

: IS 9989

Instrument Used

Instrument

Calibrated

: SLM

Calibration Status

General Information:-

Sampling Location

Near Crusher Unit-II

Instrument Code

: VTL/SLM/04

Meteorological condition during monitoring

Date of Monitoring

: Clear Sky : 18/01/2025 To 19/01/2025

: 06:00 to 06:00 Hrs.

Time of Monitoring

: Min.8°C Max 25°C

Ambient Temperature (°C) Surrounding Activity

: Human, Vehicular & Other Activities

Parameter Required

: As per Work Order

Coordinates

S.No.	Test Parameters	Protocol	Test Result dB(A)	
			Day Time	Night Time
1	Noise Level (Leq)	IS 9989 - 1981 RA:2020	65.9	53.5

Ambient Noise Quality Standards as per Noise Pollution (Regulation and Control) Rules, 2000

Area Code	Category of Area/Zone	Limits i	Limits in dB(A) Leq*	
		Day Time	Night Time	
Α .	Industrial area	75	70	
В	Commercial area	65	55	
C	Residential area	55	45	
D	Silence Zone	50 40		

^{1.} Day Time is from 6.00 AM to 10.00 PM.

Note: Mixed categories of areas be declared as one of the four above mentioned categories by the competent Authority and the corresponding standards shall apply

End of Report*







RK Yadav Lab Incharge Authorized Signator



Page No. 1/1



^{2.} Night Time is reckoned between 10.00 PM to 6.00 AM.

^{3.}Silence Zone is defined as an area up to 100 m around premises of Hospitals, Educational and Courts. Use of vehicle horn, Loudspeaker and bursting of crackers is banned in



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No. Certificate No.	CC10512300 LES-CCL/FF/PM/		Cali. Fiel	d - Fluid Flow	Page No 1 of 2	
Calibration Date	03.08.2023	Suggest	ed Date of I	Next Calibration	02.08.2024	
Customer Name :- Address :-	Village - Mankah Tehsil - Rampur	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	26.08.202	
Date of DUC Receipt	03.08.2023 Calibration Performed At Site Condition of DUC					
Location of Performance	for Calibration	On Site	12000	William .		

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Fine Particulate Sampler	Thermo	TEI - 121	216 - TEF - 21	

02. Details of DUC

Name Dry Gas Meter Environmental Conditions During (alibration	
Make/Model	Honey well / BK - G1.6	Temperature (°C) :- 25 ± 10 °C	24.2	
SI.No.	1807079405	Relative Humidity (%) :- 45-75 %	54.2	
Cal. Range / Resolution	16.67 lpm (±2%) / 0.0002 m3	Barometric Pressure (mmHg)	744.20	

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
1	LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Lab, Mumbai
2	Digital Stop Watch	10 Sec 59 min	LES-CCL/R/14510	LES - CCL, Gr. Noida
SI.No.	Certificate No.	Calibr	Calibration Date Valid Up to	
1	PICAL/0922/F/032	05.09.2022		04.09.2023
2	LES-CCL/ET/SW/931	15.09.2022		14.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration. .Centre
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

Gr. Noida

Kasna





ULR No.	CC105123000000922F		PageNo 2 of 2
Calibration Date	03.08.2023	Suggested Date of Next Calibration	02.08.2024
Certificate No.	LES-CCL/FF/PM/SC/109		

05. Calibration Results for Flow of Dry Gas Meter

S.No.	Test meter (DUC) Measured Flow (Ipm)	Reference True Flow rate (Ipm)	Error (%)
1	16.58	16.324	1.568
2	16.59	16.313	1.698
3	16.58	16.360	1.345
4	16.63	16.340	1.775
5	16.62	16.320	1.838

Type A standard Uncertainty

for repeated data (1-5)

± 0.0081

lpm

Expanded uncertainty in Actual flow

measurement, U(k=2)

± 0.9018

lpm

2.43 % Rdg

* Kasna

Final Readings of Dry Gas Meter at the end of Calibration: 9.0884 m3 Note:-

Uncertainty Contributing factor:-

- 1. Repeatability (based on five measurement)
- 2.Uncertainty of master instruments
- 3.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place: Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasha creater toida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300	00000923F	Calibration. Field - Fluid Flow			Page No 1 of 2	
Certificate No.	LES-CCL/FF/RF/SC/419		Cambration. Field - Fidia Field			. age	
Calibration Date	Calibration Date 03.08.2023 Suggested Date of Next Calibration			02.08.2024			
Customer Name :- Address :-	M/s Prism Johns Village - Mankah Tehsil - Rampur Distt. Satna - 485	ari, P.O. Bathia, Baghelan,					
S.R.F. No.	2023/17	S.R.F. Date		22.06.2023	Issue D	ate	22.08.2023
Date of DUC Receipt	03.08.2023	Calibration Perform	med At	Site	Condition	of DUC	OK

01. DUC Fitted in instrument

Location of Performance for Calibration

Name	Make	Model	SI.No.
Fine Particulate Sampler	THERMO	TEI - 121	216 - TEF - 21

On Site

02. Details of DUC

Name	Rotameter	Environmental Conditions During Cali	bration
Resolution	1.0 lpm	Temperature (°C) :- 25 ± 10 °C	26.5
SI.No.	B21544	Relative Humidity (%) :- 45-75 %	56
Cal. Range	16.67 lpm (±2 %)	Barometric Pressure (mmHg)	738.80

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / IE).No.	Traceability
LFE GAS FLOW CALIBRATOR	0.5 -50 lpm	0416 / LES-CO	CL/R/4901	PI Calibration Laboratory, Mumbai
Certificate No.	Calibratio	n Date		Valid Up to
PICAL/0922/F/032	05.09.2	022		04.09.2023

04. Calibration Procedur LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

2. The Flowfate has been Referenced to Glandard Temperature (20 Grand Tessare (700 min.	B resolute/ condition.		
Notes :-		Authorized By	
1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna	a, Greater Noida (U.P.)	Authorized by	
2. Reference used are directly traceable to national standard through unbroken chain of calibration .			
3. Results reported are valid at the time of and under the stated conditions of measurement		\bigcirc 1	
A Table On the second of the s		/)14	

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida (Chief Executive Officer)

Scanned with CamScanner





CC-1051

ULR No.	CC105123000000923F		Page No 2 of 2
Calibration Date	03.08.2023	Suggested Date of Next Calibration	02.08.2024
Certificate No.	LES-CCL/FF/RF/SC/419		

05. Calibration Results for Flow of Rotameter

S.No.	Test meter (DUC) Measured Flow (Ipm)	Reference True Flow rate (lpm)	Error (%)	Calibration
1	16.70	16.388	1.904	0.981
2	16.70	16.354	2.116	0.979
3	16.70	16.377	1.972	0.981
4	16.70	16.380	1.954	0.981
5	16.70	16.386	1.916	0.981

Type A standard Uncertainty

for repeated data (1-5)

± 0.0061

lpm

Expanded uncertainty in Actual flow

measurement, U (k=2)

± 0.8909

lpm

2.30

% Rdg

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6 Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****

Kasna



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lescellab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300000	00924F	Cali. Field - Electr	o-Technical	Page No 1 of 1	
Certificate No.	LES-CCL/ET/TT/SC/29	96				
Calibration Date	03.08.2023	Sug	gested Date of N	ext Calibration	02.08.2024	
Customer Name :-	M/s Prism Johnson L	imited				
Address :-	Village - Mankahari, F	P.O. Bathia,				
	Tehsil - Rampur Bagh	helan,				
	Distt. Satna - 485111	(M.P)				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed A	t Site	Condition of DUC	OK	
Location of Performance	for Calibration	On Site				

01 DUC Fitted in instrument

UI. DOOT ILLCA III III SII AIII CI			
Name	Make	Model	SI.No. / ID.No.
Fine Particulate Sampler	THERMO	TEI - 121	216 - TEF - 21

02 Details of DLIC

UZ. Details of DOC			
Name	Time Totalizer	Environmental Conditions During Calibrat	ion
SI.No.	T - 216	Temperature (°C) :- 25 ± 4 °C	25.8
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	741.60

03 Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate No. PE23CC01414		Calibration Date	Valid Up to
		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Reference Time		Error	at 95 % of Cor level (k	nfidence
	(Firs/Milli/Occ)	Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 34.40hrs)	15.0070	900.42	-0.05	± 2.30987	20.80

Uncertainty Contributing Factor:

- 1. Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments

Kasna 3

Scanned with CamScanner

Authorized By

(Chief Executive Officer)

*** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230	CC105123000000919F		اط السنط المسر	Done No. 4 -65	
Certificate No.	LES-CCL/FF/PM/		Call. Fie	ld - Fluid Flow	Page No 1 of 2	
Calibration Date	03.08.2023		ted Date of	Next Calibration	02.08.2024	
Customer Name :- Address :-	M/s Prism Johns Village - Mankah Tehsil - Rampur Distt. Satna - 485	ari, P.O. Bathia, Baghelan,				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	26.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DUC	ОК	
Location of Performance	for Calibration	On Site				

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Fine Particulate Sampler	Thermo	TEI - 121	217 - TEF - 21	

02. Details of DUC

Name	Dry Gas Meter	Environmental Conditions During Calibration		
Make/Model	Honey well / BK - G1.6	Temperature (°C) :- 25 ± 10 °C	24.2	
SI.No.	1807079685	Relative Humidity (%) :- 45-75 %	54.2	
Cal. Range / Resolution	16.67 lpm (±2%) / 0.0002 m3	Barometric Pressure (mmHg)	744.20	

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range SI.No. / ID.No.		Traceability
1	LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Lab, Mumbai
-	Digital Stop Watch	10 Sec 59 min	LES-CCL/R/14510	LES - CCL, Gr. Noida
SI.No.	Certificate No.	Calibration Date		Valid Up to
1	PICAL/0922/F/032	05.09.2022		04.09.2023
2	LES-CCL/ET/SW/931	15.09.2022		14.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration .

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida

Kasna





ULR No.	CC105123000000919F		PageNo 2 of 2 02.08.2024
Calibration Date		Suggested Date of Next Calibration	02.00
Certificate No.	LES-CCL/FF/PM/SC/108		

05. Calibration Results for Flow of Dry Gas Meter

S.No.	Test meter (DUC) Measured Flow	Reference True Flow rate (Ipm)	Error (%)
	(lpm)	to the second se	0.860
1	16.65	16.508	0.866
	16.66	16.517	0.830
_2		16.503	
3	16.64		1.066
-	16.69	16.514	1.011
5	16.69	16.523	1.0.1

Type A standard Uncertainty for repeated data (1-5)

 ± 0.0034

lpm

Expanded uncertainty in Actual flow

measurement, U (k=2)

± 0.9118

lpm

2.41 % Rdg

Gr. Noida

* Kasna

Note:-

Final Readings of Dry Gas Meter at the end of Calibration: 24.8806 m³

Uncertainty Contributing factor:-

1. Repeatability (based on five measurement)

2.Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) cs-Centre A

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****

Scanned with CamScanner



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300	00000920F	Calibration. Field - Fluid Flow			Page No 1 of 2	
Certificate No.	LES-CCL/FF/RF/S	SC/295					
Calibration Date	03.08.2023	03.08.2023 Suggested Date of Next Calibration			02.	08.2024	
Customer Name :- Address :-	M/s Prism Johns Village - Mankah Tehsil - Rampur Distt. Satna - 485	ari, P.O. Bathia, Baghelan,					
S.R.F. No.	2023/17	S.R.F. Date	22.06.2023	Issue Da	ate	22.08.2023	
Date of DUC Receipt	03.08.2023 Calibration Performed At Site Condition of DUC					ОК	
Location of Performance for Calibration		On Site					

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Fine Particulate Sampler	THERMO	TEI - 121	217 - TEF - 21	

02. Details of DUC

Name	Rotameter	Environmental Conditions During Calibration		
Resolution	1.0 lpm	Temperature (°C) :- 25 ± 10 °C	26.5	
SI.No.	M20105	Relative Humidity (%) :- 45-75 %	56	
Cal. Range	16.67 lpm (±2 %)	Barometric Pressure (mmHg)	738.80	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID).No.	Traceability
LFE GAS FLOW CALIBRATOR	0.5 -50 lpm	0416 / LES-CC	CL/R/4901	PI Calibration Laboratory, Mumbai
Certificate No.	Calibratio	n Date	Valid Up to	
PICAL/0922/F/032	05.09.2	022 04.09.2023		04.09.2023

04. Calibration Procedur LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.	
Notes :-	Authorized By
1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)	Authorized by
2. Reference used are directly traceable to national standard through unbroken chain of calibration	
3. Results reported are valid at the time of and under the stated conditions of measurement	\cap 1
4. This Certificate refers only to the particular item calibrated.	1/11/2
5. Decision rule required - No	Some
6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025	SHIVSHANKER SINGH
7. Calibration status - Sticker Indicating CAL, STATUS in affixed on the Instruments	(Chief Executive Officer)

Scanned with CamScanner





CC-1051

ULR No.	CC105123000000920F		Page No 2 of 2
Calibration Date	03.08.2023	Suggested Date of Next Calibration	02.08.2024
Certificate No.	LES-CCL/FF/RF/SC/295		

05. Calibration Results for Flow of Rotameter

S.No.	Test meter (DUC) Measured Flow	Reference True Flow rate	Error (%)	Calibration Factor
1	(lpm) 16.70	(lpm) 16.284	2.555	0.975
2	16.70	16.296	2.479	0.976
3	16.70	16.288	2.529	0.975 0.975
4	16.70	16.290	2.517	
5	16.70	16.281	2.574	0.975

Type A standard Uncertainty

for repeated data (1-5)

± 0.0026

lpm

Expanded uncertainty in Actual flow

measurement, U(k=2)

± 0.8860

lpm

± 2.30

% Rdg

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurement)
- 2.Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna * Kasna *

Lilla

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939

Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300000	00921F	Cali. Field - Elect	ro-Technical	Page No 1 of 1 02.08.2024	
Certificate No.	LES-CCL/ET/TT/SC/29					
Calibration Date	03.08.2023	S	uggested Date of N	ext Calibration		
Customer Name :-	M/s Prism Johnson L	imited				
Address :-	Village - Mankahari, P.O. Bathia,					
Tehsil - Rampur Baghelan,						
	Distt. Satna - 485111	(M.P)				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed	At Site	Condition of DUC	ОК	
Location of Performance	for Calibration	On Site				

01 DUC Fitted in instrument

OI. DOOT RECUIR HISTIAMEN	•			
Name	Make	Model	SI.No.	
Fine Particulate Sampler	THERMO	TEI - 121	217 - TEF - 21	

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibrat	ion
SI.No.	T - 217	Temperature (°C) :- 25 ± 4 °C	25.8
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	741.60

03 Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate I		Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Reference Time		Error	Expanded Un at 95 % of Co level (A	onfidence
	(1.1.6.7	Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 40.80 hrs)	15.0070	900.42	-0.05	± 2.30987	20.80

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurement)
- 2.Uncertainty of master instruments
- 3 Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = and confidence level is 95 % for Normal distribution.

Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes:-	Authorized By
This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.)	
Reference used are directly traceable to national standard through unbroken chain of calibration .	
Results reported are valid at the time of and under the stated conditions of measurement	1
This Certificate refers only to the particular item calibrated.	
. Decision rule required - No	THE PROPERTY OF THE PROPERTY O
Our NABL certificate no. is CC-1051 valid up to 18.05.2025	SHIVSHANKER SINGH
7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments	(Chief Executive Officer)

**** End of Calibration Certificate ****

Scanned with CamScanner



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300		Cali. Fiel	d - Fluid Flow	Page I	No 1 of 2
Certificate No.	LES-CCL/FF/PM/S				00.	20.0004
Calibration Date	03.08.2023	3.08.2023 Suggested Date of Next Calibration			02.08.2024	
Customer Name :- Address :-	Village - Mankaha Tehsil - Rampur E	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date		22.08.2023

04 DLIC Fitted in instrument

Location of Performance for Calibration

UI. DUC FILLEU III III SII UIII			
Name	Make	Model	SI.No.
Name	make		721 - DTC - 2011
Fine Particulate Sampler	Envirotech	APM - 550	721 - DIC - 2011

On Site

02. Details of DUC

nvironmental Conditions During Calibr	ation
emperature (°C) :- 25 ± 10 °C	24.2
elative Humidity (%) :- 45-75 %	54.2
	744.20
	arometric Pressure (mmHg)

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No. / ID.No.	Traceability	
1	LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Lab, Mumbai	
-	Digital Stop Watch	10 Sec 59 min	LES-CCL/R/14510	LES - CCL, Gr. Noida	
CLNC	a um de Na	Calibration Date		Valid Up to	
SI.No.		05.	09.2022	04.09.2023	
-1	LES-CCL/ET/SW/931	15.	09.2022	14.09.2023	
2	LLO-OOL LIVOTIVO				

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

Kasna

S-Centro





ULR No.	CC105123000000913F		PageNo 2 of 2
Calibration Date	03.08.2023	Suggested Date of Next Calibration	02.08.2024
Certificate No.	LES-CCL/FF/PM/SC/105		

05. Calibration Results for Flow of Dry Gas Meter

S.No.	Test meter (DUC) Measured Flow (Ipm)	Reference True Flow rate (Ipm)	Error (%)
1	16.25	16.080	1.057
2	16.23	16.076	0.958
3	16.20	16.085	0.715
4	16.19	16.094	0.596
5	16.25	16.056	1.208

Type A standard Uncertainty

for repeated data (1-5)

± 0.0061

lpm

Expanded uncertainty in Actual flow

measurement, U(k=2)

± 0.8878

lpm

± 2.47 % Rdg

Final Readings of Dry Gas Meter at the end of Calibration: 1179.8586 m3

Uncertainty Contributing factor:-

- 1. Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for

Normal distribution. Calibration Place: Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) ES-Centre

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****

Gr. Noida

Kasna



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230000	00914F		T	
Certificate No.	LES-CCL/ET/TT/SC/2		II. Fleld - Electi	ro-Technical	Page No 1 of 1
Calibration Date	03.08.2023		ested Date of N	ext Calibration	02.08.2024
Customer Name :- Address :-	M/s Prism Johnson L Village - Mankahari, I Tehsil - Rampur Bag Distt. Satna - 485111	imited P.O. Bathla, helan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DUC	ОК
Location of Performance for Calibration		On Site			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Fine Particulate Sampler	Envirotech	APM - 550	721 - DTC - 2011

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibrat	ion
SI.No.	T - 721	Temperature (°C) :- 25 ± 4 °C	25.8
Make	CE Germany	Relative Humidity (%) :- 30-75 %	54.0
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	741.60

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability	
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)	
Calibration Certificate No.		Calibration Date	Valid Up to	
PE23CC01414		11.03.2023	10.03.2024	

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Referençe Time		Error	Expanded Und at 95 % of Cor level (k	fidence
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 937.51 hrs)	15.0070	900.42	-0.05	± 2.30987	20.80

Uncertainty Contributing Factor:

- 1. Repeatability (based on five measurement)
- 2 Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noisa (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the Instruments

Gr. Noida Wasna * Kasna *

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

*** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300	0000915F	Cali. Field - Fluid Flow		Page No 1 of	2
Certificate No.	LES-CCL/FF/PM/S	SC/419	- Cum - To			
Calibration Date	03.08.2023	Suggest	ed Date of I	Next Calibration	02.08.2024	
Customer Name :- Address :-	M/s Prism Johnso Village - Mankaha Tehsil - Rampur E Distt. Satna - 485	ri, P.O. Bathia, Baghelan,				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.20)23
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DU	с ок	\Box
Location of Performance	for Calibration	On Site				\Box

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Fine Particulate Sampler	Envirotech	APM - 550	722 - DTC - 2011

02. Details of DUC

Name	Dry Gas Meter	Environmental Conditions During Calibra	ation
Make/Model	Qinchuan / G1.6	Temperature (°C) :- 25 ± 10 °C	24.2
SI.No.	110121364	Relative Humidity (%) :- 45-75 %	54.2
Cal. Range / Resolution	16.67 lpm (±2%) / 0.0002 m3	Barometric Pressure (mmHg)	744.20

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No. / ID.No.		Traceability
1	LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/49	901	PI Calibration Lab, Mumbai
2	Digital Stop Watch	10 Sec 59 min	LES-CCL/R/14510		LES - CCL, Gr. Noida
SI.No.	Certificate No.	Calibration Date			Valid Up to
1	PICAL/0922/F/032	05.09.2022			04.09.2023
2	LES-CCL/ET/SW/931	1	5.09.2022		14.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida

Kasna





	004054000000455		PageNo 2 of 2
ULR No.	CC105123000000915F	and Calibration	02.08.2024
Calibration Date	03.08.2023	Suggested Date of Next Calibration	
Certificate No.	LES-CCL/FF/PM/SC/419		

05. Calibration Results for Flow of Dry Gas Meter

S.No.	Test meter (DUC) Measured Flow	Reference True Flow rate	Error (%)
	(lpm)	(lpm)	1.223
1	16.72	16.518	0.980
2	16.70	16.538	1.599
3	16.77	16.506	1.410
4	16.76	16.527	
5	16.72	16.520	1.211

Type A standard Uncertainty

for repeated data (1-5)

± 0.0051

lpm

Expanded uncertainty in Actual flow

measurement, U (k=2)

± 0.9123

lpm

2.40 % Rdg

ES-Centro

Gr. Noida

Kasna

Final Readings of Dry Gas Meter at the end of Calibration: 669.8188 m3 Note:-

Uncertainty Contributing factor:-

Repeatability (based on five measurement)

2.Uncertainty of master instruments

3.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for

Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration .

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230000	00916F	Cali, Field - Electro-Technical		Page No 1 of 1	
Certificate No.	LES-CCL/ET/TT/SC/29	94	II. Field - Licon	o-reciniiou.		
Calibration Date	03.08.2023	Sugg	ested Date of N	ext Calibration	02.08.2024	
Customer Name :-	M/s Prism Johnson L	imited				
Address :-	Village - Mankahari, F	P.O. Bathia,				
	Tehsil - Rampur Bagi	helan,				
	Distt. Satna - 485111					
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed At	Condition of DUC	ОК		
Location of Performance	for Calibration	On Site	•			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Fine Particulate Sampler	Envirotech	APM - 550	722 - DTC - 2011

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibrat	tion
SI.No.	T - 722	Temperature (°C) :- 25 ± 4 °C	25.8
Make	CE Germany	Relative Humidity (%) :- 30-75 %	54.0
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	741.60

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate	No.	Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)		erence ime	Error	Expanded Unated States 195 % of College 1 (k	nfidence
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 1251.40 hrs)	15.0070	900.42	-0.05	± 2.30987	20.80

Uncertainty Contributing Factor :-

- Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3 Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom == and confidence level is 95 % for Normal distribution.

Calibration Place: - Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2 Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6 Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS In affixed on the instruments

Greater Moida (U.P.)

Gr. Noida

* Kasna **

Scanned with CamScanner

SHIVSHANKER SINGH (Chief Executive Officer)

Authorized By

*** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000917F		Cali. Fiel	d - Fluid Flow	Page No 1 of 2	
Certificate No.	LES-CCL/FF/PM/S	SC/107			00.00.0004	
Calibration Date	03.08.2023	Suggest	ed Date of N	lext Calibration	02.08.2024	
Customer Name :- Address :-	M/s Prism Johnson Village - Mankaha Tehsil - Rampur E Distt. Satna - 485	ari, P.O. Bathia, Baghelan,				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed At		Condition of DU	с ок	
Location of Performance	for Calibration	On Site				

04 DUC Fitted in instrument

01. Doo i litted in instrument			2111
Name	Make	Model	SI.No.
	- indice	ADM EEO	723 - DTC - 2011
Fine Particulate Sampler	Envirotech	APM - 550	720 - DTO - 2011

02. Details of DUC

Name	Dry Gas Meter Environmental Conditions During Calibration			
Make/Model	Dij Gus meter	Temperature (°C) :- 25 ± 10 °C	24.2	
SI.No.	~	Relative Humidity (%) :- 45-75 %	54.2	
Cal. Range / Resolution		Barometric Pressure (mmHg)	744.20	

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
1	LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Lab, Mumbai
2	Digital Stop Watch	10 Sec 59 min	LES-CCL/R/14510	LES - CCL, Gr. Noida
SI.No.	Certificate No.	Calibration Date		Valid Up to
1	PICAL/0922/F/032	05.09.2022		04.09.2023
2	LES-CCL/ET/SW/931	15	.09.2022	14.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) -Centro
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida





ULR No.	CC105123000000917F		PageNo 2 of 2
Calibration Date		Suggested Date of Next Calibration	02.08.2024
Certificate No.	LES-CCL/FF/PM/SC/107		

05. Calibration Results for Flow of Dry Gas Meter

S.No.	Test meter (DUC) Measured Flow (Ipm)	Reference True Flow rate (Ipm)	Error (%)
1	16.52	16.370	0.916
2	16.51	16.338	1.053
3	16.56	16.356	1.247
4	16.58	16.366	1.308
5	16.48	16.378	0.623

Type A standard Uncertainty

for repeated data (1-5)

± 0.0066

lpm

Expanded uncertainty in Actual flow

measurement, U(k=2)

± 0.9035

lpm

± 2.43 % Rdg

Gr. Noida

Final Readings of Dry Gas Meter at the end of Calibration: 982.3680 m3 Note:-

Uncertainty Contributing factor:-

- 1. Repeatability (based on five measurement)
- 2.Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) S-Centre 2. Reference used are directly traceable to national standard through unbroken chain of calibration,

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000	918F	Cali. Field - Electro-Technical Page		Page No 1 of 1
Certificate No.	LES-CCL/ET/TT/SC/293				00.00.0024
Calibration Date	03.08.2023	Sug	gested Date of Ne	ext Calibration	02.08.2024
Customer Name :-	M/s Prism Johnson Limi	ted			
Address :-	Village - Mankahari, P.O.	. Bathia,			
	Tehsil - Rampur Baghela	an,	5.00		
	Distt. Satna - 485111 (M.	P)			
C D E No	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
S.R.F No.	2023/11	O.IV.I Date	00.2020		

S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DUC	OK
Location of Performance fo	r Calibration	On Site			

01 DUC Fitted in instrument

Name	Make	Model	SI.No.	
Fine Particulate Sampler	Envirotech	APM - 550	723 - DTC - 2011	

02 Details of DUC

UZ. Details of Doc			
Name	Time Totalizer	Environmental Conditions During Calibrat	ion
SI.No.	T - 723	Temperature (°C) :- 25 ± 4 °C	25.8
	CE Germany	Relative Humidity (%) :- 30-75 %	54.0
Make Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	741.60

03 Standard Equipment used for calibration

Range	SI.No./ID.No.	Traceability
10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Digital Automatic Timer 10 Sec - 4 hrs Calibration Certificate No.		Valid Up to
PE23CC01414		10.03.2024
	10 Sec - 4 hrs	10 Sec - 4 hrs LES-CCL/R/2510

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

libration Results : DLIC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Reference Time		Error Expanded U at 95 % of C level (onfidence	
	(1113/1111111000)	Min.	Sec.	(%)	%	Sec.	
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 1260.54 hrs)	15.0070	900.42	-0.05	± 2.30987	20.80	

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kashap of eater Noida
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments

Gr. Noida

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****

Scanned with CamScanner



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939

Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300	0000911F Cali. Field - Fluid Flow		Page No 1 of 2	
Certificate No.	LES-CCL/FF/PM/S	SC/104	15 / 1	Levet Calibration	02.08.2024
Calibration Date	03.08.2023	03.08.2023 Suggested Date of Next Calibration			02.00.2024
Customer Name :- Address :-	M/s Prism Johns Village - Mankaha Tehsil - Rampur Distt. Satna - 485	ari, P.O. Bathia, Baghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.202
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DU	C OK
Location of Performance	for Calibration	On Site			

01. DUC Fitted in instrument

01. DOC 11	ica iii iiisti aiii			0111	
Name		Make	Model	SI.No.	
	ulate Sampler	Envirotech	APM - 550	724 - DTC - 2011	
I IIIC I aitio	diate campion	LITALIOCCOLL			

02. Details of DUC

Name	Dry Gas Meter	Environmental Conditions During Calibration	
Make/Model	2.)	Temperature (°C) :- 25 ± 10 °C	24.2
SI.No.	QIIIOIIIIIII O	Relative Humidity (%) :- 45-75 %	54.2
Cal. Range / Resolution	110121010		744.20

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No. / ID.No.		Traceability
1	LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/49	01	PI Calibration Lab, Mumbai
2	Digital Stop Watch	10 Sec 59 min	LES-CCL/R/14510		LES - CCL, Gr. Noida
SI.No.	Certificate No.	Calibration Date			Valid Up to
1	PICAL/0922/F/032	05.09.2022			04.09.2023
2	LES-CCL/ET/SW/931	15.09.2022			14.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/07

Remark: 1.Refer page 2 of 2 for Calibration Results

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibrations

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida

Kasna





00-1	
PageNo.	- 2 of 2

ULR No.	CC105123000000911F		PageNo 2 of 2
Calibration Date	03.08.2023	Suggested Date of Next Calibration	02.08.2024
Certificate No.	LES-CCL/FF/PM/SC/104		

05. Calibration Results for Flow of Dry Gas Meter

S.No.	Test meter (DUC) Measured Flow	Reference True Flow rate	Error (%)
	(lpm)	(lpm)	1.238
1	16.84	16.634	1.325
2	16.83	16.610	
3	16.92	16.639	1.689
1		16.654	1.537
4	16.91		1.263
5 I	16.84	16.630	

Type A standard Uncertainty

for repeated data (1-5)

 ± 0.0069

lpm

Expanded uncertainty in Actual flow

measurement, U(k=2)

± 0.9185

Final Readings of Dry Gas Meter at the end of Calibration: 529.6490 m³

Ipm

± 2.39 % Rdg

Gr. Noida

Kasna

Uncertainty Contributing factor:-

Repeatability (based on five measurement)

2. Uncertainty of master instruments

3.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Note:-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) Centro

2. Reference used are directly traceable to national standard through unbroken chain of calibration /

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Nolda, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939

Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

	W.1.	101011001000					
ULR No.	CC10512300000	00912F	Outility to the contract of th		Page No 1 of 1		
Certificate No.	LES-CCL/ET/TT/SC/29	01					
Calibration Date	03.08.2023	Sugg	02.08.2024				
Customer Name :-	M/s Prism Johnson Limited						
Address :-	Village - Mankahari, F	Village - Mankahari, P.O. Bathla,					
	Tehsil - Rampur Bagi	Tehsil - Rampur Baghelan,					
	Distt. Satna - 485111	(M.P)					
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023		
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DUC	OK		
	ocation of Performance for Calibration						

01. DUC Fitted in instrument

Name	Make Model		SI.No.
Fine Particulate Sampler	Envirotech	APM - 550	724 - DTC - 2011

02 Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibrat	lon
SI.No.	T - 724	Temperature (°C) :- 25 ± 4 °C	25.8
Make	CE Germany	Relative Humidity (%) :- 30-75 %	54.0
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	741.60

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate No.		Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Value on DUC (Hrs/Min/Sec)	Reference Time		Error Expanded Uncer at 95 % of Confid level (k = 2		nfidence
	(maximized)	Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 1168.10 hrs)	15.0070	900.42	-0.05	± 2.30987	20.80

Uncertainty Contributing Factor :-

- 1. Repeatability (based on five measurement)
- 2 Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place: - Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Norda (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna

Scanned with CamScanner

Authorized By

(Chief Executive Officer)

.... End of Calibration Certificate



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939



CC-1051

Website: www.lesccllab.com

CALIBRATION CERTIFICATE

ULR No.	CC1051230	00000929F	Cali. Fie	eld - Fluid Flow	Page 1 of 3
Certificate No.	LES-CCL/FF/MF				
Calibration Date	04.08.2023	04.08.2023 Suggested Date of Next Calibration			03.08.2024
Customer Name :- Address :-	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed	At Site	Condition of DUC	OK
Location of Performance	for Calibration	On Site			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Respirable Dust Sampler	Thermo	TEI - 108NL	1976 - DTC - 2011

02. Details of (DUC)

Name	Orifice Manometer Flow	Orifice Manometer Flow Environmental Conditions During Cal	
Make/Trade Mark	Thermo	Temperature (°C) :- 25 ± 10 °C	2.5
SI.No.	1976 - DTC - 2011	Relative Humidity (%) :- 45-75 %	57
Cal. Range	0.7 -1.4 m ³ /min	Barometric Pressure (mmHg)	739.65
Resolution	0.01 & 0.025 m ³ /min		

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID No.		Traceability
Top Loading Orifice Calibrator	0.6 to 1.4 m³/min	57/LES-CCL	/R/15304	Enviro Instruments Gr. Noida
Certificate No.	Cali.	Date		d Up to
EI/FF/4760	25.11.	2022	24.1	1.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/08

Remark: 1. Refer page 2 of 3 for Calibration Results and page 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the Instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida





ULR No.	CC10512300000		Page No 2 of 3
Calibration Date	04.08.2023	Suggested Date of Next Calibration	03.08.2024
Certificate No.	LES-CCL/FF/MF/SC/132		

05. Calibration Results For Orifice Manometer Flow

S.No.	Test piece measured Indicated flow rate	Reference True measured flow rate in Calibration Curve	Error % Expand (Rdg) at 95 % of Cor		ed Uncertainty nfidence level (<i>k</i> =2)	
	(m ³ /min)	(m³/min)	(rtug)	± (m³/min)	(% Rdg)	
1	1.400	1.340	4.478	0.044	3.30	
2	1.27	1.230	3.252	0.041	3.30	
3	1.04	1.000	4.000	0.033	3.30	
4	0.86	0.820	4.878	0.033	3.30	
5.	0.750	0.720	4.167	0.024	3.30	
					(Curve Enclosed)	

(Curve Enclosed)

Uncertainty Contributing Factors :-

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments used for Flow measurement
- 3.Uncertainty of master instruments used for Temp.Measurement (Temp.& RH Indicator)
- 4. Uncertainty of master instruments used for Atm. Pressure Measurement (Barometer)
- 5.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and C.L is 95 % for Normal distribution.

Calibration Place: Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) ES-Centro
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)


Gr. Noida



ULR No. CC105123000000929F Date of Calibration: 04.08.2023

CALIBRATION CURVE FOR ORIFICE MANOMETER FLOW

Page No. - 3 of 3



S	1 2 3 4	Reference True Flow Rate (m³/min) 0.720 0.820 1.000 1.230	Test Piece Measured Flow Rate (m³/min) 0.750 0.86 1.04 1.27	SI.No. of the Instruments Name of the unit calibrated Name of the Party	Respirable Dust Sampler 1976 - DTC - 2011 Orifice Manometer Flow M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)
	4		1.27 1.400		

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greafer Noida (U.P.)
- Notes:
 1. This certificate shall not be reproduced, except in full without the written permisson of LES-COL.

 2. Reference used are directly traceable to national standard through unbroken chain of calibration.

- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****

Gr. Noida



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.)
E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300000	00930F	Call. Field - Electro-Technical		Page No 1 of 1	
Certificate No.	LES-CCL/ET/TT/SC/299	9				
Calibration Date	04.08.2023	Sugge	Suggested Date of Next Calibration			
Customer Name :- Address :-	M/s Prism Johnson Lie Village - Mankahari, P. Tehsil - Rampur Bagh Distt. Satna - 485111 (.O. Bathla, elan,				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issuo Dato	22.08.2023	
Date of DUC Receipt	04.08.2023	Calibration Performed At	Site	Condition of DUC	OK	

01. DUC Fitted in instrument

Location of Performance for Calibration

	OI: DOOT Read in instrument					
	Name	Mako	Model	SI.No.		
1	Respirable Dust Sampler	Thermo	TEI - 108NL	1976 - DTC - 2011		

On Site

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibration	
SI.No.	T - 1976	Temperature (°C) :- 25 ± 4 °C	26.4
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	740,20

03. Standard Equipment used for calibration

Standard Equipment Name Range		SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate No.		Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)		ference Time	Error	Expanded Ur at 95 % of Co level (k	nfidence
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 110.69 hrs)	15.0086	900.516	-0.06	± 2.30966	20.80

Uncertainty Contributing Factor :-

- Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna *

Scanned with CamScanner

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

.... End of Calibration Certificate



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230	000000931F	Cali Fi	eld - Fluid Flow	Page 1 of 3
Certificate No.	LES-CCL/FF/MF	F/SC/133		, id - i idid i ioii	
Calibration Date	04.08.2023	Sı	ggested Date o	f Next Calibration	03.08.2024
Customer Name :- Address :-	M/s Prism John Village - Manka Tehsil - Rampu Distt. Satna - 48	hari, P.O. Bathia, r Baghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed	At Site	Condition of DUC	OK
Location of Performance	Location of Performance for Calibration		•	-	

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Respirable Dust Sampler	Thermo	TEI - 108NL	1977 - DTC - 2011

02. Details of (DUC)

Name	Orifice Manometer Flow	Environmental Conditions During Calib	oration
Make/Trade Mark	Thermo	Temperature (°C) :- 25 ± 10 °C	2.5
SI.No.	1977 - DTC - 2011	Relative Humidity (%) :- 45-75 %	57
Cal. Range	0.7 -1.4 m ³ /min	Barometric Pressure (mmHg)	739.65
Resolution	0.01 & 0.025 m ³ /min		

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID No. 57/LES-CCL/R/15304		Traceability
Top Loading Orifice Calibrator	0.6 to 1.4 m³/min			Enviro Instruments Gr. Noida
Certificate No.	Cali. Da	ate	Valid Up to	
EI/FF/4760	25.11.20	022	24.1	11.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/08

Remark: 1. Refer page 2 of 3 for Calibration Results and page 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Gr. Noida (U.P.)

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)





ULR No.	CC105123000000931F		Page No 2 of 3	
Calibration Date	04.08.2023	Suggested Date of Next Calibration	03.08.2024	
Certificate No.	LES-CCL/FF/MF/SC/13			

05. Calibration Results For Orifice Manometer Flow

S.No.	Test piece measured Indicated flow rate	Reference True measured flow rate in Calibration Curve	Error % (Rdg)	Expanded l at 95 % of Confide	Uncertainty lence level (k =2)	
	(m³/min)	(m³/min)	(15)	± (m³/min)	(% Rdg)	
1	1.400	1.350	3.704	0.045	3.30	
2	1.25	1.210	3.306	0.040	3.30	
3	1.03	1.000	3.000	0.033	3.30	
4	0.89	0.860	3.488	0.033	3.30	
5	0.775	0.740	4.730	0.024	3.30	

(Curve Enclosed)

Uncertainty Contributing Factors:

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments used for Flow measurement
- 3. Uncertainty of master instruments used for Temp. Measurement (Temp. & RH Indicator)
- 4. Uncertainty of master instruments used for Atm. Pressure Measurement (Barometer)
- 5. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and C.L is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) Centre
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida




ULR No. CC105123000000931F Date of Calibration: 04.08.2023



CALIBRATION CURVE FOR ORIFICE MANOMETER FLOW

Page No. - 3 of 3



SI.No.	Reference	Test Piece	Name of the Instrument	Respirable Dust Sampler
	True Flow	Measured	SI.No. of the Instruments	1977 - DTC - 2011
	Rate	Flow Rate	Name of the unit calibrated	Orifice Manometer Flow
	(m³/min)	(m³/min)	Name of the Party	M/s Prism Johnson Limited
1	0.740	0.775		Village - Mankahari, P.O. Bathia,
2	0.860	0.89		Tehsil - Rampur Baghelan,
3	1.000	1.03		Distt. Satna - 485111 (M.P)
4	1.210	1.25		
5	1.350	1.400		

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna; Greater Nolda (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration /
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Gr. Noida * Kasna

Authorized By

SHIVSHAMKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CALIBRATION CERTIFICATE

	CALIBRATIOS	N CERTIFICATE	
ULR No.	CC105123000000932F	Cali. Field - Electro-Technical	Page No 1 of 1
Certificate No.	LES-CCL/ET/TT/SC/300		03.08.2024
Calibration Date		Suggested Date of Next Calibration	

Customer Name :-

M/s Prism Johnson Limited

Distt. Satna - 485111 (M.P)

Address :-

Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan,

				Janua Data	22.08.2023
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date Condition of DUC	ОК
Date of DUC Receipt	04.08.2023	Calibration Performed At	Site	Condition of Boo	
Location of Performance for	r Calibration	On Site			

01. DUC Fitted in instrument	t		SI.No.
Name	Make	Model	1977 - DTC - 2011
Respirable Dust Sampler	Thermo	TEI - 108NL	1977 - 2.10

2. Details of DUC		Environmental Conditions During Calibrat	011
Name	Time Totalizer	Ellerionne de la company de la	26.4
SI.No.	T - 1977	Temperature (°C) :- 25 ± 4 °C	54.0
Make	Hours	Relative Humidity (%) :- 30-75 %	740.20
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	

andard Equipment used for	Range	SI.No./ID.No.	Traceability
Standard Equipment Name		LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Digital Automatic Timer	10 Sec - 4 hrs		Valid Up to
Calibration Certificate	No.	Calibration Date 11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

Calibrati S.No.	On Results : DUC has been calibrated for following rain Displayed Value on DUC		erence 'ime	Error	at 9	anded Und 5 % of Cor level (k	fidence
	(Hrs/Min/Sec)	Min.	Sec.	(%)	•	%	Sec.
		15.0086	900.516	-0.06	±	2.30966	20.80
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 1860.49 hrs)	A			COSK Version		De la constitución de la constit

Uncertainty Contributing Factor :-

- Repeatability (based on five measurement)
- 2. Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) S-Centro

- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

Gr. Noida

Kasna

Scanned with CamScanner

(Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No. Certificate No.	CC1051230		Cali. Fie	eld - Fluid Flow	Page 1 of 3
Calibration Date	04.08.2023		gested Date o	f Next Calibration	03.08.2024
Customer Name :- Address :-	M/s Prism John Village - Manka Tehsil - Rampu Distt. Satna - 48	hari, P.O. Bathia, r Baghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed At	Site	Condition of DUC	OK
Location of Performance	for Calibration	On Site			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Respirable Dust Sampler	Thermo	TEI - 108NL	1980 - DTC - 2011

02. Details of (DUC)

Name	Orifice Manometer Flow	Environmental Conditions During Calibration			
Make/Trade Mark	Thermo	Temperature (°C) :- 25 ± 10 °C	2.5		
SI.No.	1980 - DTC - 2011	Relative Humidity (%) :- 45-75 %	57		
Cal. Range	0.7 -1.4 m ³ /min	Barometric Pressure (mmHg)	739.65		
Resolution	0.01 & 0.025 m ³ /min				

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID	No.	Traceability
Top Loading Orifice Calibrator	0.6 to 1.4 m³/min	57/LES-CCL	/R/15304	Enviro Instruments Gr. Noida
Certificate No.	Cali. Dat	te	Va	llid Up to
EI/FF/4760	25.11.202	22	24	1.11.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/08

Remark: 1. Refer page 2 of 3 for Calibration Results and page 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida





1		Page No 2 of 3
CC105123000000933F	1 - I Date of Next Calibration	03.08.2024
04.08.2023	Suggested Date of Next Cambration	
LES-CCL/FF/MF/SC/134		
	04.08.2023	

05. Calibration Results For Orifice Manometer Flow

No.	Test piece measured Indicated flow rate	Reference True measured flow rate in Calibration Curve (m³/min)	Error % (Rdg)	Expanded L at 95 % of Confide ± (m³/min)	Incertainty nce level (k =2) (% Rdg)
	(m³/min)	(m /mm)		0.045	3.30
	1.400	1.370	2.190	0.043	
1	1.400		3.361	0.039	3.30
2	1.23	1.190	0.00	0.004	3.30
	2.00	0.940	4.255	0.031	
3	0.98		3.846	0.031	3.30
,	0.81	0.780	3.040	835200	3.30
4	0.01	0.700	3.571	0.023	5.55
5	0.725	0.700	0.000.0001149.000		Curve Enclosed)

Uncertainty Contributing Factors :-

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments used for Flow measurement
- 3.Uncertainty of master instruments used for Temp.Measurement (Temp.& RH Indicator)
- 4.Uncertainty of master instruments used for Atm.Pressure Measurement (Barometer)

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and C.L is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P) **Authorized By** 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) S-Centro 2. Reference used are directly traceable to national standard through unbroken chain of calibration . 3. Results reported are valid at the time of and under the stated conditions of measurement Gr. Noida 4. This Certificate refers only to the particular item calibrated. SHIVSHANKER SINGH * Kasna (Chief Executive Officer)

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments.




ULR No. CC105123000000933F Date of Calibration:- 04.08.2023

THE PARTY OF THE P

CALIBRATION CURVE FOR ORIFICE MANOMETER FLOW

Page No. - 3 of 3



SI.No.	Reference	Test Piece	Name of the Instrument	Respirable Dust Sampler
100000000000000000000000000000000000000		Measured		1980 - DTC - 2011
	Rate	Flow Rate		Orifice Manometer Flow
	(m³/min)	(m³/min)	Name of the Party	M/s Prism Johnson Limited
1	0.700	0.725		Village - Mankahari, P.O. Bathia,
2	0.780	0.81		Tehsil - Rampur Baghelan,
3	0.940	0.98		Distt. Satna - 485111 (M.P)
4	1.190	1.23		
5	1.370	1.400		

Notes :-

- 1 This certificate shall not be reproduced, except in full without the written permisson of LES-CCL Kasna Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05,2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

CL. Kasna Greater Noida (U.P.)
tion of Gr. Noida

Kasna Kasn

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000934F	Call Field Fleetre Technical	Page No 1 of 1
Certificate No.	LES-CCL/ET/TT/SC/301	Call. Field - Electro-Technical	rage No 1 of 1
Calibration Date	04.08.2023	Suggested Date of Next Calibration	03.08.2024

Customer Name :-

Address :-

M/s Prism Johnson Limited

Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed At	Site	Condition of DUC	ОК
Location of Performance for	Calibration	On Site			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Respirable Dust Sampler	Thermo	TEI - 108NL	1980 - DTC - 2011	

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibration		
SI.No.	T - 1980	Temperature (°C) :- 25 ± 4 °C	26.4	
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0	
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	740.20	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate No. PE23CC01414		Calibration Date	Valid Up to
		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Reference Time		Error	Expanded Uncertainty at 95 % of Confidence level (k = 2)	
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 3587.28 hrs)	15.0086	900.516	-0.06	± 2.30966	20.80

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (UCP)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna

Authorized By

(Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Nolda, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230	00000935F	Call. Field - Fluid Flow		Danie A - A -
Certificate No.	LES-CCL/FF/MF	THE RESIDENCE OF THE PARTY OF T			Page 1 of 3
Calibration Date	04.08.2023	Sug	03.08.2024		
Customer Name :- Address :-	M/s Prism John Village - Manka Tehsil - Rampu Distt. Satna - 48	harl, P.O. Bathla, r Baghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	04.08.2023 Calibration Performed At Site Condition of DU			
Location of Performance	for Calibration	On Site Condition of DUC OK			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Respirable Dust Sampler	Thermo	TEI - 108NL	1981 - DTC - 2011

02. Details of (DUC)

Name	Orifice Manometer Flow	Environmental Conditions During Calibration		
Make/Trade Mark	Thermo	Temperature (°C) :- 25 ± 10 °C	2.5	
SI.No.	1981 - DTC - 2011	Relative Humidity (%) :- 45-75 %	57	
Cal. Range	0.7 -1.4 m ³ /min	Barometric Pressure (mmHg)	739.65	
Resolution	0.01 & 0.025 m ³ /min		•	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID No.		Traceability
Top Loading Orifice Calibrator	0.6 to 1.4 m³/mln 57/LES-CCL/R/15304		/R/15304	Enviro Instruments
				Gr. Noida
Certificate No.	Cali. Date		Valid Up to	
EI/FF/4760	25.11.2	05 44 0000		.11.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/08

Remark: 1. Refer page 2 of 3 for Calibration Results and page 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular Item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida





ULR No.	0010=		CC-1031
OLK NO.	CC105123000000935F		Page No 2 of 3
Calibration Date	04.08.2023		1 age 110 2 01 3
2 1151 1 11		Suggested Date of Next Calibration	03.08.2024
Certificate No.	LES-CCL/FF/MF/SC/135		

05. Calibration Results For Orifice Manometer Flow

S.No.	Test piece measured Indicated flow rate (m³/min)	ndicated flow rate flow rate in Calibration Curve		Expanded Uncertainty at 95 % of Confidence level (k = 2)		
	(III /IIIII)	(m³/min)		± (m³/min)	(% Rdg)	
1	1.375	1.320	4.167	0.044	3.30	
2	1.20	1.160	3.448	0.038	3.30	
3	1.01	0.970	4.124	0.032	3.30	
4	0.85	0.830	2.410	0.032	3.30	
5	0.725	0.700	3.571	0.023	3.30	

(Curve Enclosed)

Uncertainty Contributing Factors:

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments used for Flow measurement
- 3.Uncertainty of master instruments used for Temp.Measurement (Temp.& RH Indicator)
- 4. Uncertainty of master instruments used for Atm. Pressure Measurement (Barometer)
- 5.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and C.L is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kacnay Greater Noida (U.P.) 2. Reference used are directly traceable to national standard through unbroken chain of calibration
3. Results reported are valid at the time of and under the stated conditions of measurement
4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida




ULR No. CC105123000000935F Date of Calibration: 04.08.2023



CALIBRATION CURVE FOR ORIFICE MANOMETER FLOW

Page No. - 3 of 3



-	1 No	Reference	Test Piece	Name of the Instrument	Respirable Dust Sampler
10			Measured		1981 - DTC - 2011
		Rate	Flow Rate	til "I - "I I'h I and	Orifice Manometer Flow
		(m³/min)	(m³/min)		M/s Prism Johnson Limited
-	1	0.700	0.725		Village - Mankahari, P.O. Bathia,
	2	0.830	0.85		Tehsil - Rampur Baghelan,
1	2	0.830	1.01		Distt. Satna - 485111 (M.P)
	3	1.160	1.20		
1			25 133 173		
	5	1.320	1.375		

- Notes:
 1. This certificate shall not be reproduced, except in full without the written permisson of LES
 2. Reference used are directly traceable to national standard through unbroken chain of calibration and the stated conditions of measurement and standard through unbroken chain of calibration and the stated conditions of measurement and standard through unbroken chain of calibration and standard through u 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH

(Chief Executive Officer)

****End of Calibration Certificate****

Gr. Noida



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Nolda, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000936F		Call. Field - Electro-Technical P		Page No. 4 of 4
Certificate No.	LES-CCL/ET/TT/SC/302	CATEGORIA DE L'ANGEL D			Page No 1 of 1
Calibration Date	Calibration Date 04.08.2023		gested Date of No	03.08.2024	
Customer Name :- Address :-	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathi Tehsii - Rampur Baghelan, Distt. Satna - 485111 (M.P)	a,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023

Date of DUC Receipt	04.08,2023	Calibration Performed At	Site	Condition of DUC	OK
Location of Performance for	Calibration	On Site			

01. DUC Fitted in Instrument

Name	Mako	Model	SI.No.	
Respirable Dust Sampler	Thermo	TEI - 108NL	1981 - DTC - 2011	

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibration		
SI.No.	T - 1981	Temperature (°C) :- 25 ± 4 °C	26.4	
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0	
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	740.20	

03. Standard Equipment used for calibration

Standard Equipment Name Range		SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate No.		Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Reference Time		Error	Expanded Und at 95 % of Cor level (k	nfidence
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 168.91 hrs)	15.0086	900.516	-0.06	± 2.30966	20.80

Uncertainty Contributing Factor:

- Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom == and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.F.
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3 Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular Item calibrated.
- Decision rule required No
- 6 Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the Instruments

Greater Molda (U.P.)

Gr. Noida

Kasna **

Scanned with CamScanner

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

.... End of Calibration Certificate



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No. Certificate No.	CC1051230 LES-CCL/FF/MF	000000927F	Cali. Fie	eld - Fluid Flow	Page 1 of 3
Calibration Date	04.08.2023		ggested Date o	f Next Calibration	03.08.2024
Customer Name :- Address :-	M/s Prism John Village - Manka Tehsil - Rampu Distt. Satna - 48	hari, P.O. Bathia, r Baghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed A	At Site	Condition of DUC	ОК
Location of Performance	for Calibration	On Site			

01. DUC Fitted in instrument

Name Make		Model	SI.No.	
Respirable Dust Sampler	Thermo	TEI - 108NL	229 - TEF - 21	

02. Details of (DUC)

Name	Orifice Manometer Flow	Environmental Conditions During Calibration		
Make/Trade Mark	Thermo	Temperature (°C) :- 25 ± 10 °C	2.5	
SI.No.	229 - TEF - 21	Relative Humidity (%) :- 45-75 %	57	
Cal. Range	0.7 -1.4 m ³ /min	Barometric Pressure (mmHg)	739.65	
Resolution	0.01 & 0.025 m ³ /min			

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID No.	Traceability
Top Loading Orifice Calibrator	0.6 to 1.4 m³/min	57/LES-CCL/R/15304	Enviro Instruments Gr. Noida
Certificate No.	Cali. Dat	e	Valid Up to
EI/FF/4760	25.11.202	22	24.11.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/08

Remark: 1. Refer page 2 of 3 for Calibration Results and page 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the Instruments.

1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna Greater Noice (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)





			•
	0040540000000007		Page No 2 of 3
ULR No.	CC105123000000927	O-libration	03.08.2024
Calibration Date	04.08.2023	Suggested Date of Next Calibration	00.00.202
Certificate No.	LES-CCL/FF/MF/SC/131		

05. Calibration Results For Orifice Manometer Flow

No. Test piece meas	Test piece measured Reference True measured		Error %	Expanded Uncertainty at 95 % of Confidence level (k = 2)	
	Indicated flow rate (m³/min)	flow rate in Calibration Curve (m³/min)	(Rdg)	± (m³/min)	(% Rdg)
	1.375	1.320	4.167	0.044	3.30
١,	1.19	1.150	3.478	0.038	3.30
2		0.980	3.061	0.032	3.30
3	1.01	0.910	4.396	0.032	3.30
4	0.95			0.025	3.30
5	0.775	0.750	3.333	0.02	(Curve Enclosed)

Uncertainty Contributing Factors:

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments used for Flow measurement
- 3.Uncertainty of master instruments used for Temp.Measurement (Temp.& RH Indicator)
- 4.Uncertainty of master instruments used for Atm.Pressure Measurement (Barometer)

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and C.L is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Authorized By 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) 1. This certificate shall not be reproduced, except in full without the written permanent

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement Gr. Noida 3. Results reported are valid at the time of and under the stated conditions of measurement 4. This Certificate refers only to the particular item calibrated. SHIVSHANKER SINGH Decision rule required - No (Chief Executive Officer) 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025 7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments.

Scanned with CamScanner




ULR No. CC105123000000927F Date of Calibration: 04.08.2023



CALIBRATION CURVE FOR ORIFICE MANOMETER FLOW

Page No. - 3 of 3



SI.No.	Reference	Test Piece	Name of the Instrument	Respirable Dust Sampler
		Measured		229 - TEF - 21
	Rate	Flow Rate		Orifice Manometer Flow
	(m³/min)	(m³/min)	Name of the Party	M/s Prism Johnson Limited
1	0.750	0.775		Village - Mankahari, P.O. Bathia,
2	0.910	0.95		Tehsil - Rampur Baghelan,
3	0.980	1.01		Distt. Satna - 485111 (M.P)
4	1.150	1.19		Contract the second
5	1.320	1.375		

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL Kashar Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibrations.

 3. Results reported are valid at the time of and under the stated conditions of measurement.

 4. This Certificate refers only to the particular item calibrated.

- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05,2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****

Gr. Noida



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000928F	O II Final Floring Technical	Page No. 4 4	
Certificate No.	LES-CCL/ET/TT/SC/298	Cali. Field - Electro-Technical	Page No 1 of 1	
Calibration Date	04.08.2023	Suggested Date of Next Calibration	03.08.2024	
ustomer Name :	M/a D.:			

Customer Name :-

Address :-

M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed At	Site	Condition of DUC	OK
Location of Performance for Calibration		On Site			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Respirable Dust Sampler	Thermo	TEI - 108NL	229 - TEF - 21	

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibration		
SI.No.	T - 229	Temperature (°C) :- 25 ± 4 °C	26.4	
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0	
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	740.20	

03. Standard Equipment used for calibration

Standard Equipment Name	nent Name Range SI.		Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate	No.	Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Time at 95 % of C		Expanded Unated 195 % of Conference 195 % of C	onfidence	
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 61.40 hrs)	15.0086	900.516	-0.06	± 2.30966	20.80

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurement)
- 2.Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom == and confidence level is 95 % for Normal distribution.

Calibration Place: Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (1)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna * Kasna *

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.		C105123000000925F		ld - Fluid Flow	Page 1 of 3	
Certificate No.	LES-CCL/FF/MF		00.50.50.50.50.50.50.50			
Calibration Date	04.08.2023	Su	iggested Date o	f Next Calibration	03.08.2024	
Customer Name :- Address :-	M/s Prism John Village - Mankal Tehsil - Rampui Distt. Satna - 48	hari, P.O. Bathia, r Baghelan,				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	04.08.2023	Calibration Performed	At Site	Condition of DUC	ОК	

01. DUC Fitted in instrument

Location of Performance for Calibration

Name	Make	Model	SI.No.
Respirable Dust Sampler	Thermo	TEI - 108NL	230 - TEF - 21

On Site

02. Details of (DUC)

Name	Orifice Manometer Flow	Environmental Conditions During Calibration		
Make/Trade Mark	Thermo	Temperature (°C) :- 25 ± 10 °C	2.5	
SI.No.	230 - TEF - 21	Relative Humidity (%) :- 45-75 %	57	
Cal. Range	0.7 -1.4 m ³ /min	Barometric Pressure (mmHg)	739.65	
Resolution	0.01 & 0.025 m ³ /min			

03. Standard Equipment used for calibration

Standard Equipment Name	Range SI.No./II			Traceability
Top Loading Orifice Calibrator	0.6 to 1.4 m³/min	57/LES-CCL/R/15	304	Enviro Instruments Gr. Noida
Certificate No.	Cali. Date Va		Vali	id Up to
EI/FF/4760	25.11.202	22	24.	11.2023
		STATE OF THE PERSON OF THE PER	Market	

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC/08

Remark: 1. Refer page 2 of 3 for Calibration Results and page 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida





III D No	CC1051220000	000055	Page No 2 of 3
ULR No.	CC10512300000	00925F	03.08.2024
Calibration Date	04.08.2023	Suggested Date of Next Calibration	
Certificate No.	LES-CCL/FF/MF/SC/13	30	The second secon

05. Calibration Results For Orifice Manometer Flow

S.No.	Test piece measured	piece measured Reference True measured		Expanded U at 95 % of Confide	Incertainty nce level (k =2)
	Indicated flow rate (m³/min)	flow rate in Calibration Curve (m³/min)	(Rdg)	± (m³/mln)	(% Rdg)
1	1.350	1.400	-3.571	0.046	3.30
2	1.200	1.240	-3.226	0.041	3.30
3	0.97	1.020	-4.902	0.034	3.30
4	0.86	0.880	-2.273	0.034	3.30
5	0.750	0.780	-3.846	0.026	3.30
J				(Curve Enclosed)

Uncertainty Contributing Factors:

- Repeatability (based on five measurements)
- 2.Uncertainty of master instruments used for Flow measurement
- 3.Uncertainty of master instruments used for Temp.Measurement (Temp.& RH Indicator)
- 4. Uncertainty of master instruments used for Atm. Pressure Measurement (Barometer)
- 5.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and C.L is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Authorized By Notes:
1. This certificate shall not be reproduced, except in full without the written permission of all permission of a series of a series of a series of and under the stated conditions of measurement

3. Results reported are valid at the time of and under the stated conditions of measurement

3. Results reported are valid at the particular item calibrated. Notes :-1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Nolda (U.P.) Gr. Noida

Decision rule required - No

Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments.

SHIVSHANKER SINGH (Chief Executive Officer)




ULR No. CC105123000000925F Date of Calibration: 04.08.2023



CALIBRATION CURVE FOR ORIFICE MANOMETER FLOW

Page No. - 3 of 3



CLNO	Poference	Test Piece	Name of the Instrument	Respirable Dust Sampler
		Measured		230 - TEF - 21
	Rate	Flow Rate	City - 'ty - l'hended	Orifice Manometer Flow
	(m³/min)	(m ³ /min)		M/s Prism Johnson Limited
1	0.780	0.750	Traine or the const	Village - Mankahari, P.O. Bathia,
2	0.880	0.86		Tehsil - Rampur Baghelan,
	1.020	0.00		Distt. Satna - 485111 (M.P)
3 4	1.020	1.20		
5	1.400	1.350		

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna; Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibrations S-Centro
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments.

Authorized By

SHIVSHANKER SINGH

(Chief Executive Officer)

****End of Calibration Certificate****

Gr. Noida



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

Customer Name :-	M/s Prism Johnson Limited	Cuggottu Date of Heat Cambration	00.00.2024	
Calibration Date	04.08.2023	Suggested Date of Next Calibration	03.08.2024	
Certificate No.	LES-CCL/ET/TT/SC/297	Call. Field - Electro-Technical	Page No 1 of 1	
ULR No.	CC105123000000926F	Cali. Field - Electro-Technical	Page No. 4 - 6	

Address :-

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	04.08.2023	Calibration Performed At	Site	Condition of DUC	ОК
Location of Performance fo	r Calibration	On Site		•	*

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Respirable Dust Sampler	Thermo	TEI - 108NL	230 - TEF - 21	

02. Details of DUC

Name	Time Totalizer	Environmental Conditions During Calibration		
SI.No.	T - 230	Temperature (°C) :- 25 ± 4 °C	26.4	
Make	Hours	Relative Humidity (%) :- 30-75 %	54.0	
Range / Resolution	0.01 - 99999.99 hrs. / 0.01 hrs.	Barometric Pressure (mmHg)	740.20	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No./ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2510	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate	No.	Calibration Date	Valid Up to
PE23CC01414		11.03.2023	10.03.2024

04. Calibration Procedure LES-CCL/WI/31/ET/SC-03

05. Calibration Results: DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (Hrs/Min/Sec)	Reference Time		Error	Expanded Unated to the second	nfidence
		Min.	Sec.	(%)	%	Sec.
1	0.25 /15.0 / 900 (Final Readings of TTR at the end of Calibration: 131.60 hrs)	15.0086	900.516	-0.06	± 2.30966	20.80

Uncertainty Contributing Factor:

- Repeatability (based on five measurement)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = and confidence level is 95 % for Normal distribution.

Calibration Place: - Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

- This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida
 Reference used are directly traceable to national standard through unbroken chain of calibration .
 Results reported are valid at the time of and under the stated conditions of measurement
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

**** End of Calibration Certificate ****

Gr. Noida



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC10512300000	00940F	Cali. Field - Fluid Flow		Page No 1 of 3
Certificate No.	LES-CCL/FF/RF/SC/3	13	04		
Calibration Date	03.08.2023	03.08.2023 Suggested			02.08.2024
Customer Name :- Address :-	M/s Prism Johnson L Village - Mankahari, F Tehsil - Rampur Bagh Distt. Satna - 485111	P.O. Bathia, nelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DUC	OK
Location of Performance	for Calibration	On Site			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Gaseous Sampling Attachment	Envirotech	APM - 411	4298 - DTC - 2011

02 Details of DUC

Name	Rotameter	Environmental Conditions During Calib	ration
Resolution	0.1 lpm	Temperature (°C) :- 25 ± 10 °C	29.6
ID.No.	09/0228	Relative Humidity (%) :- 45-75 %	58
Cal. Range / Range	0.5 - 3.0 lpm / 0 - 3.0 lpm	Barometric Pressure (mmHg)	740.20

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID. No.	Traceability
LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Laboratory, Mumbai
Certificate No.	0.0 00 1	Calibration Date	Valid Up to
		05.09.2022	04.09.2023
PICAL/0922/F/032			

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC-07

Remark 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for Calibration Curve

2. The Flow Rate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) Centre
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item_calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

Gr. Noida





		Page No 2 of 3
ULR No.	CC105123000000940F	
Calibration Date	03.08.2023	Suggested Date of Next Calibration 02.08.2024
Certificate No.	LES-CCL/FF/RF/SC/313	

05. Calibration Results for Flow of Rotameter

S.No.	(DUC) Indicated reading	Reference True Flow rate	Error (%) FS	Calibration Factor
	(lpm)	(lpm)	1.000	0.940
1	0.5	0.470	0.967	0.942
2	0.5	0.471	0.933	0.944
3	0.5	0.472	0.900	0.946
4	0.5	0.473	0.867	0.948
5	0.5	0.474	1.400	0.958
6	1.0	0.958	1.100	0.978
7	1.5	1.467	1.933	0.971
8	2.0	1.942	1.667	0.980
9	2.5	2.450	2.400	0.976
10	3.0	2.928	1.867	0.981
11	3.0	2.944	1.833	0.982
12	3.0	2.945	1.800	0.982
13	3.0	2.946	1.767	0.982
14	3.0	2.947	(Cu	rve Enclosed)

Type A standard Uncertainty

I. for repeated data (1-5)

0.0007 lpm 0.0007 lpm

II. for repeated data (10-14)

Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

1.93 %FS or

I. 0.5 lpm

13.02 % Rdg

2.31 % Rdg

ES-Centre

Gr. Noida

Kasna *

OF

2.15 %FS

II. 3.0 lpm **Uncertainty Contributing Factor:**

- 1. Repeatability (based on five measurements)
- 2. Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

- Notes:
 1 . This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Nolda (U.P.) 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH

(Chief Executive Officer)




ULR No. CC105123000000940F

Date of Calibration:- 03.08.2023



CC-1051 Page No. - 3 of 3

CALIBRATION CURVE FOR ROTAMETER



SI.No.	Reference	Test Piece	Name of the Instrument	Rotameter
31.140.	True Flow	Measured	SI.No. of the Instrument	09/0228
	Rate	Flow Rate	Name of the Party	M/s Prism Johnson Limited
	(lpm)	(lpm)		Village - Mankahari, P.O. Bathia,
1	0.472	0.5		Tehsil - Rampur Baghelan,
2	0.958	1.0		Distt. Satna - 485111 (M.P)
3	1.467	1.5		
4	1.942	2.0		
5	2.45	2.5		
6	2.942	3.0		

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater-Noida (U
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the Instruments

ES-Centro Gr. Noida Kasna

Authorized By

(Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Nolda, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230000	Call, Flo	old - Fluid Flow	Page No 1 of 3	
Certificate No.	LES-CCL/FF/RF/SC/3	11			
Calibration Date	03.08.2023	Sugge	sted Date o	f Next Calibration	02.08.2024
Customer Name :- Address :-	Village - Mankahari, I Tehsil - Rampur Bagi	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	03.08.2023 Calibration Performed At Site Condition of DUC OK				
Location of Performance	for Calibration	On Site			

01 DUC Fitted in instrument

Name	Make	Model	SI.No.
Gaseous Sampling Attachment	Envirotech	APM - 411	4299 - DTC - 2011

02 Details of DUC

Name	Rotameter	Environmental Conditions During Calif	oration
Resolution	0.1 lpm	Temperature (°C):- 25 ± 10 °C	29.6
ID.No.	10/0911	Relative Humidity (%) :- 45-75 %	58
Cal. Range / Range	0.5 - 3.0 lpm / 0 - 3.0 lpm	Barometric Pressure (mmHg)	740.20

03 Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID. No.	Traceability
LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Laboratory, Mumbai
Certificate No.		Calibration Date	Valid Up to
PICAL/0922/F/032		05.09.2022	04.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC-07

Remark 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for Calibration Curve

2. The Flow Rate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Nolda (U.P.) S-Centre
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the Instruments

Authorized By

Gr. Noida

Kasna

SHIVSHANKER SINGH

(Chief Executive Officer)

Scanned with CamScanner





			Page No 2 of 3
ULR No.	CC105123000000938F	Data of Novt Calibration	02.08.2024
Calibration Date	03.08.2023	Suggested Date of Next Calibration	
Certificate No.	LES-CCL/FF/RF/SC/311		

05. Calibration Results for Flow of Rotameter

S.No.	(DUC) Indicated reading	Reference True Flow rate	Error (%) FS	Calibration Factor
	(lpm)	(lpm)	-0.700	1.042
1	0.5	0.521	-0.733	1.044
2	0.5	0.522	-0.753	1.046
3	0.5	0.523	-0.767	1.048
4	0.5	0.524	-0.833	1.050
5	0.5	0.525	-0.333	1.010
6	1.0	1.010	-1.100	1.022
7	1.5	1.533	-1.400	1.021
8	2.0	2.042	-0.633	1.008
9	2.5	2.519	-0.733	1.007
10	3.0	3.022	-0.700	1.007
11	3.0	3.021	-0.733	1.007
12	3.0	3.022	-0.767	1.008
13	3.0	3.023	-0.707	1.008
14	3.0	3.024		unus Englosed)

(Curve Enclosed)

Type A standard Uncertainty

0.0007 lpm I. for repeated data (1-5) 0.0007 lpm

II. for repeated data (10-14) Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

1.93 %FS or 11.75 % Rdg 1. 0.5 lpm 2.15 %FS or 2.25 % Rdg ± II. 3.0 lpm

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurements)
- 2. Uncertainty of master instruments
- 3.Resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place: Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (LIP) ES-Centro

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular Item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida

Kasna *




ULR No. CC105123000000938F

Date of Calibration:- 03.08.2023

CC-1051 Page No. - 3 of 3

CALIBRATION CURVE FOR ROTAMETER



SI.No.	Reference	Test Piece	Name of the Instrument	Rotameter
31.140.	True Flow	Measured	SI.No. of the Instrument	10/0911
	Rate	Flow Rate	Name of the Party	M/s Prism Johnson Limited
	(lpm)	(lpm)		Village - Mankahari, P.O. Bathia,
1	0.523	0.5		Tehsil - Rampur Baghelan,
2	1.010	1.0		Distt. Satna - 485111 (M.P)
3	1.533	1.5		
4	2.042	2.0		
5	2.519	2.5		
6	3.022	3.0		

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the Instruments

S-Centre Gr. Noida **Authorized By**

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CALIBRATION CERTIFICATE

ULR No.	CC10512300000	00937F	Cali. Field - Fluid Flow			
Certificate No.	LES-CCL/FF/RF/SC/3				Page No 1 of 3	
Calibration Date	03.08.2023		sted Date o	f Next Calibration	02.08.2024	
Customer Name :- Address :-	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)					
S.R.F No.	2023/17	S.R.F Date	22 06 2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023 Calibration Performed At Site Condition of DUC					
Location of Performance for Calibration		On Site	(a) = 10 = (a)			

01. DUC Fitted in instrument

Name	Make	Model	SI.No.	
Gaseous Sampling Attachment	Envirotech	APM - 411	4297 - DTC - 2011	

02. Details of DUC

Name	Rotameter	Environmental Conditions During Calibration		
Resolution	0.1 lpm	Temperature (°C) :- 25 ± 10 °C	29.6	
ID.No.	2000/820	Relative Humidity (%) :- 45-75 %	58	
Cal. Range / Range	0.5 - 3.0 lpm / 0 - 3.0 lpm	Barometric Pressure (mmHg)	740.20	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID. No.	Traceability
LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Laboratory, Mumbai
Certificate No.		Calibration Date	Valid Up to
PICAL/0922/F/032		05.09.2022	04.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC-07

Remark 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for Calibration Curve

2. The Flow Rate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida (U.P.)

Gr. Noida

**

Kasna **

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)





The state of the s	THE PARTY OF THE P	Page No 2 of 3
ULR No.	CC105123000000937F	
Calibration Date	03.08.2023	Suggested Date of Next Calibration 02.08.2024
Certificate No.	LES-CCL/FF/RF/SC/310	

05, Calibration Results for Flow of Rotameter

B.No.	(DUC) Indicated reading	Reference True Flow rate	Error (%) F8	Calibration Factor
	(lpm)	(lpm)	-0.800	1.048
1	0.5	0.524	-0.833	1.050
2	0.5	0.525	-0.867	1.052
3	0.5	0.526	-0.900	1.054
4	0.5	0.527	-0.933	1,056
5	0.5	0.528	-0.667	1.020
6	1.0	1.020	7/10/2007	1.020
7	1.5	1.530	-1.000	1.006
8	2.0	2.012	-0.400	1.015
9	2.5	2.538	-1.267	1.014
10	3.0	3.043	-1,433	1.014
11	3.0	3.042	-1,400	1.014
12	3.0	3.043	-1.433	1.015
13	3.0	3.044	-1.467	1.015
14	3.0	3.045	-1.500	urve Enclosed)

Type A standard Uncertainty

I. for repeated data (1-5)

0.0007 lpm

II. for repeated data (10-14)

0.0007 lpm

Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

I. 0.5 lpm

11.68 % Rdg

1.93 %FS or

II. 3.0 lpm

2.23 % Rdg ±

or

Gr. Noida

Kasna

2.15 %FS

Uncertainty Contributing Factor :-

- 1. Repeatability (based on five measurements)
- 2. Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = ∞ and confidence level is 95 % for Normal distribution.

Calibration Place: Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

Notes :-

1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greafer Nolda (U.P.) ES-Centre Co

2. Reference used are directly traceable to national standard through unbroken chain of calibration .

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)




ULR No. CC105123000000937F

Date of Calibration:- 03.08.2023

Page No. - 3 of 3

CALIBRATION CURVE FOR ROTAMETER



SI.No.	Reference	Test Piece	Name of the Instrument	Rotameter
Ollivo.	True Flow	Measured	SI.No. of the Instrument	2000/820
	Rate	Flow Rate	Name of the Party	M/s Prism Johnson Limited
	(lpm)	(lpm)		Village - Mankahari, P.O. Bathia,
1	0.526	0.5		Tehsil - Rampur Baghelan,
2	1.020	1.0		Distt. Satna - 485111 (M.P)
3	1.530	1.5		
4	2.012	2.0		
5	2.538	2.5		
6	3.043	3.0		

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.R.)

 2. Reference used are directly traceable to national standard through unbroken chain of calibration.

 3. Results reported are valid at the time of and under the stated conditions of measurement

 4. This Certificate refers only to the particular item calibrated.

 5. Decision rule required No

- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the Instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230000	000939F Cali, Field - Fluid Flow		Page No 1 of 3		
Certificate No.	LES-CCL/FF/RF/SC/3					
Calibration Date	03.08.2023	03.08.2023 Suggested Date of Next Calibration			02.08.2024	
Customer Name :- Address :-	Village - Mankahari, Tehsil - Rampur Bag	M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)				
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed At	Site	Condition of DUC	OK	
Location of Performance	for Calibration	On Site		•		

01. DUC Fitted in instrument

Name	Make	Model	SI.No.
Gaseous Sampling Attachment	Envirotech	APM - 411	1366 - DTC - 2011

02. Details of DUC

Name	Rotameter	Environmental Conditions During Calibration		
Resolution	0.1 lpm	Temperature (°C) :- 25 ± 10 °C 29.		
ID.No.	09/0232	Relative Humidity (%) :- 45-75 %	58	
Cal. Range / Range	0.5 - 3.0 lpm / 0 - 3.0 lpm	Barometric Pressure (mmHg)	740.20	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID. No.	Traceability
LFE Gas Flow Calibrator	0.5 - 50 lpm	0416 / LES-CCL/R/4901	PI Calibration Laboratory, Mumbai
Certificate No.		Calibration Date	Valid Up to
PICAL/0922/F/032		05.09.2022	04.09.2023

04. Calibration Procedure :- LES-CCL/WI/31/FF/SC-07

Remark 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for Calibration Curve

2. The Flow Rate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

er Noida (U.P.)
Authorized By

S-Centre

Gr. Noida

Kasna

SHIVSHANKER SINGH (Chief Executive Officer)

Scanned with CamScanner





	10040E422000000020E		Page No 2 of 3
ULR No.	CC105123000000939F	Suggested Date of Next Calibration	02.08.2024
Calibration Date	03.08.2023	Suggested Date of Next Campitation	
Certificate No.	LES-CCL/FF/RF/SC/312		

05. Calibration Results for Flow of Rotameter

S.No.	(DUC) Indicated reading	Reference True Flow rate	Error (%) FS	Calibration Factor
	(lpm)	(lpm)	0.867	0.948
1	0.5	0.474	0.833	0.950
2	0.5	0.475	0.800	0.952
3	0.5	0.476	0.767	0.954
4	0.5	0.477	0.733	0.956
5	0.5	0.478	1.233	0.963
6	1.0	0.963	-0.667	1.013
7	1.5	1.520	-0.667	1.010
8	2.0	2.020	0.600	0.993
9	2.5	2.482	1.833	0.982
	3.0	2.945	1.867	0.981
10	3.0	2.944	1.833	0.982
11	3.0	2.945	1.800	0.982
12	3.0	2.946	1.767	0.982
13 14	3.0	2.947	1.707 (Cu	rve Enclosed)

Type A standard Uncertainty

I. for repeated data (1-5)

0.0007 lpm

II. for repeated data (10-14)

0.0007 lpm

Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

I. 0.5 lpm

12.91 % Rdg

1.93 %FS or

II. 3.0 lpm

2.31 % Rdg

2.15 %FS OF

Kasna *

Uncertainty Contributing Factor:

- 1. Repeatability (based on five measurements)
- 2. Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Calibration Place:- Calibration done of M/s Prism Johnson Limited, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)




ULR No. CC105123000000939F

Date of Calibration:- 03.08.2023

CC-1051 Page No. - 3 of 3

CALIBRATION CURVE FOR ROTAMETER



			Name of the Instrument	Rotameter
SI.No.	Reference	Test Piece	Name of the instrument	09/0232
01.110.	True Flow		SI.No. of the Instrument	M/s Prism Johnson Limited
	3333	Flow Rate	Name of the Party	M/s Prism Johnson Emilied
	Rate			Village - Mankahari, P.O. Bathia,
	(lpm)	(lpm)		Tehsil - Rampur Baghelan,
1	0.476	0.5		Distt. Satna - 485111 (M.P)
2	0.963	1.0		
3	1.520	1.5		
4	2.02	2.0		
	2.482	2.5		
5	2.945	3.0		
6	2.945	0.0		

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P. 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05 2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

S-Centre Gr. Noida * Kasna

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.		3000000941F		on Field -	Page No 1 of 1	
Certificate No.	LES-CCL/MEC	CH/SLM/46	Mech	anical		
Calibration Date	03.08.2023	2023 Suggested Date of Next Calibration		02.08.2024		
Customer Name :-	M/s Prism Joh	nnson Limited				
Address :-	Village - Mank	Village - Mankahari, P.O. Bathia,				
	Tehsil - Ramp					
	Distt. Satna -					
				l. 5.4.	22.00.2022	
S.R.F No.	2023/17	S.R.F Date	22.07.2023	Issue Date	22.08.2023	
Date of DUC Receipt	03.08.2023	Calibration Performed	At Parmanent Lab.	Condition of DU	с ок	
Location of Performance	or Calibration	Laboratory				

01. Details of (DUC)

Name Sound Level Mete		Environmental Conditions During Calib	ration
Make	Cygnet	Temperature(°C) :- 23 ± 1.5 °C	23.4
SI.No.	A0905-276	Relative Humidity (%) :- 30-70 %	57
Model	2001	Barometric Pressure (mmHg)	735.10
Range / Resolution	30 - 130 dB / 0.1 dB		

02. Standard Equipment used for calibration

Standard Equipment Name	Range		Traceability
Sound Level Calibrator	94 dB, 114 dB	I.164109	IDEMI, MUMBAI
Certificate No.		tion Date	Valid Up to
CC/FCL/1626/22-23	16.0	1.2023	15.01.2024

LES-CCL/WI/31/MECH/03 03. Calibration Procedure :-

04. Calibration Results:

DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (dB)	Reference Value (dB)	Error (%Rdg)	Expanded Uncertainty at 95 % of Confidence level (k = 2)
-	93.4	93.6	-0.21	± 0.77 dB
2	113.6	113.8	-0.18	± 0.77 dB

Remark : The reading of DUC represent the Average, of five reading measurements.

Uncertainty Contributing Factor :- 1. Repeatability (based on five measurement) 2. Uncertainty of master instruments 3. Resulation of DUC The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Nolda (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna

(Chief Executive Officer)

Authorized By

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	ULR No. CC105123000000		Cali. Field - Fluid Flow		Page No 1 of 3
Certificate No. Calibration Date	LES-CCL/FF/RF/316 05.08.2023		Suggested Date of Next Calibration		04.08.2024
Customer Name :- Address :-	ustomer Name :- M/s Prism Johnson Limited ddress :- Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan,				
CDENO	Distt. Satna - 485111 (2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
S.R.F No. Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK

04 DUC Eitted in instrument

Location of Performance for Calibration

	01. DUC Fitted in instrument				
Γ	Name	Make	Model	SI.No. / ID.No.	
·ŀ	Stack Sampler	Envirotech Inst	APM - 620	988-DTD-14 / MSK/GDM/F/SMK-1	
- 1	Stack Salliplei	LITVII OLCOIT III St	7 11 111		

Laboratory

02. Details of DUC

OZ. Dotano o. Do	D 1 1	Environmental Conditions During Calibration	
Name	Rotameter	Environmental Conditions During Cumstance	25.6
Resolution	2.0 lpm	Temperature (°C) :- 25 ± 3 °C	
SI.No.	D21090	Relative Humidity (%) :- 45-75 %	58
			736.40
Cal. Range / Range	10 - 60 ipili / 0 - 60 ipili	Dai oniotito i 1000 m. c	

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	Sr.No. / ID. No.	Traceability	
51.NO.	Air Flow Calibrator	0.2 - 10.0 lpm	002-DTD-2015	PI Calibration Laboratory, Mumbai	
1		0 - 75 mmHg	Sr. No. 03	LES-CCL, Gr. Noida	
2	Digital Vacuum Indicator		T- 02	Calyss Calibration, Noida	
3	Digital Temp. Indicator	0 - 50°C		PI Calibration Laboratory, Mumbai	
4	Orifice Flow Calibrator	11- 100 lpm	001-DTD-2015		
SI.No.	Certificate No.		Calibration Date	Valid Up to	
1	PICAL/0922/F/033		05.09.2022	04.09.2023	
2	LES-CCL/MECH/PI/884	15.09.2022 08.06.2023			14.09.2023 07.06.2024
3	CCTPL/TI/0133/02			04.09.2023	
4	PICAL/0922/F/031		05.09.2022	04.09.2020	

04. Calibration Procedure :- LES-CCL/WI/31/FF/03 & 04

Remark: 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for calibration curve

2. The Flowrate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) Centre
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH Chief Executive Officer

Gr. Noida

Kasna *



LES-Centre for Calibration Laboratory



ULR No.	CC105123000000950F		Page No 2 of 3
		Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/FF/RF/316		

05. Calibration Results for Flow Rate of Rotameter

S.No.	Measured Flow Rate (DUC) Ipm	Reference True Flow Rate (lpm)	Error FS (%)	Calibration Factor
	10.0	9.844	0.260	0.984
			0.258	0.985
2	10.0	9.845	0.257	0.985
3	10.0	9.846	0.255	0.985
4	10.0	9.847	0.253	0.985
5	10.0	9.848	1.000	0.970
6	20.0	19.4	1,500	0.970
7	30.0	29.1	0.667	0.990
8	40.0	39.6	1.833	0.978
9	50.0	48.9	1.667	0.983
10	60.0	59.0	1.667	0.983
11	60.0	59.0	1.500	0.985
12	60.0	59.1		0.985
13	60.0	59.1	1.500	0.983
14	60.0	59.0	1.667 (Curve Enclose	

A. Type A standard Uncertainty

I. for repeated data (1-5) II. for repeated data (10-14) 0.0069 lpm 0.0233 lpm

B. Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

I. For 10.0 lpm

3.32 %Rdg

II. For 60.0 lpm

2.32 %Rdg

Uncertainty Contributing Factor:-

- 1.Repeatability (based on five measurements)
- 2.Uncertainty of master instruments,

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = ∞ and confidence level is 95 % for Normal distribution.

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) ES-Centre

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)


Gr. Noida



ULR No. CC105123000000950F Calibration Date 05.08.2023

CALIBRATION CURVE FOR ROTAMETER

Page No. - 3 of 3



SI.No.	True Flow	Measured	Name of the Instrument SI.No. of the Instrument Name of the Party	Rotameter D21090 M/s Prism Johnson Limited Village - Mankahari, P.O. Bathia,	
1 2	(lpm) 9.846 19.4	(lpm) 10.0 20.0 30.0		Tehsil - Rampur Baghelan,	
3 4 5 6	29.1 39.6 48.9 59.0	40.0 50.0 60.0			Authorized By

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) of Golibratio
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No

59.0

- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)





CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000951F	Call, Field - Fluid Flow	Page No 1 of 3	
Certificate No.	LES-CCL/FF/RF/317	Gam Fleid - Fluid Floid		
Calibration Date	05.08.2023	Suggested Date of Next Calibration		
Customer Name :-	M/s Prism Johnson Limited	AND A CONTRACTOR OF THE PARTY O		
Address :-	Village - Mankahari, P.O. Bathla,			

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/17	8.R.F. Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performance	STATE OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY.	Laboratory	· Andrews		

01. DUC Fitted in Instrument

Name	Make	Model	81.No.
Stack Sampler	Thermo	TEI - 130	165 - TEF - 21

02. Details of DUC

Name	Rotameter	Environmental Conditions During Calibration		
Resolution	0.2 lpm	Temperature (°C) :- 25 ± 3 °C	24.2	
SI.No.	S191045	Relative Humidity (%) :- 45-75 %	53	
Cal. Range / Range	1.0 - 6 lpm / 0 - 6 lpm	Barometric Pressure (mmHg)	736.40	

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No.	Traceability
1	Air Flow Calibrator	0.2 - 10.0 lpm	002-DTD-2015	Pl Calibration Laboratory, Mumbai
2	Digital Vacuum Indicator	0 - 75 mmHg	Sr. No. 03	LES-CCL, Gr. Nolda
3	Digital Temp. Indicator	0 - 50°C	T- 02	Calyss Calibration, Noida
SI.No.	Certificate No.	Calibration Date		Valid Up to
1	PICAL/0922/F/033	05.09.2022		04.09.2023
2	LES-CCL/MECH/PI/884	15.09.2022		14.09.2023
3	CCTPL/TI/0133/02	08.06.2023		07.06.2024

04. Calibration Procedure :- LES-CCL/WI/31/FF/04

Remark 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Nolda (U.P.)
- Reference used are directly traceable to national standard through unbroken chain of calibration .
- Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- Decision rule required No
- Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker Indicating CAL, STATUS in affixed on the Instruments

Authorized By

SHIVSHANKER SINGH

(Chief Executive Officer)

Gr. Noida



LES-Centre for Calibration Laboratory



ULR No.	CC105123000000	951F	Page No 2 of 3 04.08.2024
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.00.2024
Certificate No.	LES-CCL/FF/RF/317		

05. Calibration Results for Flow of Rotameter

(DUC) Indicated reading	Reference True Flow rate	Error (%)	Calibration Factor
(Ipm)	(lpm)		0.946
1.0	0.946		0.949
20.7030	0.949		0.950
100000000	0.950		0.951
	0.951		0.952
	0.952		0.981
	1.962		0.973
1 11-22-2	2.919		0.973
	3.892	\$25	0.988
	4.938	A TO THE RESERVE OF T	0.980
	5.881		0.980
1	5.881		0.980
1	5.882		0.981
ACCURATE TO A CONTRACT OF THE PARTY OF THE P	5.883		0.981
	5.884	1.933 /Cur	ve Enclosed)
	Indicated reading (Ipm)	Indicated reading (Ipm) (Ipm) (Ipm) (Ipm)	Indicated reading

Type A standard Uncertainty

I. for repeated data (1-5)

0.1091 lpm

II. for repeated data (10 - 14)

0.0117 lpm

Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

I. 1.0 lpm

5.84 % Rdg

0.07 %FS Or

5.84 % Rdg

-2.64 %FS OF

Kasna

II. 6.0 lpm

Uncertainty Contributing Factor:

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) Gr. N.

2. Reference used are directly traceable to national standard through unbroken chain of calibration .

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHAMKER SINGH (Chief Executive Officer)

Scanned with CamScanner




ULR No. CC105123000000951F Calibration Date 05.08.2023

(88)

CC-1051 Page No. - 3 of 3

CALIBRATION CURVE FOR ROTAMETER



SI.No.	Reference	Test Piece	Name of the Instrument	Rotameter
01.110.	True Flow	Measured	SI.No. of the Instrument	S191045
	Rate	Flow Rate	Name of the Party	M/s Prism Johnson Limited
	(lpm)	(lpm)		Village - Mankahari, P.O. Bathia,
1	0.950	0.5		Tehsil - Rampur Baghelan,
2	1.962	1.0		Distt. Satna - 485111 (M.P)
3	2.919	1.5		
4	3.892	2.0		
5	4.938	2.5		
6	5.882	3.0		

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****

Gr. Noida

Kasna *



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123	300000952F Cali, Field - Electro-Technical		Page No 1 of 1	
Certificate No.	LES-CCL/ET/S	SW/32			
Calibration Date	05.08.2023		Suggested Da	ate of Next Calibration	04.08.2024
Customer Name :-	M/s Prism Jol	nnson Limited			
Address :-		kahari, P.O. Bathia, our Baghelan, 485111 (M.P)			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performance f	for Calibration	Laboratory	-		

01. DUC Fitted in the Instruments

Name	Make	Model	SI.No.
Stack Sampler	Thermo	TEI - 130	165 - TEF - 21
Stack Sampler	Hiemo	121 100	

02. Details of DUC

Vame	Stop watch	Environmental Conditions During Calibration	
Name Make/Trade Mark	Racer	Temperature (°C) :- 25 ± 4 °C	27.4
Make/Trade Mark	SW - 165	Relative Humidity (%) :- 30-75 %	38.0
SI.No.	0 -15 min. / 0.01 Sec.	Barometric Pressure (mmHg)	734.50
Cal. Range / Resolution	0-15 mm. / 0.01 Sec.	Barometre resoure (mm-3)	

03. Standard Equipment used for calibration

Traceability
ses, Haridwar (Uttarakhand)
Valid Up to
09.03.2024
0

04. Calibration Procedure : LES-CCL/WI/31/ET/02

05. Calibration Results :-

DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	0	Standard reading Average five Measurements Time (min)	Error (%)	Expanded Uncertainty at 95 % of Confidence level (k =2) (sec)
	(min) 15.005	15.0028	0.015	± 4.53

Uncertainty Contributing Factors :- 1. Repeatability (based on five measurements)

- 2 Uncertainty of master instruments

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = ∞ and confidence

level is 95 % for Normal distribution.

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Norda (U.P.)

Reference used are directly traceable to national standard through unbroken chain of calibration.

- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4 This Certificate refers only to the particular item calibrated
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

Gr. Noida

Scanned with CamScanner

(Chief Executive Officer)

.... End of Calibration Certificate



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Nolda, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000953F		Call. Field - Mechanical	Page No 1 of 2
Certificate No.	LES-CCL/MECH/PI/25		Call. Field - Mechanical	rugo ito: Torz
Calibration Date	05.08.2023	Suggest	ted Date of Next Calibration	04.08.2024
Customer Name :-	M/s Prism Johnson Limited			

Address :-

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performan	ce for Calibration	Laboratory			

01. DUC Fitted in Instrument

Ī	Name	Make	Model	SI.No.
r	Velocty Monitor	Thermo	VSS - 1	47 - TEF - 21

02. Details of DUC

Name	Pressure Indicator	Environmental Conditions During Calib	ration
Make / Sl.No	Testo / PI - 165	Temperature(°C) :- 25 ± 1.5 °C	23.8
Model	Testo - 510	Relative Humidity (%) :- 30-70 %	53
Resolution	0.1 mmH ₂ O	Barometric Pressure (mmHg)	734.50
Cal. Range	0 - 1000 mmH₂O		

03 Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
Digital Pressure Gauge	0 - 2000 mmWC	VEM1503080 / LES-CCL/R/2503	GTCL, New Delhi
Certificate No.	* /	Calibration Date	Valid Up to
23061201-01		12.06.2023	11.06.2024

LES-CCL/WI/31/MECH/ 01 04. Calibration Procedure :-

Remark: Refer page 2 of 2 for Calibration Results

Notes :-1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

CS-Centro 2. Reference used are directly traceable to national standard through unbroken chain of calibration .

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

Our NABL certificate no. is CC-1051 valid up to 18.05.2025

Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

(Chief Executive Officer)

Gr. Noida



LES-CENTRE FOR CALIBRATIOB LABORATORY



ULR No.	CC105123000000953F		Page No 2 of 2
Calibration Date		Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/MECH/PI/25		

05.(A) Corrected Calibration Results for Pressure Indicator

Set (DUC)	CYC	LE 1		LE 2		LE 3	Standard	Error %	Expanded ± Uncertainty
Value	UP	DOWN	UP (mmH 0)	DOWN	UP (mmH₂0)	DOWN (mmH₂0)	Avg.Rdg. (mmH₂0)	/° (FS)	(mmH₂0)
(mmH₂0)	(mmH ₂ 0)	(mmH₂0)	(mmH₂0)	(mmH₂0)	1.0	4.1	2.6	-0.16	6.64
1.0	1.0	10.2	1.2	1.1	10.0	10.0	10.1	-0.01	4.69
10.0	10.1	9.9	100.1	100.0	100.9	100.6	100.3	-0.03	4.72
100.0	99.9	200.2	200.3	200.8	200.1	200.4	200.3	-0.03	4.69
200.0 400.0	400.1	400.2	400.3	400.2	400.1	400.2	400.2	-0.02	4.69
800.0	800.5	800.6	800.5	800.4	800.5	800.5	800.5	-0.05	4.69
1000.0	999 1	999.2	999.3	999.2	999.1	999.7	999.7	0.03	4.69
1000.0	05.(B) Correc	ted Calib	ration Re	sults for	Pressure	Indicator	r	(Pa) ↓
9.8	10.3	100.0	12.2	11.2	10.3	40.5	25.9	-1.61	65.1
	99.5	97.5	101.5	99.5	98.5	98.5	99.5	-0.14	46.0
98.1		988.6	981.5	980.6	989.6	986.3	983.4	-0.27	46.3
980.7	979.6		1964.7	1969.2	1962.7	1965.2	1964.4	-0.31	46.0
1961.3	1962.7	1963.7		3924.5	3923.6	3924.2	3924.4	-0.17	46.0
3922.7	3923.6	3924.5	3925.5			7850.2	7850.3	-0.50	46.0
7845.3	7850.2	7851.1	7850.2	7849.2	7850.2		9803.5	0.31	46.0
9806.7	9797.7	9798.7	9799.7	9798.7	9797.7	9803.4	3000.0		1.

Remark: The reading of Pressure represents the mean of six reading

Uncertainty Contributing Factors:-

- 1. Repeatability (based on 3 Cycles)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution. **Authorized By**

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna; Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna

Scanned with CamScanner

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site A, Kasna, Greater Noida, Gautam Budh Nagar - 2010/0 (15.5) E-mail: lesectivit@gmail.com, lesectivit@gmail.com, Call No. 551/154545, 552/175/17, 571/24/19 Wateria : www.lasecillab.com



CALIBRATION CERTIFICATE

	Christin	Tron Carlos		
ULR No.	CC105123000	0000955F	Calli, Flato - Machanical	944 No142
Certificate No.	LES-COLMECHIVO	3/41	THE RESERVE THE PROPERTY OF THE PERSON NAMED IN	1/19/1/1
Calibration Date	05.08.2023	Suggested Date of Next	Camp account	· ·
Customer Name :-	M/s Prism Johnson Village - Mankahar	n Limited n, P.O. Bathia,		

Village - Mankahan, P.O. Barna, Address >

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

			1 1111111111111111111111111111111111111	leaves trates	11:11:11
2554	2023/17	S.R.F. Data	This Tills	Contracted.	CX
S.R.F No. Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lat.	CANDIGON OF ITS	Colored all sections and the second
Location of Performance			and the same of th		Control Control Control

31,860 01. DUC Fitted in Instrument Merch 181-755-21 Make Name TEI - 132 Thermo Stack Sampler

02. Details of DUC	6-1016	Environmental Conditions During Calibration
lame	Vacuum Gauge (GAS)	Tomospistants (C) > Z5 Z 1.5
Aake	Akvalo	Palators Homitally (%) - or 15 %
	SVG - 185	Description Disability (MMM)
THE RESERVE AND ADDRESS OF THE PARTY OF THE	80 -500 mmHg / 0 - 780 mmHg 0-100 = 25 mmHg & 100-780 = 2	d) markly

Traceability
TO MEN CAKI
Valid Up to
11.08.2024
V VAPP CONT

04. Calibration Procedure > LES-CCL/M/31/MECH/02

Remark: Refer page 2 of 2 for Calibration Results

1. This certificate shall not be reproduced, except in full without the written permission of LES-CEL Kaspy, Casaser Norda (N.F.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration 3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

S. Decision rule required - No

6. Our NASI, certificate no. is CC-1551 valid up to 18.65 2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the indominants

Authorized By

Count & was dies " Hard



LES - Centre For Calibration Laboratory



ULR No.	CC105123000000955F		Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/MECH/VG/41		

05. Corrected Calibration Results for Vacuum Gauge (Sl. No. SVG-165)

							Ctondard	Error	Expende	d Uncertainty
Set DUC	CYC	LE 1	CYC	LE 2		LE 3	Standard	%	•	±
Value	UP	DOWN	UP	DOWN	UP		Avg.Reading	(FS)	(bar)	(mmHg)
(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	1.45	0.083	62.421
80	74.3	72.5	73.5	70.2	69.0	68.4	71.3			62.387
		100.4	102.7	99.8	99.8	104.9	102.6	-0.35	0.083	
100	102.5					200.3	199.3	0.09	0.083	62.392
200	199.0	198.7	198.8	196.9	202.3			0.48	0.083	62.379
300	296.0	295.1	299.4	295.2	297.0	295.7	296.4			62.439
			403.8	399.2	405.5	403.6	403.4	-0.45	0.083	
400	404.6	403.8		-		504.6	506.1	-0.80	0.083	62.393
500	507.6	505.7	505.7	503.9	509.2	304.0				

Remark:

The reading of vacuum represents the Average of five reading

Uncertainty Contributing Factor

- 1. Repeatability (based on 3 Cycle)
- 2.Uncertainty of master instruments
- 3.Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom ≂∞ and confidence level is 95 % for Normal distribution.

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) S-Centre
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration. 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

Gr. Noida

Kasna

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000954F		Cali. Field - Mechanical	Page No 1 of 2
Certificate No.	LES-CCL/MECH/VG	LES-CCL/MECH/VG/40		04.00.0004
Calibration Date	05.08.2023	Suggested Date of Next	Calibration	04.08.2024

Customer Name:-

M/s Prism Johnson Limited

Address :-

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/28	S.R.F. Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt		Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performan					

01 DUC Fitted in Instrument

01. DOOT Itted III IIIstrament				- 1
Name	Make	Model	SI.No.	\dashv
Stack Sampler	Thermo	TEI - 130	165 - TEF - 21	
I Stack Sallible I				

02 Details of DUC

Name Vacuum Gauge (SPM)		Environmental Conditions During Calibration			
	Akvalo	Temperature (°C) :- 23 ± 1.5 °C	25.3		
Make SI.No.	GVG - 165	Relative Humidity (%) :- 30-70 %	53		
		Barometric Pressure (mmHg)	746.20		
	0-100 = 25 mmHg & 100-760 = 20 mmHg				

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
Digital Vacuum Gauge	-1.0 to 2 bar	VEM1503079 / LES-CCL/R/2504	GTCL, New Delhi
Certificate No.	Calibr	ation Date	Valid Up to
23061201-02	12.0	06.2023	11.06.2024

04. Calibration Procedure :- LES-CCL/WI/31/MECH/02

Remark: Refer page 2 of 2 for Calibration Results

Notes :-	d, except in full without the written permisson of LES-CC	Call
	d except in full without the written permisson of LES-CC	L.Kasna, Greater Noida (U.P.
1 .This certificate shall not be reproduce	J, except in fair without the miner permission	0

1. This certificate shall not be reproduced, except in the standard through unbroken chain of calibration 2. Reference used are directly traceable to national standard through unbroken chain of calibration 3. Results reported are valid at the time of and under the stated conditions of measurement

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the Instruments

Authorized By

(Chief Executive Officer)



LES - Centre For Calibration Laboratory



ULR No.	CC105123000000954F		Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/MECH/VG/40		

05. Corrected Calibration Results for Vacuum Gauge (SI. No. GVG- 165)

Set DUC	CYC	LE 1	CYC	LE 2	CYC	LE 3	Standard	Error	Expende	d Uncertainty
Value	UP	DOWN	UP	DOWN	UP	DOWN	Avg.Reading	%		±
(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(FS)	(bar)	(mmHg)
80	81.2	78.8	81.9	78.0	82.7	80.0	80.4	-0.07	0.083	62.463
100	101.3	100.3	101.4	100.3	100.3	103.3	101.9	-0.25	0.083	62.372
200	203.0	278.0	202.4	202.4	199.2	200.1	214.2	-1.87	0.099	74.290
300	294.2	293.8	296.6	294.8	300.2	298.5	296.3	0.48	0.083	62.391
400	405.6	401.7	402.3	399.6	406.2	404.5	403.3	-0.44	0.083	62.462
500	501.9	501.9	499.9	499.4	499.2	500.0	500.4	-0.05	0.083	62.359

Remark:

The reading of vacuum represents the Average of five reading

Uncertainty Contributing Factor

- 1. Repeatability (based on 3 Cycle)
- 2. Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC
- 4. Uncertainty due to hystersis,

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.)

 2. Reference used are directly traceable to national standard through unbroken chain of calibration.

 3. Results reported are valid at the time of and under the stated conditions of measurement

 4. This Certificate refers only to the particular item calibrated.

 5. Decision rule required No

- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****

Kasna *



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230	CC105123000000956F Calibration Field - Thermal		Page No 1 of 2	
Certificate No.	LES-CCL/TH/TF		- Cambration - Total		
Calibration Date	05.08.2023	Suggested Da	ate of Next Calibration	04.08.2024	

Customer Name :-

M/s Prism Johnson Limited

Address :-

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F. No.	2023/17	S.R.F. Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performanc	e for Calibration	Laboratory			

04 DUC Fitted in instrument

	of. Doc Fitted in his	unient		
Γ	Name	Make	Model	SI. No.
H			TEI - 132	47 - TEF - 21
- 1	Velocty Manitor	Thermo	161-102	

02 Details of DUC

Name	Thermocouple with Temperature Indic	ator Environmental Conditions During Cali	bration
Name	Audiotronics	Temperature (°C) :- 25 ± 4 °C	24.6
Make/Trade Mark	TP - 165	Relative Humidity (%) :- 30-75 %	56.0
SI.No.	50 - 600 °C / 0 - 600 °C	Barometer Pressure (mmHg)	739.65
Cal. Range / Range	30 - 000 C / 0 - 000 C		
Resolution	1 0		

Standard Equipment used for calibration

3. Standard Equipment document	Range	SI.No.	Traceability
Standard Equipment Name		YD5002383	Calyss Calibration, Noida
Digital Thermometer with R - Type T/C		bration Date	Valid Up to
Certificate No.		08.06.2023	07.06.2024
CCTPL/DTM/0133/03		0.00.202	

LES-CCL/WI/31/TH/01 04. Calibration Procedure :-

Remark: Refer page 2 of 2 for Calibration Results.

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noidà (U.P.) S-Centre
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- Decision rule required No
- Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

Chief Executive Officer)

Gr. Noida



LES - Centre For Calibration Laboratory



ULR No.	CC10512300000	U930F	Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/TH/TP/22	=	

05. Corrected Calibration Results for Thermocouple with Temperature Indicator

S.No.	Device Under Calibration (^O C)	Std.Reading (°C)	Error FS (%)	Calibration Factor	at 95	nded Uncertainty % of Confidence rel (k =2) (°C)
	48	49.9	-0.32	1.039	±	1.91
		100.8	-0.30	1.018	±	1.91
2	99			1.007	±	1.92
3	197	198.5	-0.25	STATE OF THE STATE	-	2.12
	297	298.2	-0.20	1.004	±	
4			-0.29	1.004	±	1.95
5	397	398.7		4.004	±	2.01
6	497	498.8	-0.31	1.004	1	
	595	597.3	-0.38	1.004	±	2.04

Remark: The Reported value is Average of ten readings.

Uncertainty Contributing Factor:-

- 1.Repeatability (based on ten measurement)
- 2.Uncertainty of Master Instruments
- 3.Resulation of DUC
- 4. Drift of Master Thermocouple

The evaluated Expanded Uncertainty in calibration at a coverage factor $k \cong 2$,

for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- Decision rule required No
- Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida

Authorized By

SHIV SHÁNKAR SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No. Certificate No.	CC10512300 LES-CCL/FF/PT/38		Cali. Field -	Fluid Flow	Page No 1 of 2
Calibration Date	05.08.2023	Sugge	sted Date of Nex	t Calibration	04.08.2024
Customer Name :- Address :-	M/s Prism Johnso Village - Mankaha Tehsil - Rampur B Distt. Satna - 4851	ri, P.O. Bathia, aghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DL	JC OK
Location of Performance	for Calibration	Laboratory			

01. Details of DUC

Name	S -TYPE PITOT TUBE	Environmental Conditions During Calibration	
	0.6+0.6 mrt	Temperature (°C) :- 25 ± 3 °C	25.4
Length	PT - 47	Relative Humidity (%) :- 45-75 %	56.0
SI.No Cal. Range	3 - 20 m/sec	Barometric Pressure (mmHg)	734.75

02. Standard Equipment used for calibration

	Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
51.No.	S -Type Pitot Tube	3 to 25 m/s	V626 / LES-CCL/R/12101	Enviro Instruments, Gr. Noida
	•	0 - 100 mmwc	VEM153080 / LES-CCL/R/2503	GTCL, New Delhi
3	Digital Pressure Gauge Dig.Temp.Indicator With Sensor		T- 01 / LES -CCL/R/15301	Calyss Calibration, Noida
	Certificate No.	Calibration Date		Valid Up to
			30.11.2022	29.11.2023
1	EI/FF/4670			11.06.2024
2	23061201-01		12.06.2023	
3	CCTPL/TI/0133/01		08.06.2023	07.06.2024

03. Calibration Procedure :-

LES-CCL/WI/31/FF/06

Remark 1. Refer page 2 of 2 for Calibration Results.

2. The Velocity has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Norda (U.P.) Centre

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida



LES-Centre for Calibration Laboratory



ULR No.	CC105123000000957F		Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/FF/PT/38		

04. CALIBRATION OBSERVATIONS AND RESULTS FOR S - TYPE PITOT TUBE

S.No.	Standard 'S' Type Pitot Tube K = 0.8668		'S' Type Pitot Tub (DUC)	e
	Dynamic Pressure (mmwc)	Air Velocity (m/s)	Dynamic Pressure (mmwc)	Factor K
1	0.85	3.392	0.8	0.8973
2a	6.74		5.1	
2b	6.73		5.4	
2c	6.70	10.179	5.6	0.9561
2d	6.76		5.7	
2e	6.74		5.7	
2f	6.79		5.8	
3	13.95	13.999	12.5	0.9144
4	23.06	17.302	22.4	0.8788
5	31.16	20.132	30.3	0.8797
			Averaged Coefficient (K)	0.9053

Remark: The reading of dynamic pressure represents the mean of 6 reading.

Type A standard Uncertainty Repeted Data Srial No. (2a to 2f)

0.0084 m/s

0.2030 m/s

Expanded uncertainty in Actual flow

Measurement at 95 % calibration at a coverage factor (k=2)

Uncertainty Contributing factor:-

- 1.Repeatability (based on three measurement)
- 2.Uncertainty of master instruments
- 3. Resulation Of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna Greater Noise (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

S-Centre Gr. Noida

or

Authorized By

9.9 % Rdg

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000942F	Cali. Field - Fluid Flow	Page No 1 of 3
Certificate No.	LES-CCL/FF/RF/314		04.08.2024
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.06.2024
Customer Name :-	M/s Prism Johnson Limited		

Address :-

Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

22.08.2023 Issue Date 22.06.2023 S.R.F Date 2023/17 S.R.F No. OK Parmanent Lab. | Condition of DUC Calibration Performed At 05.08.2023 Date of DUC Receipt Location of Performance for Calibration Laboratory

04 DUC Fitted in instrument

UI. DOC I Itted III IIIsti	unioni			
Name	Make	Model	SI.No.	
Ivaille	Wake	moue.	000 DTC 00	- 1
Stack Sampler	Vavubodhan	VSS:- 1	623 - DTG - 09	

02 Details of DUC

	- : 0 !!! - 4!	
Rotameter		00.0
1.0 lpm / Flow star	Temperature (°C) :- 25 ± 3 °C	23.6
	Relative Humidity (%) :- 45-75 %	56
		734.50
	1.0 lpm / Flow star E9B090	1.0 lpm / Flow star Temperature (°C) :- 25 ± 3 °C

03. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	Sr.No. / ID. No.	Traceability
1	Air Flow Calibrator	0.2 - 10.0 lpm	002-DTD-2015	PI Calibration Laboratory, Mumbai
2	Digital Vacuum Indicator	0 - 75 mmHg	Sr. No. 03	LES-CCL, Gr. Noida
	Digital Vacuum maioator Digital Temp. Indicator	0 - 50°C	T- 02	Calyss Calibration, Noida
3	Orifice Flow Calibrator	11- 100 lpm	001-DTD-2015	PI Calibration Laboratory, Mumbai
4		11 100 гр	Calibration Date	Valid Up to
SI.No.		05.09.2022		04.09.2023
1	PICAL/0922/F/033	15.09.2022		14.09.2023
2	LES-CCL/MECH/PI/884	08.06.2023		07.06.2024
3	CCTPL/TI/0133/02			04.09.2023
4	PICAL/0922/F/031	100 mm 1 mm 1 mm	05.09.2022	04.03.2020

04. Calibration Procedure :- LES-CCL/WI/31/FF/03 & 04

Remark: 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for calibration curve

2. The Flowrate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

1. This certificate shall not be reproduced, except in full without the written permission.

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement.

- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida



LES-Centre for Calibration Laboratory



ULR No.	CC105123000000942F		Page No 2 of 3
		Suggested Date of Next Calibration	04.08.2024
	LES-CCL/FF/RF/314		

05. Calibration Results for Flow Rate of Rotameter

S.No.	Measured Flow Rate	Reference True Flow Rate (Ipm)	Error FS (%)	Calibration Factor
	(DUC) Ipm		0.100	0.994
1	5.0	4.970	0.097	0.994
2	5.0	4.971	0.093	0.994
3	5.0	4.972		0.995
4	5.0	4.973	0.090	0.995
5	5.0	4.974	0.087	0.989
	10.0	9.886	0.380	0.980
6	15.0	14.7	1.000	
7		19.5	1.667	0.975
8	20.0	24.1	3.000	0.964
9	25.0		2.333	0.977
10	30.0	29.3	2.333	0.977
11	30.0	29.3	2.000	0.980
12	30.0	29.4	2.000	0.980
	30.0	29.4		0.977
13 14	30.0	29.3	2.333 (Curve Enclos	

A. Type A standard Uncertainty

I. for repeated data (1-5) - 5 lpm

0.0061 lpm 0.0234 lpm

II. for repeated data (10-14) - 30 lpm

B. Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

I. For 5 lpm

11.86 %Rdg

-8.14 %FS or

II. For 30 lpm

2.3 %Rdg

2.18 %FS or

Uncertainty Contributing Factor:-

- 1.Repeatability (based on five measurements)
- 2.Uncertainty of master instruments,

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for

Normal distribution.

Notes :-

S-Centre

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) 2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker Indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida




ULR No. CC105123000000942F Calibration Date 05.08.2023

CALIBRATION CURVE FOR ROTAMETER



Page No. - 3 of 3



SI.No.	Reference	Test Piece	Name of the Instrument	Rotameter
			SI.No. of the Instrument	E9B090
	Rate	Flow Rate	Name of the Party	M/s Prism Johnson Limited
	(lpm)	(lpm)		Village - Mankahari, P.O. Bathia,
1	4.972	5.0		Tehsil - Rampur Baghelan,
2	9.886	10.0		Distt. Satna - 485111 (M.P)
3	14.7	15.0		Short and the Market and the State of the St
4	19.5	20.0		
5	24.1	25.0		
6	29.3	30.0		

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida (U.P.)

Kasna **

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lescci307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-105

CALIBRATION CERTIFICATE

	WILLIAM TO THE TOTAL		
ULR No.	CC105123000000943F	Call. Field - Fluid Flow	Page No 1 of 3
Certificate No.	LES-CCL/FF/RF/315	Suggested Date of Next Calibration	04.08.2024
Calibration Date	05.08.2023	Suggested Date of Next Camping	

Customer Name :-

M/s Prism Johnson Limited

Address :-

Village - Mankahari, P.O. Bathla,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

			T 00 00 0023	Issue Date	22.08.2023
S.R.F No.	2023/17	S.R.F. Date	ZZ.UU.ZUZU	Condition of DUC	ОК
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of Dec	
Land Dorformano	e for Calibration	Laboratory			

Clittad in instrument

01. DUC Fitted in instrument		Model	SI.No.
Name	Mako	Model	623 - DTG - 09
Stack Sampler	Vayubodhan	VSS - 1	023-010-00

Detalle of DUC

02. Details of DUC		Environmental Conditions During Calibration	
Name	Rotameter	Environmental Conditions During Cumput	24.2
Resolution		Temperature (°C) :- 25 ± 3 °C	53
		Relative Humidity (%) :- 45-75 %	736.40
SI.No.	0.5 - 3 lpm / 0 - 3 lpm	Barometric Pressure (mmHg)	730,40
Cal. Range / Range	0.5 - 3 lpm / 0 - 3 lpm	Barometric Probotic (mm-g)	

03. Standard Equipment used for calibration

03. Star	ndard Equipment used for	Calibration	SI.No.	Traceability
SI.No.	Standard Equipment Name	Range		PI Calibration Laboratory, Mumbai
1	Air Flow Calibrator	0.2 - 10.0 lpm	002-DTD-2015	LES-CCL, Gr. Noida
<u> </u>	Digital Vacuum Indicator	0 - 75 mmHg	Sr. No. 03	
		0 - 50°C	T- 02	Calyss Calibration, Noida
3	Digital Temp. Indicator		alibration Date	Valid Up to
SI.No.	Certificate No.		05.09.2022	04.09.2023
1	PICAL/0922/F/033			14.09.2023
2	LES-CCL/MECH/PI/884		15.09.2022	07.06.2024
3	CCTPL/TI/0133/02		08.06.2023	01.00.2021

04. Calibration Procedure :- LES-CCL/WI/31/FF/04

Remark 1.Refer page 2 of 3 for Calibration Results and 3 of 3 for Calibration Curve

2. The Flowrate has been Referenced to Standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration .

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. Is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

C.

Gr. Noida



LES-Centre for Calibration Laboratory



ULR No.	CC105123000	000943F	Page No 2 of 3
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/FF/RF/31		

05. Calibration Results for Flow of Rotameter

S.No.	(DUC) Indicated reading (Ipm)	Reference True Flow rate (Ipm)	Error (%) FS	Calibration Factor
1	0.5	0.471	0.967	0.942
2	0.5	0.472	0.933	0.944
3	0.5	0.472	0.900	0.946
4	0.5	0.475	0.833	0.950
5	0.5	0.476	0.800	0.952
6	1.0	0.965	1.167	0.965
7	1.5	1.442	1.933	0.961
8	2.0	1.962	1.267	0.981
9	2.5	2.460	1.333	0.984
10	3.0	2.928	2.400	0.976
11	3.0	2.927	2.433	0.976
12	3.0	2.928	2.400	0.976
13	3.0	2.929	2.367	0.976
14	3.0	2.930	2.333	0.977

(Curve Enclosed)

Type A standard Uncertainty

I. for repeated data (1-5)

± 0.2551 lpm

II. for repeated data (10 - 14)

± 0.0528 lpm

Expanded uncertainty in Actual flow measurement at 95% as a coverage factor k=2

I. 0.5 lpm

± 5.84 % Rdg

29.79 %FS

II. 3.0 lpm

± 5.84 % Rdg

or or

Gr. Noida

Kasna

30.13 %FS

Uncertainty Contributing Factor:-

- 1. Repeatability (based on five measurements)
- 2.Uncertainty of master instruments
- 3.Resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. (California) Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the Instruments

Authorized By


SHIVSHANKER SINGH


(Chief Executive Officer)



ULR No. CC105123000000943F Calibration Date 05.08.2023

CALIBRATION CURVE FOR ROTAMETER





OL No.	Reference	Test Piece	Name of the Instrument	Rotameter
SI.No.	True Flow	Measured	SI.No. of the Instrument	
	Rate	Flow Rate	Harrie or the real	M/s Prism Johnson Limited
	(lpm)	(lpm)		Village - Mankahari, P.O. Bathia,
1	0.473	0.5		Tehsil - Rampur Baghelan,
2	0.965	1.0		Distt. Satna - 485111 (M.P)
3	1.442	1.5		
4	1.962	2.0		
5	2.460	2.5		
6	2.928	3.0		

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL trasne, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration. 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the instruments

Gr. Noida

Kasna

Authorized By

(Chief Executive Officer)

••••End of Calibration Certificate••••



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Nolda, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939
Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123	3000000944F	Cali. Field - Electro-Technical		Page No 1 of 1	
Certificate No.	LES-CCL/ET/S	SW/31				
Calibration Date	05.08.2023		Suggested Da	ate of Next Calibration	04.08.2024	
Customer Name :-	M/s Prism Jol	nnson Limited				
Address :-	Village - Mank Tehsil - Ramp Distt. Satna -					
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023	
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	ОК	
Location of Performance f	or Calibration	Laboratory	•			

01. DUC Fitted in the Instruments

Name	Make	Model	SI.No.	
Stack Sampler	Vayubodhan	VSS - 1	623 - DTG - 09	

02. Details of DUC

Name	Stop watch	Environmental Conditions During Calibration		
Make/Trade Mark	Racer	Temperature (°C) :- 25 ± 4 °C	27.4	
SI.No.	SW - 623	Relative Humidity (%) :- 30-75 %	38.0	
Cal. Range / Resolution	0 -15 min. / 0.01 Sec.	Barometric Pressure (mmHg)	734.50	

03. Standard Equipment used for calibration

Standard Equipment Name	Range	ID.No.	Traceability
Digital Automatic Timer	10 Sec - 4 hrs	LES-CCL/R/2507	Pooja Enterprises, Haridwar (Uttarakhand)
Calibration Certificate N	lo.	Calibration Date	Valid Up to
PE23CC01370		10.03.2023	09.03.2024
04. Calibration Procedure:	LES-CCL/WI/3	1/ET/02	

05. Calibration Results :-

DUC has been calibrated for following Parameter (S) ranges (S)

S.No.	Displayed Value on DUC (min)	Standard reading Average five Measurements Time (min)	Error (%)	Expanded Uncertainty at 95 % of Confidence level (k =2) (sec)
1	15.004	15.0026	0.009	± 4.53

Uncertainty Contributing Factors :- 1. Repeatability (based on five measurements)

- 2. Uncertainty of master instruments
- 3.Resolation of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom = ∞ and confidence level is 95 % for Normal distribution.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (UP)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Gr. Noida Kasna * Kasna *

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939

Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC105123000000945F	Cali. Field - Mechanical	Page No 1 of 2
Certificate No.	LES-CCL/MECH/PI/24		
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024

Customer Name :-

M/s Prism Johnson Limited

Address :-

Village - Mankahari, P.O. Bathia, Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performance	e for Calibration	Laboratory			

01. DUC Fitted in Instrument

Г	Name	Make	Model	SI.No.
	Stack Sampler	Vayubodhan	VSS - 1	623 - DTG - 09

02. Details of DUC

Name	Pressure Indicator	Environmental Conditions During Calibration		
Make	Testo	Temperature(°C) :- 25 ± 1.5 °C	23.8	
Model	Testo - 510	Relative Humidity (%) :- 30-70 %	53	
Resolution	0.1 mmH ₂ O	Barometric Pressure (mmHg)	734.50	
Cal. Range	0 - 1000 mmH ₂ O			

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
Digital Pressure Gauge	0 - 2000 mmWC	VEM1503080 / LES-CCL/R/2503	GTCL, New Delhi
Certificate No.		Calibration Date	Valid Up to
23061201-01		12.06.2023	11.06.2024

04. Calibration Procedure :- LES-CCL/WI/31/MECH/ 01

Remark: Refer page 2 of 2 for Calibration Results

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida



LES-CENTRE FOR CALIBRATIOB LABORATORY



ULR No.	CC105123000000945F		Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/MECH/PI/24		

05.(A) Corrected Calibration Results for Pressure Indicator

Set (DUC)	CYC	LE 1	CYC	CLE 2	CYC	CLE 3	Standard	Error	Expanded
Value	UP	DOWN	UP	DOWN	UP	DOWN	Avg.Rdg.	%	± Uncertainty
(mmH ₂ 0)	(mmH ₂ 0)	(mmH ₂ 0)	(mmH₂0)	(mmH ₂ 0)	(mmH₂0)	(mmH₂0)	(mmH₂0)	(FS)	(mmH₂0)
1.0	0.7	10.2	0.8	0.7	0.5	3.8	2.3	-0.13	6.77
10.0	9.4	9.3	9.6	9.5	9.4	9.4	9.5	0.05	4.69
100.0	98.9	99.8	99.1	99.0	99.9	99.6	99.3	0.07	4.72
200.0	198.1	198.0	198.3	198.8	198.1	198.3	198.3	0.17	4.69
400.0	398.7	398.6	398.9	398.8	398.7	398.7	398.7	0.13	4.69
800.0	799.2	799.1	799.4	799.2	799.1	799.1	799.2	0.08	4.69
1000.0	998.1	998.0	998.3	998.2	999.1	998.9	998.8	0.12	4.71
1000.0	05.0	3) Correc		ration Re	sults for	Pressure	Indicator		(Pa) ↓
0.0	7.3	100.0	8.3	7.3	5.4	37.6	22.4	-1.26	66.4
9.8	92.6	91.7	94.6	93.6	92.6	92.6	93.1	0.49	46.0
98.1		978.8	971.7	970.8	979.8	976.4	973.6	0.71	46.3
980.7	969.8		1945.0	1949.6	1943.1	1944.9	1944.5	1.68	46.0
1961.3	1943.1	1942.1	3911.8	3910.8	3909.8	3909.8	3910.3	1.23	46.0
3922.7	3909.8	3908.9		7837.4	7836.4	7836.8	7837.6	0.77	46.0
7845.3	7837.4	7836.4	7839.4		9797.7	9796.2	9795.0	1.16	46.1
9806.7	9787.9	9786.9	9789.9	9788.9	3737.1	0,00,2			

Remark: The reading of Pressure represents the mean of six reading

Uncertainty Contributing Factors:-

- Repeatability (based on 3 Cycles)
- 2.Uncertainty of master instruments 3. Uncertainty due to resolution of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Nolda (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker Indicating CAL, STATUS in affixed on the Instruments

S-Centro Gr. Noida **Authorized By**

SHIVSHANKER SINGH (Chief Executive Officer)

****End of Calibration Certificate****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

	w			
ULR No.	CC105123000	0000946F	Cali. Field -	Page No 1 of 2
Certificate No.	LES-CCL/MECH/VG		Mechanical	
Calibration Date	05.08.2023	Suggested Date of Next	Calibration	04.08.2024

Customer Name :-

Address :-

M/s Prism Johnson Limited

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F No.	2023/28	S.R.F. Date	22.00.2020	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performan	ce for Calibration	Laboratory			

01 DUC Fitted in Instrument

OI. DOO I ILLOG III III DII GIII				- 1
Name	Make	Model	SI.No.	\dashv
Stack Sampler	Vayubodhan	VSS - 1	623 - DTG - 09	
I Stack Sampler I	v u j u b o u i u i i			

02 Details of DUC

UZ. Details of Dec	Veenum Cougo (SPM)	Environmental Conditions During Calibration			
Name	Vacuum Gauge (SPM)	Temperature (°C) :- 23 ± 1.5 °C	25.3		
Make	Manometer		53		
SI.No.	GVG - 623	Relative Humidity (%) :- 30-70 %	746.20		
Cal. Range / Range	80 -500 mmHg / 0 - 760 mmHg	Barometric Pressure (mmHg)	740.20		
Resolution	0-100 = 25 mmHg & 100-760 = 20 mmHg				

03 Standard Equipment used for calibration

Standard Equipment Name	Range SI.No. / ID.No.		Traceability	
Digital Vacuum Gauge	-1.0 to 2 bar	VEM1503079 / LES-CCL/R/2504	GTCL, New Delhi	
Certificate No.	Calibr	Valid Up to		
23061201-02	12.0	06.2023	11.06.2024	

04. Calibration Procedure :- LES-CCL/WI/31/MECH/02

Remark: Refer page 2 of 2 for Calibration Results

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) S-Centror

2. Reference used are directly traceable to national standard through unbroken chain of calibration.

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida



LES - Centre For Calibration Laboratory



ULR No.	CC105123000000946F		Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/MECH/VG/38		

05. Corrected Calibration Results for Vacuum Gauge (SI. No. GVG-623)

Set DUC	CYC	LE 1	CYC	LE 2	CYC	LE 3	Standard	Error	Expende	d Uncertainty
Value	UP	DOWN	UP	DOWN	UP	DOWN	Avg.Reading	%		±
(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(FS)	(bar)	(mmHg)
80	81.2	79.1	80.7	80.2	82.7	81.5	80.9	-0.15	0.083	62.376
100	97.4	96.7	93.5	92.2	92.2	93.3	94.7	0.69	0.083	62.379
200	178.3	177.2	178.9	175.3	177.8	176.6	177.4	2.98	0.083	62.402
300	310.6	309.0	313.2	311.6	315.0	314.0	312.2	-1.61	0.083	62.385
400	399.6	399.0	403.3	400.8	405.6	400.9	401.5	-0.20	0.083	62.456
500	503.2	502.3	498.5	497.1	502.4	500.6	500.7	-0.09	0.083	62.387

Remark:

The reading of vacuum represents the Average of five reading

Uncertainty Contributing Factor

- 1. Repeatability (based on 3 Cycle)
- 2.Uncertainty of master instruments
- 3. Uncertainty due to resolution of DUC
- 4. Uncertainty due to hystersis,

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****

Gr. Noida



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CALIBRATION CERTIFICATE

•			
CC105123000	0000947F	Cali. Field -	Page No 1 of 2
LES-CCL/MECH/VC	G/39		
05.08.2023	Suggested Date of Next	Calibration	04.08.2024
	LES-CCL/MECH/V	CC105123000000947F LES-CCL/MECH/VG/39 05.08.2023 Suggested Date of Next (LES-CCL/MECH/VG/39 Mechanical Mechanical

Customer Name :-

M/s Prism Johnson Limited

Address :-

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

	2022/47	S.R.F. Date	22.06.2023	Issue Date	22.08.2023
S.R.F No.	2023/17		22.00.2020		ОК
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of Doo	-
Location of Performan	ce for Calibration	Laboratory			

04 DUC Fitted in Instrument

01. DOC 1 itted in instrument			lot Ma	- 1	
	Name	Make	Model	SI.No.	-
-	Name		1/00 4	623 - DTG - 09	- 1
	Stack Sampler	Vayubodhan	VSS - 1	623 - DTG - 03	
	Stack Sample	Vajaboanan			

02 Details of DUC

UZ. Details of Doc		Environmental Conditions During C	Calibration	
Name	Vacuum Gauge (GAS)	Environmental conditions 24 mg	25.3	
	Manometer	Temperature (°C) :- 23 ± 1.5 °C	100,000,000,000,000,000,000,000,000,000	
Make		Relative Humidity (%) :- 30-70 %	53	
SI.No.	SVG - 623		734.50	
Cal. Range / Range	80 -500 mmHg / 0 - 760 mmHg	Barometric Pressure (mmHg)	104.00	
Resolution	0-100 = 25 mmHg & 100-760 = 20 mmHg			

03. Standard Equipment used for calibration

. Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
Standard Equipment Name Digital Vacuum Gauge	-1.0 to 2 bar	VEM1503079 / LES-CCL/R/2504	GTCL, New Delhi
<u> </u>	Calibration Date 12.06.2023		Valid Up to
Certificate No.			11.06.2024
23061201-02			

04. Calibration Procedure :- LES-CCL/WI/31/MECH/02

Remark: Refer page 2 of 2 for Calibration Results

1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL Kasna Greater Noida (U.P.)

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement

This Certificate refers only to the particular item calibrated.

Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

7. Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida



LES - Centre For Calibration Laboratory



ULR No.	CC10512300000094	/F	Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/MECH/VG/39		

05. Corrected Calibration Results for Vacuum Gauge (Sl. No. SVG- 623)

Set DUC	CYC	LE 1	CYC	LF 2	CYC	LE 3	Standard	Error	Expende	d Uncertainty
Value	UP	DOWN	UP	DOWN	UP		Avg.Reading	%		± (
(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(mmHg)	(FS)	(bar)	(mmHg)
,	73.0	70.5	74.3	72.8	75.2	71.9	73.0	1.17	0.083	62.427
80			72.75.79.79				102.8	-0.37	0.083	62.393
100	102.8	100.6	104.3	104.4	104.4	99.8				62.394
200	187.5	185.8	184.6	183.2	182.0	181.1	184.0	2.10	0.083	
	304.2	303.0	304.6	303.4	307.8	306.2	304.8	-0.64	0.083	62.374
300							409.9	-1.30	0.083	62.402
400	411.6	410.0	407.8	406.8	412.5	410.4				62.386
500	505.2	504.2	510.4	508.4	507.9	506.0	507.0	-0.92	0.083	02.300

Remark:

The reading of vacuum represents the Average of five reading

Uncertainty Contributing Factor

- 1. Repeatability (based on 3 Cycle)
- 2.Uncertainty of master instruments
- 3.Uncertainty due to resolution of DUC
- 4. Uncertainty due to hystersis,

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****

* Kasna



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230	00000948F	Calibration Field - Thermal	Page No 1 of 2	
Certificate No.	rtificate No. LES-CCL/TH/TP/21				
Calibration Date	05.08.2023	Suggested Date of Next Calibration		04.08.2024	

Customer Name :-

Address :-

M/s Prism Johnson Limited

Village - Mankahari, P.O. Bathia,

Tehsil - Rampur Baghelan, Distt. Satna - 485111 (M.P)

S.R.F. No.	2023/17	S.R.F. Date	22.06.2023	Issue Date	22.08.2023
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
Location of Performanc	e for Calibration	Laboratory			

01. DUC Fitted in instrument

Name	Name Make Model		SI. No.	SI. No.	
Stack Sampler	Vayubodhan	VSS - 1	623 - DTC - 09		

02. Details of DUC

Name	Thermocouple with Temperature Indicator Environmental Conditions During Calibration				
Make/Trade Mark	Audiotronics	Temperature (°C) :- 25 ± 4 °C	24.6		
SI.No.	TP - 623	Relative Humidity (%) :- 30-75 %	56.0		
Cal. Range / Range	50 - 600 °C / 0 - 600 °C	Barometer Pressure (mmHg)	739.65		
Resolution	1 °C				

03. Standard Equipment used for calibration

Standard Equipment Name	Range	SI.No.	Traceability
Digital Thermometer with R - Type T/C	0 - 1600 °C	YD5002383	Calyss Calibration, Noida
Certificate No.	Calibration Date		Valid Up to
CCTPL/DTM/0133/03	(08.06.2023	07.06.2024

04. Calibration Procedure :-

LES-CCL/WI/31/TH/01

Remark: Refer page 2 of 2 for Calibration Results.

Notes :-

- 1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.)
- 2. Reference used are directly traceable to national standard through unbroken chain of calibration.
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- 4. This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

Chief Executive Officer)

Centre

Gr. Noida



LES - Centre For Calibration Laboratory



ULR No.	CC10512300000	1948F	Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/TH/TP/21		

05. Corrected Calibration Results for Thermocouple with Temperature Indicator

S.No.	Device Under Calibration	Std.Reading (°C)	Error FS (%)	Calibration Factor	at 95	nded Uncertainty % of Confidence rel (k =2) (°C)
	(°C)	49.9	-0.48	1.062	±	1.91
1		100.5	-0.41	1.025	±	1.91
2	98	100.5		1.007	±	1.92
3	197	198.5	-0.25	1.007	<u> </u>	
	298	300.1	-0.34	1.007	±	2.12
4	290		0.24	1.005	±	1.95
5	397	399.0	-0.34		+	2.01
_	498	501.0	-0.49	1.006	±	2.01
6	430		-0.55	1.006	±	2.04
7	595	598.3	-0.55	1.000		

Remark: The Reported value is Average of ten readings.

Uncertainty Contributing Factor:-

- 1.Repeatability (based on ten measurement)
- 2.Uncertainty of Master Instruments
- 3.Resulation of DUC
- 4. Drift of Master Thermocouple

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Notes :-

- 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna, Greater Noida (U.P.) alibiation 2. Reference used are directly traceable to national standard through unbroken chain of calibration .
- 3. Results reported are valid at the time of and under the stated conditions of measurement
- This Certificate refers only to the particular item calibrated.
- 5. Decision rule required No
- 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025
- 7. Calibration status Sticker indicating CAL, STATUS in affixed on the instruments

Centre A. Gr. Noida **Authorized By**

SHIV SHANKAR SINGH (Chief Executive Officer)

**** End of Calibration Certificate ****



(A Division of Lata Envirotech Services)

K-307, UPSIDC Industrial Area, Site -5, Kasna, Greater Noida, Gautam Budh Nagar - 201310 (U.P.) E-mail: lesccl307@gmail.com, lesccllab@gmail.com, Cell No.: 9911766898, 9821735177, 9355384939 Website: www.lesccllab.com



CC-1051

CALIBRATION CERTIFICATE

ULR No.	CC1051230000	000949F	Cali. Field - Fluid Flow		Page No 1 of 2
Certificate No.	LES-CCL/FF/PT/37				1 age 110 1 01 2
Calibration Date	05.08.2023	Sugges	ted Date of Nex	t Calibration	04.08.2024
Customer Name :- Address :-	M/s Prism Johnson Village - Mankahari, Tehsil - Rampur Bag Distt. Satna - 485111	P.O. Bathia, ghelan,			
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023

Location of Performance for Calibration		Laboratory			
Date of DUC Receipt	05.08.2023	Calibration Performed At	Parmanent Lab.	Condition of DUC	OK
S.R.F No.	2023/17	S.R.F Date	22.06.2023	Issue Date	22.08.2023

01. Details of DUC

Name	S -TYPE PITOT TUBE	Environmental Conditions During Calibration	Calibration	
Length	0.6+0.6 mrt	Temperature (°C) :- 25 ± 3 °C	25.4	
ID.No. / SI.No	V - 102	Relative Humidity (%) :- 45-75 %	56.0	
Cal. Range	3 - 20 m/sec	Barometric Pressure (mmHg)	734.75	

02. Standard Equipment used for calibration

SI.No.	Standard Equipment Name	Range	SI.No. / ID.No.	Traceability
1	S -Type Pitot Tube	3 to 25 m/s	V626 / LES-CCL/R/12101	Enviro Instruments, Gr. Noida
2	Digital Pressure Gauge	0 - 100 mmwc	VEM153080 / LES-CCL/R/2503	GTCL, New Delhi
3	Dig.Temp.Indicator With Sensor	0 - 50 °C	T- 01 / LES -CCL/R/15301	Calyss Calibration, Noida
	Certificate No.		Calibration Date	Valid Up to
1	EI/FF/4670		30.11.2022	29.11.2023
2	23061201-01		12.06.2023	11.06.2024
3	CCTPL/TI/0133/01		08.06.2023	07.06.2024

03. Calibration Procedure :-

LES-CCL/WI/31/FF/06

Remark 1. Refer page 2 of 2 for Calibration Results.

2. The Velocity has been Referenced to standard Temperature (20 °C) and Pressure (760 mmHg Absolute) Condition.

Notes :-

1 .This certificate shall not be reproduced, except in full without the written permisson of LES-CCL.Kasna, Greater Noida (U.P.) .- Centre

2. Reference used are directly traceable to national standard through unbroken chain of calibration

3. Results reported are valid at the time of and under the stated conditions of measurement

4. This Certificate refers only to the particular item calibrated.

5. Decision rule required - No

6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025

Calibration status - Sticker indicating CAL, STATUS in affixed on the instruments

Authorized By

SHIVSHANKER SINGH (Chief Executive Officer)

Gr. Noida



LES-Centre for Calibration Laboratory



ULR No.	CC105123000000949F		Page No 2 of 2
Calibration Date	05.08.2023	Suggested Date of Next Calibration	04.08.2024
Certificate No.	LES-CCL/FF/PT/37		

04. CALIBRATION OBSERVATIONS AND RESULTS FOR S - TYPE PITOT TUBE

S.No.	Standard 'S' Type Pitot Tube K = 0.8668		'S' Type Pitot Tube (DUC)	
	Dynamic Pressure (mmwc)	Air Velocity (m/s)	Dynamic Pressure (mmwc)	Factor K
1	0.85	3.395	0.8	0.8973
2a	6.41		5.1	
2b	6.44		5.4	
2c	6.46	9.726	5.6	0.9346
2d	6.48		5.7	
2e	6.42		5.7	
2f	6.45		5.8	
3	13.84	13.892	12.5	0.9109
4	23.05	17.292	22.4	0.8786
5	30.94	19.992	30.3	0.8766
		•	Averaged Coefficient (K)	0.8996

Remark: The reading of dynamic pressure represents the mean of 6 reading.

7. Calibration status - Sticker Indicating CAL, STATUS in affixed on the Instruments

Type A standard Uncertainty Repeted Data Srial No. (2a to 2f)

± 0.0074 m/s

0.1985 m/s

or

Scanned with CamScanner

Expanded uncertainty in Actual flow

Measurement at 95 % calibration at a coverage factor (k=2)

Uncertainty Contributing factor:-

- 1.Repeatability (based on three measurement)
- 2. Uncertainty of master instruments
- 3. Resulation Of DUC

The evaluated Expanded Uncertainty in calibration at a coverage factor k = 2, for degrees of freedom =∞ and confidence level is 95 % for Normal distribution.

Notes: 1. This certificate shall not be reproduced, except in full without the written permisson of LES-CCL. Kasna Greater Notice (U.P.) 2. Reference used are directly traceable to national standard through unbroken chain of calibration. 3. Results reported are valid at the time of and under the stated conditions of measurement 4. This Certificate refers only to the particular item calibrated. 5. Decision rule required - No 6. Our NABL certificate no. is CC-1051 valid up to 18.05.2025 Authorized By Authorized By SHIVSHANKER SINGH

(Chief Executive Officer)

10.1 % Rdg

****End of Calibration Certificate****



ENVIRONMENTAL TEST & CALIBRATION LABORATORY

(An ISO: / 9001/2015 Certified Company)

(A Centre for Environmental Monitoring, Data Generation, Service & Calibration of Air Pollution Monitoring System, Old Monitoring Instruments Hire & Purchase, Services, Supplier of Environmental Monitoring Instruments, Consumables Accessories & Digital On-Line Scientific Goods)

K-307, UPSIDC Industrial Area, Site - V, Kasna, Greater Noida, Distt., - Guatam Budh Nagar-201310, U.P. Call No.: 09267945626, 0999139742, E-mail etcl.singh@gmail.com / shivshankar300@gmail.com

MI/S Prism Jhonson Ltd

(Cemement Division - Unit-II), Village - Mankahari ,P.O.Bathia , Tehsil-Rampur Baghelan ,Distt.-Satna- 485111 (MP)

Page:	1 of 2
Certificate No:	ETCL/Balance/0120
Date of Calibration:	05-08-2023

CALIBRATION CERTIFICATE

This is to certify that the Digital Weighing Balance Make -Metler Toledo ,Model - ML-204 has been calibrated by us. Details of reference and their traceabilities to NABL accredited agencies are given below.

Digital Weighing Balance Make -Metler Toledo , Model - ML-204

SL. No: B319299006

S. No.	Name of Unit Calibrated	Calibrator Traceable to	Master Calibration Certificate No. & Date of Calibration
	Digital Weighing Balance Make -Metler Toledo , Model - MI		
(i)	Dig. Weighing Balance Sl No- B319299006	Weight Box EI, Gr. Noida, G.B.Nagar (UP)	EI.ME/475 Dt: 02/07/2023

Recalibration is due on 04/08/2024 or after a major repair or overhaul.

For Environmental Test & Calibration Laboratory

Gr. Noida on Laboration Laboratio

EShivshanker Singh (Chief Executive)

Environmental Test Calibration Laboratory

M/S Prism Jhonson Ltd (Cemement Division - Unit-II), Village -Mankahari ,P.O.Bathia , Tehsil-Rampur Baghelan ,Distt.-Satna- 485111 (MP)

CALIBRATION RESULTS

Envi	ronmental Conditions	Certificate No. ETCL /Balance /120
Temperature (°C)	Barometric Pressure (mmHg)	Date of Calibration -05/08/2023
27 <u>+</u> 5	737 <u>+</u> 2	

<u>Model - ML-204</u>, <u>Model - Make -Metler Toledo</u>

SI No- B319299006

0 No	Test Piece Measured	Ref	Reference		
S. No.	weight (gm)	Std. Mark (gm)	True Measured weight (gm)	Factor	
1 2 3 4 5 6 7	100.0190 49.99820 19.99710 10.00210 4.99850 2.00200 0.99530	100 50 20 10 5 2	99.99871 49.99899 19.99927 9.99934 4.99945 1.99945 0.99942	1.000 1.000 1.000 1.000 0.999 1.004	
8 9 10 11 12 13	0.50653 0.19950 0.09970 0.04990 0.02020 0.01090	500 200 100 50 20 10	0.49955 0.20015 0.10015 0.05012 0.02010 0.01007	0.986 1.003 1.005 1.004 0.995 0.924	

Checked by



Certified by



M.P. Pollution Control Board E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

Consent No:H-59332

RED-LARGE

CCA-Expansion
Hazardous Authorization up
to - 30/11/2028

CONSENT NO: ***

PCB ID: 13880

Outward No:119350,15/12/2023

NO: /MPPCB/SAT

NO. / MITTOD/ OH

To,

The Propritor

M/s. M/s. Prism Johnson Ltd.

(Cement Division Unit- II) (13880), Village-Mankahari, P.O. Bathia, Tehsil-Rampur Baghelan, Distt. Satna - 485111 (M.P.)

Subject: Grant of Authorization (For Expansion) under Hazardous and Other Waste (Management and Transboundary Movement)

Rules, 2016.

Ref: Your Application Receipt No. 1301693 Dt. 31/10/2023 and last communication received on Dt.22/11/2023.

With reference to your above application for Grant of Authorization (For Expansion) has been considered under the aforesaid Acts and existing rules therein. The M. P. Pollution Control Board has agreed for Authorisation for co-processing of AFR and Hazardous waste in cement plant as per Rule 9 of Hazardous and Other Waste (Management and Transboundary Movement) Rules, 2016 and CPCB guidelines for preprocessing and co-processing of hazardous and other waste in Cement plants, valid for 05 years up to 30/11/2028, subject to the fulfillment of the terms & conditions, enclosed with this letter

SUBJECT TO THE FOLLOWING CONDITIONS :-

a. Location: Village - Mankahari, P O Bathia, Rajdeep Rewa Road Satna Tehsil - Rampur Baghelan, Distt -Satna,

Contact No. 9109912455

b. The capital investment in Cr: Rs. 1333 /-s

c. Product & Production Capacity:

Sr. No.	Product	Qty/year
1.	Cement	6.70 Million tone/year (Six point Seven million tone per year)
2.	Clinker	3.0 Million tone/year (Three million tone per year)
3.	Generation of Electricity by DG-Set-1x 6 MWH	6.00 MWH (Six MWH)

Enclosures:-

- * Conditions under Hazardous waste Rules 2016.
- * General conditions

By the order of Chairman, MPPCB

mthakul

Seeding from UIDAI

Segul

Digitally Sign with Andhaar

Signature Not Verified

Digitally Signed by : Chandra

Mohan Thakur, AS

Date: 15/12/2023 12:30:13 PM

(Organic Authentication on AADHAR from UIDAI Server)

TPAV # 4M61SPYD9X

CHANDRA MOHAN THAKUR Member Secretary





M.P. Pollution Control Board E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

CONDITIONS PERTAINING TO THE HAZARDOUS AND OTHER WASTES (MANAGEMENT AND TRANSBOUNDARY MOVEMENT) RULES, 2016:-

[See rule 6 (2)]

FORM-2

GRANT OR RENEWAL OF AUTHORISATION BY STATE POLLUTION CONTROL BOARD TO THE OCCUPIERS, RECYCLERS, REPROCESSORS, REUSERS, USER AND OPERATORS OF DISPOSAL FACILITIES

1. Number of authorisation and date of issue:

COE-1301693, dt: 31/10/2023 2. Reference of application (No. and date) From 01/12/2023 to 30/11/2028 3. The Authorization shall be valid

4. The Occupier of M/s. Prism Johnson Ltd. (Cement Division Unit- II) (13880) is hereby granted an authorisation based on the signed inspection report of regional officer (can be seen in XGN) for generation/collection, reception, storage, recycling, preprocessing, co-processing/ utilisation, of hazardous or other wastes as per CPCB guidelines dated 7/07/2017 for preprocessing and co-processing of hazardous and other waste in Cement plants / Rule 09 of Hazardous and Other Waste (Management and Transboundary Movement) Rules, 2016 on the premises situated at Village - Mankahari, P O Bathia , Rajdeep Rewa Road Satna, Tehsil - Rampur Baghelan Distt - Satna (M.P.) - 485111, Phone No. 07672275301.

Details of Authorisation

	Category of Hazardous Waste as per the Schedules I, II and III of these	Catg.	Existing Capacity	*	Authorised mode of disposal co-processing, in cement plant.
110.					co-processing, in cement plant.
1	rules Ballast Water Containing Oil From Ships(3.4)	3.4	(ton/annum) 3300.000-M.T	(ton/annum) Nill	Co. processing in coment plant
2		5056	16500.000-M.T		Co- processing in cement plant
2.	Spent Solvents(28.6)	28.6	25000.000-M.T	Nill	Co- processing in cement plant
J. 1	Spent acid(26.3)	26.3		Nill	Co- processing in cement plant
4.	Spent Solvents(20.2)	20,2	25000.000-M.T	Nill	Co- processing in cement plant
) .	Spent solvent(21.2)	21.2	550.000-M.T	Nill	Co- processing in cement plant
o. 7	Sludge Containing Oil(2.2)	2.2	3300.000-M.T	Nill	Co- processing in cement plant
1.	Spent Catalyst(4.2)	4.2	3300.000-M.T	Nill	Co- processing in cement plant
8.	Distillation Residues(20.3)	20.3	6600.000-M.T	Nill	Co- processing in cement plant
9.	Oily Sludge or Emulsion(4.1)	4.1	3300.000-M.T	Nill	Co- processing in cement plant
10.	Spent Catalyst(28.2)	28.2	1100.000-M.T	Nill	Co- processing in cement plant
11.	Spent Catalyst(18.1)	18.1	1650.000-M.T	Nill	Co- processing in cement plant
12.	Wastes or residues containing oil(5.2)	5.2	1752.500-M.T	Nill	Co- processing in cement plant
13.	Slop Oil(4.3)	4.3	3300.000-M.T	Nill	Co- processing in cement plant
14.	Spent Clay Containing Oil(4.5)	4.5	3300.000-M.T	Nill	Co- processing in cement plant
15.	Acid from used batteries(9.3)	9.3	12000.000-M.T	Nill	Co- processing in cement plant
16.	Process Waste Sludge/Residues Containing Acid, Toxic Metals, Organic compounds	26.1	6000.000-M.T	Nill	Co- processing in cement plant
17.	Spent solvent(26.4)	26.4	25000.000-M.T	Nill	Co- processing in cement plant
18.	Spent pickling liquor(13.1)	13.1	6000.000-M.T	Nill	Co- processing in cement plant
19.	Spent solvents(29.4)	29.4	25000.000-M.T	Nill	Co- processing in cement plant
20.	Process Residue and wastes(28.1)	28.1	8250.000-M.T	Nill	Co- processing in cement plant
21.	Drilling mud containing oil(2.3)	2.3	6000.000-M.T	Nill	Co- processing in cement plant
22.	Process wastes or residues(29.1)	29.1	25000.000-M.T	Nill	Co- processing in cement plant
23.	Spent acids(29.6)	29.6	3000.000-M.T	Nill	Co- processing in cement plant
24.	Exhaust Air or Gas cleaning residue(35.1)	35.1	Nill	3000.000-M.	Co- processing in cement plant
25.	cargo residue, washing water and sludge containing oil(3.1)	3.1	Nill		Co- processing in cement plant
26.	Drill cuttings excluding those from water based mud(2.1)	2.1	Nill	6000.000-M.	Co- processing in cement plant
27.	Date-expired products(28.5)	28.5	Nill	16500.000-M.	Co- processing in cement plant
28.	Chemical sludge from waste water treatment(35.3)	35.3	Nill		TCo- processing in cement plant
29.	cargo residue and sludge containing chemicals(3.2)	3.2	Nill	3300.000-M.	Co- processing in cement plant
30.	Sludge And Filters Contaminated With Oil(3.3)	3.3	Nill	3300.000-M.	Co- processing in cement plant
31.	Carbon residue(18.2)	18.2	Nill		Co- processing in cement plant
32.	Organic Residues From Process(4.4)	4.4	Nill	3300.000-M.	Co- processing in cement plant
33.	Organic Residues(1.4)	1.4	Nill		Co- processing in cement plant
34.	Cathode Residues Including Pot Lining Wastes(11.2)	11.2	Nill		TCo- processing in cement plant
35.	Brine Sludge(16.3)	16.3	Nill	6000.000-M	Co- processing in cement plant
36.	Process residues(38.1)	38.1	Nill		Co- processing in cement plant
37.	Off Specification Products(28.4)		ent No.H-5933		Co- processing in cement plant

Scanned with OKEN Scanner



M.P. Pollution Control Board E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

38.	Any process or distillation residue(36.1)	36.1	Nill	3000.000-M.TCo- processing in cement plant
39.	Spent carbon(28.3)	28.3	Nill	3000.000-M.TCo- processing in cement plant
40.	Spent Catalyst And Molecular Sieves(1.6)	1.6	Nill	3300.000-M.TCo- processing in cement plant
41.	Drosses and waste from treatment of salt sludge	11.5	Nill	6000.000-M.TCo- processing in cement plant
42.	Sludge From Acid Recovery Unit(13.2)	13.2	Nill	6000.000-M.TCo- processing in cement plant
43.	Wastes or Residues (Not Made With Vegetable Or	23.1	Nill	6000.000-M.TCo- processing in cement plant
	Animal Materials)(23.1)			
44.	Spent ion exchange resin containing toxic metals	35.2	Nill	6000.000-M.TCo- processing in cement plant
45.	process Wastes, Residues and sludges(21.1)	21.1	Nill	550.000-M.TCo- processing in cement plant

- (1) The authorisation is subject to the following general and specific conditions (Please specify any conditions that need to be imposed over and above general conditions if any)
- (2) The industry shall comply with the provisions of SOP issued by the CPCB dated 07-07-2017 Guidelines for preprocessing ,and co-processing of hazardous waste and other waste / AFR in cement plant.
- (3) Industry shall comply the emission norms as per MoEF &CC notification vide GSR no 497 dated 10-05-2016 as amended.
- (4) Industry shall submit six monthly compliance of SOP for AFR co-processing by cement plant.
- (5) Industry shall insure installation, regular operation and internet connectivity of CEMS with the Board for online Continuous stack Emission Monitoring System (CSEMS) with to monitor gaseous emission and regular monitoring of heavy metal as per provisions of CPCB- SOP and connect the same with Environment Surveillance Centre, M.P. Pollution Control Board Bhopal for remote surveillance

A. General conditions of authorisation:

Print Dt: 30/11/2023

- The authorised person shall comply with the provisions of the Environment (Protection) Act, 1986, and the rules made there
 under.
- The authorisation or its renewal shall be produced for inspection at the request of an officer authorised by the State Pollution Control Board.
- 3. The person authorised shall not rent, lend, sell, transfer or otherwise transport the hazardous and other wastes except what is permitted through this authorisation.
- Any unauthorised change in personnel, equipment or working conditions as mentioned in the application by the person authorised shall constitute a breach of his authorisation.
- 5. The person authorised shall implement Emergency Response Procedure (ERP) for which this authorisation is being granted considering all site specific possible scenarios such as spillages, leakages, fire etc. and their possible impacts and also carry out mock drill in this regard at regular interval of time;
- 6. The person authorised shall comply with the provisions outlined in the Central Pollution Control Board guidelines on Implementing Liabilities for Environmental Damages due to Handling and Disposal of Hazardous Waste and Penalty
- 7. It is the duty of the authorised person to take prior permission of the State Pollution Control Board to close down the facility.
- The imported hazardous and other wastes shall be fully insured for transit as well as for any accidental occurrence and its cleanup operation.
- The record of consumption and fate of the imported hazardous and other wastes shall be maintained.
- 10. The hazardous and other waste which gets generated during recycling or reuse or recovery or pre-processing or utilisation of imported hazardous or other wastes shall be treated and disposed of as per specific conditions of authorisation.
- 11. The importer or exporter shall bear the cost of import or export and mitigation of damages if any.
- 12. An application for the renewal of an authorisation shall be made as laid down under these Rules.
- 13. Any other conditions for compliance as per the Guidelines issued by the Ministry of Environment, Forest and Climate Change or Central Pollution Control Board from time to time.
- 14. Annual return shall be filed by June 30th for the period ensuring 31st March of the year.
- 15. The non hazardous solid waste arresting in the industry/unit/unit premises sweeping, etc. be disposed off scientifically so as not to cause any nuisance/pollution. The applicant shall take necessary permission from civic authorities for disposal to dumping site. If required.

Consent No:H-59332

Page: 3 / 6



M.P. Pollution Control Board E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

B. Specific conditions:

- 1. The industry shall display the information on hazardous waste generated on notice board of size 6' x 4' (in Hindi & English) outside the unit main gate along with quantity and nature of hazardous chemicals being handled in the plant, including wastewater, air emission and hazardous wastes.
- 2. The authorisation or its renewal shall be produced for inspection at the request of an officer authorised by the State Pollution Control Board.

Additional Haz condition:-

Print Dt: 30/11/2023

- The industry shall obtain insurance under Public Liability Insurance Act, if applicable and shall submit a copy to theboard.
- Any unauthorized change in production capacity, process, raw materials, personnel, equipments etc. as mentioned inthe application by the person authorized shall constitute a breach of this authorisation.
- 3. The unit shall maintain the records of hazardous waste as per the Form-3 of rule 6(5) and shall online submit the annual return in Form-4 as per rule 6(5) 20(2) to this office on or before 30th June every year and preferably before 30th April.
- The information regarding quantity of hazardous wastes generated and its analysis report should be sent to the Boardonline at least annualy.
- 5. Hazardous Waste Storage Site & Danger signboard shall be provided with all safety devices at the storage site.
- The authorized person shall inform the name and address of the contact person / occupier responsible for hazardouswaste management.
- 7. No import of hazardous waste is allowed at the site.
- 8. In the event of any accident due to handling of hazardous wastes, the authorized person must inform immediately to the Regional Office & Head office of the board on fax/telephone/email-it_mppcb@rediffmail.com about the incident and detail report should be sent in Form No.5 as per Rule-10 of Hazardous and other Waste (Management and Transboundary Movement) Rule 2016 as amended upto date.
- 9. The occupier or operator of the Treatment, Storage and Disposal Facility or recycler shall ensure that the hazardous waste are packaged and labeled, based on the composition in a manner suitable for safe handling, storage and transportas per the guidelines issued by the Central Pollution Control Board vide - October 2004 & conditions issues from timeto time.
- 10. The labeling and packaging shall be easily visible and be able to withstand physical conditions and climate factors.
- 11. The transport of the hazardous wastes shall be in accordance with the provision of these rules and the rules madeby the Central Govt. under the Motor Vehicle Act 1988 and other guidelines issued from time to time in this regard.
- 12. In case of transportation of hazardous wastes through a State other than the State of origin or destination, the occupier shall intimate the concerned State Pollution Control Board before he hands over the hazardous wastes to thetransporter.
- 13. The occupier shall provide the transporter with six copies of the manifest as per the colour codes as per rule 20(1).
- 14. The occupier shall forward copy 1 (white) to the State Pollution Control Board and in case the hazardous wastes islikely to be transported through any transit State, the occupier shall prepare an additional copy each for intimation to such State and forward the same to the concerned SPCB before he hands over the hazardous wastes to the transporter.
- 15. No transporter shall accept hazardous wastes from an occupier for transport unless copies 3 to 7 of the manifestaccompany it.
- 16. The transporter shall submit copies 3 to 7 of the manifest duly signed with date to the operator of the facility along with the waste consignment.

Consent No:H-59332



Page: 4/6



M.P. Pollution Control Board E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

- 17. The industry shall comply with the Standard Operating Procedure (SOP) and Monitoring Protocol as per theguidelines issued by the Central Pollution Control Board for the Industries engaged in the coprocessing of the hazardous waste.
- 18. The industry shall procure the pre-processed hazardous waste from the agency duly authorised by the MPPCB and the transportation shall be done through the transporters registered with the MPPCB under the Rules, 2016.

GENERAL CONDITIONS:

1. The non hazardous solid waste arresting in the industry/unit/unit premises sweeping, etc. be disposed off scientifically so as not to cause anynuisance/pollution. The applicant shall take necessary permission from civic authorities for disposal to dumping site. If required.

Non Hazardous Solid wastes:- (If any)

Type of waste	Quantity	Disposal
Scrap/ Plastic packing material wood, card board, gunny begs etc	Record should be maintained	Sale to authorized party/As Per CPCB. MoEF Guide lines.

- 2. The applicant shall allow the staff of Madhya Pradesh Pollution Control Board and/or their authorized representative, upon the representation of credentials:
 - a. To inspect raw material stock, manufacturing processes, reactors, premises etc to perform the functions of the Board.
- b. To enter upon the applicant's premises where an effluent source is located or in which any records are required to be kept under the terms and conditions of this Consent.
 - c. To have access at reasonable times to any records required to be kept under the terms and conditions of this Consent.
 - d. To inspect at reasonable times any monitoring equipment or monitoring method required in this Consent: or,
 - e. To sample at reasonable times any discharge or pollutants.
- 4. This consent / authorisation is transferable in nature, in case of any change in ownership / management, the new owner / partner / directors / proprietor shall immediately apply for the consent with new requisite information.
- 5. The issuance of this Consent does not convey any property rights in either real or personal property or any exclusive privileges, nor does it authorise any invasion of personal rights, nor any infringement of Central, State or local laws or regulations.
- 6. Industry shall install separate electric metering arrangement for running of pollution control devices and this arrangement shall be made in such fashion that any non functioning of pollution control devices shall immediately stop electric supply to the production and shall remain tripped till such time unless the pollution control device/devices are made functional. The record of electricity consumption for running of pollution control equipment shall be maintained and submitted to the Board every month.
- 7. This consent is granted in respect of Water pollution control Act 1974 or Air Pollution Control act, 1981 or Authorization under the provisions of Hazardous and other Waste (Management & Transboundary movement) Rules 2016 only and does not relate to any other Department/Agencies. License required from other Department/Agencies have to be obtained by the unit separately and have to comply separately as per there Act / Rules.
- 8. Balance consent/authorisation fee, if any shall be recoverable by the Board even at a later date.
- 9. The applicant shall submit such information, forms and fees as required by the board not letter than 180 day prior to the date of expiration of this consent/authorization.
- 10. The industry/unit shall establish a separate environmental cell, headed by senior officer of the unit for reporting the environmental compliances. The industry/ Unit shall submit environmental statement for the previous year ending 31st March on or before 30th September every year to the Board.
- Industry shall obtain membership of Emergency Response Center of the Board if needed.
- 12. Knowingly making any false statement for obtaining consent or compliance of consent conditions shall result in the imposition of criminal penalties as provided under the section 42(g) of the Water Act or section 38 (g) of the Air Act.
- 13. After notice and opportunity for the hearing, this consent may be modified, suspended or revoked by the Board in whole or in part during its term for cause including, but not limited to the following:



Page: 5 / 6

Scanned with OKEN Scanner



M.P. Pollution Control Board E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

- (a) Violation of any terms and conditions of this Consent.
- (b) Obtaining this Consent by misrepresentation of failure to disclose fully all relevant facts.
- (c) A change in any condition that requires temporary or permanent reduction or elimination of the authorized discharge.
- 14. On violation of any of the above-mentioned conditions the consent granted will automatically be taken as canceled and necessary action will be initiated against the industry.

Additional condition:- (if any) :-

- The industry shall operate the Outdoor HD Industrial grade IP (Internet Protocol) Cameras with pan-Tilt-Zoom (PTZ) feature, minimum focal length 30X with night vision facility and temper proof mechanism at suitable location to display all emission sources and effluent discharge point shall be kept operational & in working order and connect the same with Environment Surveillance Centre of MP Pollution control board Bhopal for remote surveillance.
- Industry shall ensure regular operation and maintenance of canyons water foggers installed in the plant. They must be kept in working condition at all times.
- Industry shall obtain Consent to operate for expansion as per CTE (expansion) conditions / consent condition.

Authorization as required under the Hazardous and Other Waste (Management and Transboundary Movement) Rules, 2016 is granted to your industry subject to fulfillment of all the conditions mentioned above. For renewal purpose you shall have to make an application to this Board through XGN at least Six months before the date of expiry of this Authorisation. The applicant without valid Authorisation (for operation) of the Board shall not bring in to use any outlet for the discharge of effluent and gaseous emission.

> For and on behalf of M.P. Pollution Control Board

By the order of Chairman, MPPCB

Digitally Sign with Andhaar

(Organic Authentication on AADHAR from UIDAI Server) TPAV # 4M61SPYD9X

CHANDRA MOHAN THAKUR Member Secretary

Scanned with OKEN Scanner







VTL/WW/03

ULR No.

: TC1122725000000787F

Report No.

: VTL/WW/2503280010/A

M/s PRISM JOHNSON LIMITED

: 7.8 F-01

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL

Format No

Satna (M.P.) Name & Address of the Party :

Report Date

: 02/04/2025

Sample Description

: Waste Water

Receipt Date

: 28/03/2025-02/04/2025 : 28/03/2025

Sampling Location

: STP Outlet

Sampling Date

Period of Analysis

: 27/03/2025

Sample Collected By

: VTL Team

Sampling Type

: Grab

Preservation

: Suitable Preservation

Sample Quantity

: 2 Ltr.

Method of sa

vietno	d of sampling : IS :3025		Coordinate	es :	
S.No.	Test Parameters	Test Method	Result	Unit	Limits
1	pH ,	IS: 3025 (P-11): 2022	7.45	-	5.5 to 9.0
2	Total Suspended Solids (TSS)	IS: 3025 (P-17): 2022	33.5	mg/L	100
3	Total Dissolved Solids (TDS)	IS:3025 (P-16): 2023	876.2	mg/L	2100
4	Oil & Grease	IS:3025 (P-39): 2021	*BLQ(**LOQ-4.0)	mg/L	10
5	Biochemical Oxygen Demand (BOD) (3 days @ 27°C)	IS: 3025 (P-44): 2023	13.0	mg/L	30
6	Chemical oxygen Demand (COD)	IS: 3025 (P-58): 2023	58.0	mg/L	250
7	Faecal coliform	APHA 24th Edition 9221 C: 2023	84	MPN/100 ml	

^{*}BLQ-Below Limit OF Quantification, **LOQ- Limit Of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/1

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified




- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601


3 0141-2954638


M bd@vibranttechnolab.com


www.vibranttechnolab.com


Rainwater Harvesting structure photographs


































At DIC Land



At Cafeteria





Behind B-type

S. No.	Land use type	Runoff Coefficient (As per CGWB Guidelines)	Rainfall	Area M2	Total Recharge 2024 -25
1	Roof - Project office	0.85	1.110	386	364.19
2	Roof - School	0.85	1.110	1150	1085.03
3	Roof of MRSS	0.85	1.110	1900	1792.65
4	Roof of Cement Mill Load Center U2	0.85	1.110	1100	1037.85
5	Roof General Store	0.85	1.110	2000	1887.00
6	Cooler Load Centre U1	0.85	1.110	1100	1037.85
7	Cooler Load Centre U2	0.85	1.110	1000	943.50
8	Durtech shed	0.85	1.110	800	754.80
9	Durtech sheu	0.85	1.110	30000	28305.00
10	Packing Plant Unit I	0.85	1.110	375	353.81
11	Packing Plant Unit II	0.85	1.110	1500	1415.25
12	Mines Workshop	0.85	1.110	468	441.56
13	Ground water recharge with abandoned bore well near steel yard	0.85	1.110	40000	37740.00
14	Groundwater Recharge with Abandoned Bore well - 1	0.2	1.110	10000	2220.00
15	Groundwater Recharge with Abandoned Bore well - 2	0.2	1.110	10000	2220.00
16	Groundwater Recharge with Abandoned Bore well - 3 (Near Kiln)	0.2	1.110	2500	555.00
17	Groundwater Recharge Pit Connected with	0.85	1.110	9746	9195.35
18	Storm Drain - A type Colony	0.3	1.110	17307	5763.23
19	Groundwater Recharge Pit Connected with	0.85	1.110	22828	21538.22
20	Storm Drain - Near Nursery	0.3	1.110	47748	15900.08
21	Runoff Water Harvesting Structure Behind C- Type	0.65	1.110	30000	21645.00
22	New security Barrack	0.65	1.110	10000	7215.00
23	Near E & G Type Colony	0.65	1.110	30000	21645.00
24	Near DIC Land	0.65	1.110	10000	7215.00
25	Cafeteria RWH	0.65	1.110	10050	7251.08
26	Behind B-Type	0.65	1.110	10000	7215.00
TOTAL RECHARGE					

Roof top rainwater harvesting structures

Abandoned Borewell

Ground water recharge -Storm Drain

By e-mail

Dt: 16/05/2025

GOVERNMENT OF INDIA MINISTRY OF MINES INDIAN BUREAU OF MINES OFFICE OF THE REGIONAL CONTROLLER OF MINES, JABALPUR

No. JAB/SAT/LST/MMP-01/2025-26

ICM IOUNCON LIMITED

Shri/M/s. PRISM JOHNSON LIMITED , 305, LAXMI NIWAS APARTMENTS AMEERPET HYDERABAD

Sub Approval of modifications in the Mining Plan in respect of your Mining Lease Area for Limestone over an area of 99.416 Ha. situated in
Sijahata Village, Rampur Baghelan Taluka, Satna District of Madhya Pradesh State.

- Ref: (i) Your Letter No. NIL dated 23/03/2025 submitting draft copy of modified Mining Plan in respect of aforesaid M.L. Area.
 - (ii) This office letter of even no. dated 22/04/2025.
 - (iii) Your Letter No. Nil dated 05/05/2025 submitting final copies of Mining Plan in respect of aforesaid M.L. Area.

Circ

In exercise of the powers conferred by clause (b) of sub-section (2) of section 5 of the Mines & Minerals (Development & Regulation) Act, 1957 and clause (3) of Rule 17 of the Minerals (Other than Atomic and Hydro Carbons Energy Minerals) Concession Rules, 2016 read with Government of India Order No.S.O.445(E) dated 28.04.1987 and S.O. 1857(E) dated 18th May, 2016; I hereby **APPROVE** the modifications in Mining Plan alongwith Progressive Mine Closure Plan (PMCP) for the period of 2025-26 to 2026-2027 (proposal period may be indicated). This approval is subject to the following conditions:

A. General Conditions:

- 1. That the Modified Mining Plan is approved without prejudice to any other laws applicable to the mine / area from time to time whether made by the Central Government, State Government or any other authority.
- 2. That this approval of the Modified Mining Plan does not in any way imply the approval of the Government in terms of any other provisions of the Mines & Minerals (Development & Regulation) Act, 1957 or the Mineral Concession Rules, 1960 or any other laws including Forest (Conservation) Act, 1980, Environment (Protection) Act, 1986 and the rules made there under.
- 3. That the Modified Mining Plan is approved without prejudice to any other order or direction from any court of competent jurisdiction.
- 4. The provisions of the Mines Act, 1952 and Rules and Regulations made thereunder including submission of notices of opening, appointment of manager and other statutory officials as required by the Mines Act, 1952 shall be complied with.
- 5. If anything is found to be concealed as required by the Mines Act in the contents of the modified mining plan and the proposal for rectification has not been made, the approval shall be deemed to have been withdrawn with immediate effect.
- 6. The execution of modified mining plan shall be subjected to vacations of prohibitory orders / notices, if any.
- 7. ^^A copy of EIA/EMP Report approved by MOEF, New Delhi should be submitted to this office within one month of its approval along with a copy of their approval letter. (^^ if applicable)
- 8. The Environmental Monitoring Cell of the company shall continue monitoring ambient Air quality, dust fall rate, water quality, soil sample analysis and noise level measurements on various stations established for the purpose both in the core zone and buffer zone, as per Department of Environment guidelines and keeping in view IBM's Circular No. 3/92, season- wise every year or by engaging preferably the services of and Environmental Laboratory approved by MOEF / CPCB. The data so generated shall be maintained in a bound paged register kept for the purpose and the same shall be made available to the inspecting officer on demand.
- 9. This approval for proposed mining operation and associated activities is restricted to the mining lease area only. The mining lease area is as shown on the statutory plans by the Lessee/QP/Applicant and Indian Bureau of Mines has not undertaken verification of mining lease boundary on the ground.
- 10. Your attention is invited to the Supreme Court interim order in W.P. (C) No. 202 dated 12.12.1996 for compliance. The approval of above said Modified Mining Plan is therefore, issued without prejudice to and is subject to the said directions of the Supreme Court as applicable.
- 11. This department does not undertake any responsibility regarding correctness of the boundaries of the lease area shown on the ground with reference to lease map & other plans furnished by the lessee.
- 12. Yearly report as required under Rule 26(2) of Mineral Conservation and Development Rules 1988, setting forth the extent of protective and rehabilitative works carried out as envisaged in the approved progressive mine closure plan and if there is any deviations, reasons thereof shall be submitted before 1st July of every year.
- 13. The validity period of the financial assurance shall be renewed before the expiry of the same and should be submitted to this office.(wherever applicable)

- 14. At any stage, if it is observed that the information furnished in the document are incorrect or misrepresent facts, the approval of the document shall be revoked with immediate effect.
- 15. This approval is given for received proposals as applicable from this date for the Mining activities to be carried out within the mining lease area. The earlier instances of irregular mining / illegal mining, if any shall not be regularized through the approval of this document.
- 16. The approval of the above said Modified Mining Plan with PMCP is subject to condition that you shall maintain boundary pillars as indicated in Rule 12 of Minerals (Other than Atomic and Hydro Carbons Energy Minerals) Concession Rules, 2016.

B. Special Conditions:

- 1. The lessee to keep a separate record of sale of mineral, if any, from the lease and will report such sale in the monthly & annual returns to be submitted under the Mineral Conservation & Development Rules, 2017.
- 2. An Environmental monitoring cell should be constituted to carry out regular monitoring of environmental parameters (Air, Water & Noise level) and quarterly report of Environmental monitoring should be submitted to the Regional Controller of Mines, Indian Bureau of Mines, Ranchi. Further, daily monitoring report should be displayed on display board near mine/mine office.
- 3. The approval is given for the received proposals as applicable from this date for the mining activities to be carried out within the lease area. The earlier instances of irregular mining/ illegal mining, if any, shall not be regularized through the approval of this document.
- 4. It shall be mandatory for the project proponent, abstracting ground water, to obtain NO Objection Certificate from Central Ground Water Authority or, the concerned State/Union Territory Ground Water Authority, as the case may be.
- 5. 6. That the yearly report in the prescribed format indicating the extent of protective and rehabilitative works carried out as envisaged in the Review of Mining Plans with prograssive Mine closure Plan required under Rule 26(2) of Mineral Conservation and Development Rules, 2017shall be submitted before 1st of July of every year to the Regional office, Indian Bureau of Mines.
- 6. As per Madhya Pradesh State Government's order dated 10/08/2011 if there is enhancement of production proposed from that in the approved scheme of mining under such circumstances additional stamp duty has to be paid by the lessee for the enhances quantum of production and also a supplementary agreement has to be made by the lessee.
- 7. Any increase in production proposed should only be carried out after obtaining statutory permission from all regularity bodies . Encl: 01 Digital Copy of Approved Modified Mining Plan.(JAB/SAT/LST/MMP-01/2025-26)

Yours faithfully,

(SALIL SANDIP KUJUR)

Regional Controller of Mines/OIC

Copy without enclosure forwarded for information to Shri. Amit Biswas, Qualified Person

(SALIL SANDIP KUJUR)

Regional Controller of Mines/OIC

Not on first Two copies:

Copy forwarded for kind information to:

- (i) The Controller of Mines (CZ), Indian Bureau of Mines, Nagpur.
- (ii) The Director of Mines Safety, D.G.M.S Jabalpur
- (iii) The Director, Govt. of Madhya Pradesh, Khaniz Bhawan, 29A Arera Hills, Jail Road, Bhopal (MP) alongwith Modified Mining Plan.
- (iv)The District Collector, Satna (M.P.)
- (v) QP file/Mine file/Guard file.

(SALIL SANDIP KUJUR)

Regional Controller of Mines/OIC

By e-mail

Dt: 26/12/2024

GOVERNMENT OF INDIA MINISTRY OF MINES INDIAN BUREAU OF MINES OFFICE OF THE REGIONAL CONTROLLER OF MINES, JABALPUR

No. E 12129 MCDR-MPC0LST/58/2024-JBP-IBM_RO_JBP

DDICM IQUINGON I IMITED

Shri/M/s. PRISM JOHNSON LIMITED ,
305, LAXMI NIWAS APARTMENTS AMEERPET HYDERABAD

Sub Approval of Review of Mining Plan in respect of Prism Cement Limestone Mine over an area of 772.067 Hect; situated in Sijahata
Village, Rampur Baghelan Tehsil, Satna District of Madhya Pradesh State.

References: 1) Draft Review of Mining plan received on MPAS, dated – 30/09/2024

- 2) This office scrutiny comments dated 16/11/2024 & 20/12/2024
- 3) Final copy of Review of Mining Plan received on MPAS, dated 23/12/2024

Sir,

In exercise of the powers conferred under Clause (b) of Sub-section (2) of Section 5 of Mines and Minerals (Development and Regulation) Act, 1957 as amended from time to time notified thereunder read with Government of India Order no. S.O.1857(E),dated 18/05/2016, I hereby **Approve** the above said Review of Mining Plan submitted under Rule 17(2) of Minerals (Other than Atomic and Hydrocarbons Energy Minerals) Concession Rules, 2016 as amended from time to time notified thereunder. This approval is subject to the following conditions: -

- 1. The Review of Mining Plan is approved without prejudice to any other law applicable to the mine area from time to time whether made by the Central Government, State Government or any other authority and without prejudice to any order or direction from any court of competent jurisdiction.
- 2. The proposals shown on the plates and /or given in the document is based on the lease map /sketch submitted by the lessee and is applicable from the date of approval.
- 3. It is clarified that the approval of aforesaid Review of Mining Plan does not in any way imply the approval of the Government in terms of any other provision of Mines & Minerals (Development & Regulation) Act 1957, or the Minerals (Other than Atomic and Hydro Carbons Energy Minerals) Concession Rules, 2016 and any other laws including Forest (Conservation) Act, 1980, Environment (Protection) Act, 1986 or the rules made there under, Mines Act, 1952 and Rule & Regulations made there under.
- 4. Indian Bureau of mines has not undertaken verification of the mining lease boundary on the ground and does not undertake any responsibility regarding correctness of the boundaries of the leasehold shown on the ground with reference to lease map & other plans furnished by the lessee.
- 5. At any stage, if it is observed that the information furnished, data incorporated in the document are incorrect or misrepresent facts, the approval of the document shall be revoked with immediate effect.
- 6. If the approval conflicts with any other law or court order/direction under any statute, it shall be revoked immediately.
- 7. The Financial Assurance furnished by you is **Rs. 10,75,00,000/-** (**Rs. Ten Crore Seventy Five Lakh Only**) is **valid up** to 31/03/2030 and next Financial Assurance shall be submitted on or before 31/03/2030.
- 8. This approval is restricted in respect of proposals given in the document for the period 2025-26 to 2029-30 with validity up to 31/03/2030, subject to all other statutory clearances.
- 9. It shall be mandatory to project proponent, abstracting ground water to obtain **No objection certificate** from Central Ground Water Authority or the M.P. State Ground Water Authority.

Yours faithfully,

(Pukhraj Nenival)

Indian Bureau of Mines, Jabalpur

Copy for information to-

- 1. The Director of Geology and Mining, Govt. of Madhya Pradesh, Khaniz Bhawan, 29A Arera Hills, Jail Road, Bhopal (MP).
- 2. The Controller of Mines (CZ), Indian Bureau of Mines, Nagpur.
- 3. The District Collector, Satna (M.P.)
- 4. Shri Amit Biswas, M/s Prism Johnson Ltd. Rajdeep, Rewa Road, Satna (M.P.) 485001; E-mail amit.biswas@prismjohnson.in
- 5. Shri Santosh Kumar, M/s Prism Johnson Ltd. Rajdeep, Rewa Road, Satna (M.P.) 485001; E-mail santosh.kumar@prismjohnson.in

(Pukhraj Nenival)

Regional Controller of Mines

Indian Bureau of Mines, Jabalpur



GOVERNMENT OF INDIA MINISTRY OF MINES INDIAN BUREAU OF MINES OFFICE OF THE REGIONAL CONTROLLER OF MINES, JABALPUR

No. E 10308 MCDR-MPC0LST/11/2024-JBP-IBM RO JBP

Dt: 29/05/2024

Shri/M/s. PRISM JOHNSON LIMITED,

305, LAXMI NIWAS APARTMENTS AMEERPET HYDERABA MENDHI LIMESTONE MINE 117594HECT (38MPR35314) (46412701)

Sub Approval of Review of Mining Plan in respect of Mendhi Limestone Mine over an area of 117.594 Hect; situated in Mendhi Village,

: Rampur Baghelan Taluka, Satna District of Madhya Pradesh State.

References: 1) Draft Review of Mining plan received on MPAS, dated – 01/03/2024

- 2) This office scrutiny comments dated 13/04/2024, 13/05/2024 & 28/05/2024
- 3) Final copy of Review of Mining Plan received on MPAS, dated 29/05/2024

Sir,

In exercise of the powers conferred under Clause (b) of Sub-section (2) of Section 5 of Mines and Minerals (Development and Regulation) Act, 1957 as amended from time to time notified thereunder read with Government of India Order no. S.O.1857(E),dated 18/05/2016, I hereby **Approve** the above said Review of Mining Plan submitted under Rule 17(2) of Minerals (Other than Atomic and Hydrocarbons Energy Minerals) Concession Rules, 2016 as amended from time to time notified thereunder. This approval is subject to the following conditions: -

- 1. The Review of Mining Plan is approved without prejudice to any other law applicable to the mine area from time to time whether made by the Central Government, State Government or any other authority and without prejudice to any order or direction from any court of competent jurisdiction.
- 2. The proposals shown on the plates and /or given in the document is based on the lease map /sketch submitted by the lessee and is applicable from the date of approval.
- 3. It is clarified that the approval of aforesaid Review of Mining Plan does not in any way imply the approval of the Government in terms of any other provision of Mines & Minerals (Development & Regulation) Act 1957, or the Minerals (Other than Atomic and Hydro Carbons Energy Minerals) Concession Rules, 2016 and any other laws including Forest (Conservation) Act, 1980, Environment (Protection) Act, 1986 or the rules made there under, Mines Act, 1952 and Rule & Regulations made there under.
- 4. Indian Bureau of mines has not undertaken verification of the mining lease boundary on the ground and does not undertake any responsibility regarding correctness of the boundaries of the leasehold shown on the ground with reference to lease map & other plans furnished by the lessee.
- 5. At any stage, if it is observed that the information furnished, data incorporated in the document are incorrect or misrepresent facts, the approval of the document shall be revoked with immediate effect.
- 6. If the approval conflicts with any other law or court order/direction under any statute, it shall be revoked immediately.
- 7. In case of the mining lease is declared as 'Lapsed' by the State Government, under provision of Section 4A(4) of MMDR Act 1957 (as amended up to 28th March, 2021) read with Rule 20 of the Mineral (Other than Atomic and Hydrocarbons Energy Minerals) Concession Rules, 2016 notified on 02/11/2021, at any course of time, the approval of Review of Mining Plan will stand revoked immediately without any further correspondence".
- 8. The Financial Assurance furnished by you is **Rs. 3,13,80,000/-** (Rs. Three Crore Thirteen Lakh Eighty Thousand Only) is **valid up** to 31/03/2026 and next Financial Assurance shall be submitted on or before 31/03/2026.
- 9. This approval is restricted in respect of proposals given in the document for the period 2024-25 (from the date of approval) to 2025-26, with validity up to 31/03/2026, subject to all other statutory clearances.
- 10. It shall be mandatory to project proponent, abstracting ground water to obtain **No objection certificate** from Central Ground Water Authority or the M.P. State Ground Water Authority.

Table no. 1. ML area 772.067 Ha. (Hinauti&Sijahata)

Present Dumps status as per Mining Plan

Dump No.	Location of Dump	Present Height of Dump (m)	Slope of the Dump
S1	300E to 400E and 80N to 220N	2.0	24
S2	410E to 880E and 210N to 350N	6.0	27
S3	920E to 1010E and 320N to 360N	0	-
S4	1060E to 1220E and -60N to 320N	0	-

Table no. 2. ML area 99.416 Ha. (Hinauti&Sijahata)
Present Dumps statusas per Mining Plan

Dump No.	Location of Dump	Present Height of Dump(m)	Slope of the
			Dump
D1	1720E to1810E and -1130N to-1155N	6.0	27
D2	1670E to1720E and -1240N to-1120N	6.7	27.5

Table no. 3. ML area 117.594 Ha. (Mendhi)
Present Dumps status:-Nil

PLAN FOR PROTECTION OF THE NATURAL WATER COURSE PASSING NEARBY PRISM CEMENT LIMITED LEASE AREAS

1. INTROCUCTION:

The Limestone Mine of M/s. Prism Johnson Ltd. is near villages Hinauti & Sijhatta in district of Satna, Madhya Pradesh. The area is in Vindhyan Limestone/shale formations, where Limestone is bearing mined from mining lease areas of 772.067 Ha. 117.594 Ha. 512.317 Ha. 99.416 Ha., amongst other mining leases. As per the conditions of the Environment Clearance, a plan was protection of natural water courses passing nearby Prism Cement Ltd. Leases was to be prepared and submitted.

The natural water courses under the present plan comprise Tamas River, Nar Nala and Magardha Nala.

2. LAND USE IN THE BUFFER AREA OF THE LEASES:

Buffer zone:

The land use of buffer zone is given in **Table 1** based on satellite imaginary and census data.

TABLE NO.1

Land Use / Land Cover Details of Buffer Zone Area

LAND USE	AREA (in Hectares)	AREA (in %)
River/Canal	634.71	1.32
Ponds/Reservoir	561.73	1.17
Stonsy area	144.16	0.30
Open land	441.36	0.92
Open scrub land	3737.14	7.76
Forest Land	1685.11	3.50
Plantation	2445.89	5.08
Fallow land	29729.69	61.77
Crop land	7542.87	15.67
Human Settlement	706.28	1.47
Industrial Area	75.80	0.16
Mine Quarry	425.75	0.88
Total	48310.49	100

(Source - EIA/EMP)

3. **DRAINAGE**:

The Tamas (Tons) River mainly controls the drainage pattern. The none seasonal nalla viz. Magardaha and Nar nala flowing on west and east of the lease area respectively flow towards north and ultimately join the Tamas River. The area is almost flat with gentle slope towards East and Northeast. A substantial part of rainfall in the area drains away as surface run-off, along streamlets towards the Northeast to the Tamas River. The drainage map of Tamas (Tons) sub basin of Ganga basin is depicted in **Figure 2**. The drainage pattern of buffer zone (part of Tamas sub basin) is also given in **Figure 3**.

FIGURE 2





FIGURE-3

DRAINAGE MAP OF BUFFER ZONE



4. HYDROMETEROLOGY:

Madhya Pradesh state is situated within 180 N to 250 N and 740 E to 820 E experiences tropical climate. Frontispieces gives the orographic feature of the state. Geographical location and orographic features have profound influence on the climate of area. As per IMD the year may be divided into four seasons. The winter season from January to February is followed by the summer season from March to May. The period from June to September constitutes the southwest monsoon season and the period from October to December form the post monsoon season.

4.1 **Rainfall**: Rainfall data of Mine site and Satna IMD station are collected for the project of 2008 to 2014 and given in (**Table NO. -2**).

<u>TABLE NO.2</u> Year wise rainfall data (2008 to 2014) : Satna and Mine Site

Month/	2008	20	09	20	10	20	11	20	12	2013		2014
Year	Mine Site	Mine Site	Satna	Mine Site	Satna	Mine Site	Satna	Mine Site	Satna	Mine Site	Satna	Mine Site
Jan	2.0	35.3	12.9	8.8	1.7	0.0	0.0	36.0	32.3	0.0	0.0	38.9
Feb	35.1	0.0	0.0	13.3	5.5	1.0	0.9	0.0	0.0	67.9	45.9	104.3
Mar	1.3	3.6	1.4	0.0	0.0	3.2	0.2	3.6	3.9	34.6	11.5	29.3
Apr	12.0	0.7	3.8	0.0	0.1	0.0	1.1	0.0	0.2	1.8	4.2	8.7
May	12.5	10.5	14.5	18.6	1.6	36.2	7.3	0.0	0.0	0.0	0.0	1.3
Jun	215.6	12.5	25.8	16.9	16.4	313.9	328.6	17.9	15.6	270.4	384.2	90.2
Jul	216.8	173.2	207.6	283.3	228.1	140.2	252.1	380.7	279.7	576.5	338.6	305.2
Aug	220.2	214.9	192.5	198.3	209.7	206.7	289.8	435.0	455.1	414.5	451.6	127.2
Sep	71.5	109.7	152.0	213.5	176.4	205.3	143.9	132.1	169.3	134.9	71.5	193.9
Oct	0.0	72.9	220.4	29.6	13.7	0.0	3.1	15.1	2.5	131.4	143.7	200.7
Nov	20.1	80.9	58.9	11.8	9.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Dec	0.0	2.6	2.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	21.9
Total	807.1	716.7	892.7	794.0	662.9	906.5	1027.0	1020.3	958.6	1631.9	1451.2	1121.7

(Source - Mine & Satana Dist.)

5. GEOLOGY:

The relevant portion of Geological report of the area have been adapted for present study. Part of compilation done from other references.

5.1 Regional Geology

Geologically, this area forms part of the Rewa Plateau belonging to the Upper Vindhyan Supergroup of rock formations in Indian stratigraphy. The Vindhyan formations are roadly classified into lower calcareous and an upper arenaceous facies.

The limestone deposit in the area of investigation belongs to the Bhander series. The general trend of Bhander Limestone is East - Northeast to West - Southwest having low southerly dips of less than 5⁰. The litho stratigraphy of Vindhyan formation is given in **Table NO.3**

TABLE NO.3 Litho stratigraphy of Satna District

Supergroup	Group	Formation				
		Maihar Sandstone				
	Bhander Group	Sirbu Shale				
		Bhander Limestone				
Vindhyan Cunorgroup	Rewa Group	Sandstone and shale				
Vindhyan Supergroup	Kaimur Group	Sandstone and shale				
	UNCONFORMITY					
		Rohtas Formation				
		Khemjua Formation				
	Semri Group	Porcellance Formation				
		Basal Formation				
	UNCONFORMITY					
Bundekhand granites/Bijawar phyllites						

5.2 Local Geology:

The detailed geological prospecting was carried out by GEM Division of ACC to identify the geological structure in the area and association of different rock types. The lithological succession of various formations encountered in the area of investigations based on the sub-surface data generated is as follows:

Overburden Soil
Buff to pale grey magnesian limestone
Upper shaly limestone
Grey limestone
Lower shaly limestone
Grey to grayish grey shale

6.0 SUGGESTED STRUCTURES FOR PROTECTION AND DEVELOPMENT OF NATURAL WATER COURSES:

- **6.1** RAINWATER HARVESTING
- **6.1.1 General:** Rain water harvesting can be defined as activity of direct collection of Rain

water and storage of rainwater as well as other activity aimed at harvesting and conserving surface and ground water preventing loss through evaporation and seepage and other hydrological studies and engineering inventions aiming at most efficient utilization of rainwater towards best use for the humanity.

The detail project report for rainwater harvesting is given below incorporating; source, area, design of individual structure within mine lease area and outside.

6.1.2 Source of Water:

The source or water available for rainwater harvesting is only surface water. The resource estimation for lease area has been done considering total lease area of 10.25 km2 (7.72 km2 + 2.53 km2). Monsoon normal rainfall 0.973 m and surface runoff coefficient of 0.40. The estimated surface water resource will be 3.99 MCM out of this 0.58 MCM will be used in plant & mine. The mine water discharge will be zero. It is expected that remaining estimated resource 3.41 MCM will be available for recharge to the system and future use. CGWA while granting ground water had laid condition for implementation of ground water recharge measure to the tune of 1.206 MCM/ year for augmenting the ground water resource of the area.- Source of data, Hydrological Studies Report.

6.1.3 Identification of area:

The areas identified within lease area are given in Table No.4

Table no. 4: Identification of area

Sr. No.	Identification of area	Unit
1	Surface water reservoir in the Mined out area as recharge	3 Nos
	pond.	
2	Check dam on Nar nadi.	8 Nos
3	Office and residential building area for Rooftop rainwater	10 Nos
	harvesting	
4	Lease area (side of retention wall) of dump for recharge pit	4 Nos
	with shaft structure	
5	Recharge trench in colony area.	500 m
6	In the colony area away from mine for Gravity head recharge	10 Nos
	tubewell.	

These structures in respective areas will augment the ground water table and shall reduce load on the natural water courses for rural utility of irrigation amongst others.

In addition to the measures taken above, the area in proximity to Tamas River, Magardha Nala and Nar Nala will be provided with bunds above and beyond HFL. Safety barrier of 50 meters will be left our permanently. This barrier will be densely planted thus making the water courses totally immune from mining activities. No mine water will be discharged in the natural water courses without de-siltation in the settling ponds.

The garland drains with check dams are constructed all along the peripheries of the lease area. De-siltation of natural water ways up-stream and down-stream, will be undertaken after consultation with the authorities to keep the natural water courses healthy.

Periodical deepening of village ponds and de-siltation of the same will be carried out to augment water bodies in surrounding areas.

6. CONCLUSION AND REOCMMENDATION:

The natural water ways protection plan will be updated to accommodate new ideas and government water development programs. The present plan with all implementation will keep the natural water courses safe and healthy.



Sample Description

Sampling Location

Preservation

Sample Collected By



erience the unimaginable Sample Number : VTL/W/01

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

: VTL Team

: Sijahata - Village (Borewell)

: Suitable Preservation

ULR No.

: TC1122725000000758F

Report No.

: VTL/W/2503280010/A

Format No

: 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

Sample Quantity

: Grab

: 2 Ltr.

Method of sampling : IS :3025			Coordin	ates	:	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.38		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable		Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	259.0	mg/L	200	600
7	Calcium (as Ca) .	IS: 3025 (P-40): 2024	73.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	219.3	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	175.4	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	18.68	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	786	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	52.61	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.48	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	22.36 1 <i>e Unimagi</i>	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.38	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	. 0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000758F

Report No.

· VTL/W/2503280010/A

ampi	mple Number: VTL/W/01		Report	No.	: VTL/W/2503280010/A		
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023		
					Acceptable Limit	Permissible Limit	
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.42	mg/L	5.0	15.0	
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5	
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3	
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation	
23	Lead (as Pb).	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation	
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05	
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation	
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample		
27	E.Coli .	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	()	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation	
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation	
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0	

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601



Sample Description

Sampling Location

Sample Collected By

Method of sampling

Preservation

S.No.



erience the unimaginable" Sample Number: VTL/W/02.

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Test Method

Satna (M.P.)

: Water Sample

: VTL Team

: IS:3025

: Packing Plant Unit-II

: Suitable Preservation

ULR No.

: TC1122725000000759F

Report No.

: VTL/W/2503280011/A

Format No

· 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

IS:10500-2012,RA 2023

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

: Grab

Sample Quantity

Results

*BLQ(**LOQ-0.02)

: 2 Ltr.

Test Parameters

Coordinates

Units

Acceptable Permissible Limit Limit IS: 3025 (P-11): 2022 7.52 6.5 to 8.5 No Relaxation pH (at 25°C) *BLQ(**LOQ-1.0) 2 Colour IS: 3025:(P-4): 2021 Hazen 5 15 IS: 3025: (P-10): 2023 *BLQ(**LOQ-1.0) NTU 1 5 3 Turbidity IS: 3025 (P-5): 2018 4 Odour Agreeable Agreeable Agreeable 5 IS:3025 (P-8): 2023 Agreeable Agreeable Agreeable Taste --IS: 3025 (P-21): 2009, RA 2019 225.0 200 600 6 Total Hardness (as CaCO3) mg/L IS: 3025 (P-40): 2024 55.0 200 Calcium (as Ca) mg/L 75 Total Alkalinity (as CaCO3) IS: 3025 (P-23): 2023 202.5 mg/L 200 600 IS: 3025 (P-32): 1988, RA 2019 137.9 250 1000 9 Chloride (as CI) mg/L IS: 3025 (P-46): 2023 21.33 30 100 10 mq/L Magnesium (as Mg) 11 Total Dissolved Solids IS:3025 (P-16): 2023 620 mg/L 500 2000 400 42.1 200 12 Sulphate (as SO4) IS: 3025 (P-24): Sec: 1: 2022 mg/L APHA 24th Edition, 4500F-D: 0.39 1.0 1.5 mg/L 13 Fluoride (as F) 2023 IS 3025 (P-34) : Sec 1 : 2023 45.0 No Relaxation 17.4 14 Nitrate (as NO3) mg/L (Clause 6.4) APHA 24th Edition 3111 B, 0.31 No Relaxation Iron (as Fe) mg/L 1.0 15 2023 16 Aluminium (as Al) IS 3025 (P-55): 2003, RA 2019 *BLQ(**LOQ-0.03) mg/L 0.03 0.2 APHA 24th Edition 4500B-C: *BLQ(**LOQ-0.2) 0.5 2.4 mg/L 17 Boron (as B)



18





RK Yadav Lab Incharge Authorized Signatory

mg/L



No Relaxation

Page No. 1/2

Total Chromium (as Cr)

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

2023 APHA 24th Edition 3111 B,

2023

Vibrant Techno Lab Pvt. Ltd.

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601

0.05





ULR No.

: TC1122725000000759F

Report No.

· VTL/W/2503280011/A

ampi	mpie Number: V1L/W/02		Report	No.	: VTL/W/2503280011/A			
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023			
					Acceptable Limit	Permissible Limit		
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.41	mg/L	5.0	15.0		
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5		
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3		
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation		
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation		
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05		
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation		
26	Total Coliform	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	,		
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample			
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation		
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation		
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0		

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





erience the unimaginable Sample Number : VTL/W/03

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

: Hinauta Village-Borewell

: Suitable Preservation

ULR No.

: TC1122725000000788F

Report No.

: VTL/W/2503280012/A

Format No

: 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

: Grab

Sample Quantity

: 2 Ltr.

Method of sampling

Preservation

Sample Description

Sampling Location

Sample Collected By

: IS :3025

: VTL Team

Coordinates

• ---

Metho	d of sampling : IS:	3025	Coordin	ates	:	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS : 3025 (P-11) : 2022	7.27	-	6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable		Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	312.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	83.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	248.5	mg/L	200	600
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	153.9	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	25.49	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	730	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	63.9	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.49	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	e unimagi	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.43	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



≥ bd@vibranttechnolab.com







ULR No.

: TC1122725000000788F

· VTI M/2503280012/A

sample	e Number: VTL/W/03		Report	No.	: VTL/W/25032	80012/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
		x.			Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.51	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01 .	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
27	E.Coli	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



M bd@vibranttechnolab.com







Experience the unimaginable Sample Number: VTL/W/04

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

: Hinauti Village -Handpump

: Suitable Preservation

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

ULR No.

: TC1122725000000760F

Report No.

: VTL/W/2503280013/A

Format No

: 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

: Grab

Sample Quantity

: 2 Ltr.

Method of sampling

Preservation

Sample Collected By

Sample Description

Sampling Location

· IS -3025

: VTL Team

Metho	d of sampling : IS	:3025	Coordin	ates	:	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	012,RA 2023
	2				Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.32		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable		Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	285.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	81.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	252.4	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	176.9	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	20.15	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	760	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	62.4	mg/L	. 200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.45	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	20.16 IC Unimaga	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.35	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signator



Page No. 1/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- 9 SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000760F

Report No.

: VTL/W/2503280013/A

	C Number: VIE/VV/04		кероп	140.	; VILIVVIZ503Z	00010//
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	012,RA 2023
	*				Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.42	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



M bd@vibranttechnolab.com

www.vibranttechnolab.com



Sample Description

Sampling Location

Preservation

Sample Collected By



erience the unimaginable"
Sample Number: VTL/W/05

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

: VTL Team

: Majhiyar Village

: Suitable Preservation

ULR No.

: TC1122725000000761F

Report No.

: VTL/W/2503280014/A

Format No

: 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

: Grab

Sample Quantity

: 2 Ltr.

Metho	d of sampling : IS:	3025	Coordinates :			
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.57		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS : 3025: (P-10) : 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable		Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	212.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	50.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	195.1	mg/L	200	600
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	97.6	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	21.20	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	710	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	36.4	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.35	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	12.45 1 <i>e unimadi</i>	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.32	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



www.vibranttechnolab.com





ULR No.

: TC1122725000000761F

Report No

· VTI /W/2503280014/A

sampi	e Number: VTL/W/05		Report	No.	: VTL/W/25032	80014/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	012,RA 2023
					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.47	mg/L	5.0	15.0
20	Copper (as Cu) .	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-2
27	E.Coli -	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





xperience the unimaginable"
Sample Number: VTL/W/06

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

: PCL Colony Supply Water -Borewell Temple

Satna (M.P.)

: Water Sample

: Suitable Preservation

ULR No.

: TC1122725000000762F

Report No.

: VTL/W/2503280015/A

Format No

: 7.8 F-01

1/2

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

Crob

Sample Quantity

: Grab

Janip

: 2 Ltr.

Method of sampling

Preservation

Sample Collected By

Sample Description

Sampling Location

: IS:3025

: VTL Team

Coordinates

S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	Permissible Limit No Relaxation 15 5 Agreeable Agreeable 600 200 600 1000 1000 2000 400 1.5 No Relaxation No Relaxation 0.2 2.4	0-2012,RA 2023	
					Acceptable Limit	THE SELECTION OF S		
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.22	-	6.5 to 8.5	No Relaxation		
2	Colour .	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15		
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5		
4	Odour	IS: 3025 (P-5): 2018.	Agreeable		Agreeable	Agreeable		
5	Taste	IS :3025 (P-8): 2023	Agreeable	1220	Agreeable	Agreeable		
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	247.0	mg/L	200	600		
7	Calcium (as Ca)	IS: 3025 (P- 40): 2024	78.0	mg/L	75	200		
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	210.4	mg/L	200	600		
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	99.8	mg/L	250	1000		
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	12.73	mg/L	30	100		
11	Total Dissolved Solids	IS :3025 (P-16): 2023	680	mg/L	500	2000		
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	35.6	mg/L	200	400		
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.37	mg/L	1.0	1.5		
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	15.34 16 U/I/I/I/I/I/I/I	mg/L	45.0	No Relaxation		
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.31	mg/L	1.0	No Relaxation		
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2		
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4		
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation		







RK Yadav
Lab Incharge
Authorized Signatory



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000762F

· V/TI ////2503280015/A

Sampl	e Number: VTL/W/06		Report	No.	: VTL/W/25032	80015/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	012,RA 2023
					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.40	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	'
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory




Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



≥ bd@vibranttechnolab.com







perience the unimaginable"
Sample Number: VTL/W/07

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

: Mankahari Village -Handpump

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

: Suitable Preservation

ULR No.

: TC1122725000000763F

Report No.

: VTL/W/2503280016/A

Format No

: 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

Sample Quantity

: Grab : 2 Ltr.

Coordinates

Method of sampling

Sample Description

Sampling Location

Preservation

Sample Collected By

: IS:3025

: VTL Team

S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	Permissible Limit No Relaxation 15 5 Agreeable 600 200 600 1000 1000 2000 400 1.5 No Relaxation No Relaxation
		e ***			Acceptable Limit	
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.29	-	6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	235.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P- 40): 2024	56.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	220.3	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	92.4	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	23.75	mg/L	30	100
11	Total Dissolved Solids .	IS :3025 (P-16): 2023	690	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	33.6	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.37	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	16.42	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.28	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000763F

Report No.

: VTL/W/2503280016/A

ampi	e Number: VIL/W/07		Report	No.	: VIL/W/25032	80016/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	012,RA 2023
	F				Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.38	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	= -
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







Lab Incharge
Authorized Signatory



Page No. 2/2


Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



≥ bd@vibranttechnolab.com







Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

: Badarkha Village -Borewell

: Suitable Preservation

ULR No.

: TC1122725000000764F

Report No.

: VTL/W/2503280017/A

Format No

: 7.8 F-01

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

: Grab

Sample Quantity

: 2 Ltr.

Method	of	sampling	

Sample Collected By

Sample Description

Sampling Location

Preservation

: IS:3025

: VTL Team

: --Coordinates

S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 202	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.36		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS : 3025: (P-10) : 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	177.	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	243.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P- 40): 2024	62.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	. 278.4	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	125.3	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	21.46	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	794	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	42.5	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.43	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	22.16 7 <i>e</i> Unimag	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.36	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000764F

Papart No.

. V/TI AAI/2503200017/A

	e Number: VTL/W/08	· · · · · · · · · · · · · · · · · · ·	Report	No.	: VTL/W/25032	80017/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.45	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	=
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601



M bd@vibranttechnolab.com

www.vibranttechnolab.com





ULR No.

: TC1122725000000765F

Report No.

: VTL/W/2503280018/A

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Format No Party Reference No : NIL

: 7.8 F-01

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

: Water Sample

Report Date : 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

: Malgaon Village -Handpump

Sampling Date

: 26/03/2025

Sample Collected By Preservation

Sample Description

Sampling Location

: VTL Team

Sampling Type Sample Quantity : Grab

: Suitable Preservation

Coordinates

: 2 Ltr.

Method of sampling

: IS:3025

S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.42		- 6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	258.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	83.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	253.6	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	110.4	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	12.37	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	590	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	36.2	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.38	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	15.42	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.31	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000765F

Sample Number: VTL/W/09		Report No.		: VTL/W/2503280018/A		
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.42	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report











Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601



Sample Description

Sampling Location

Preservation

Sample Collected By



ULR No.

: TC1122725000000766F

Report No.

: VTL/W/2503280019/A

Name & Address of the Party : M/s PRISM JOHNSON LIMITED Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

: 7.8 F-01 Format No Party Reference No : NIL

Satna (M.P.)

: Water Sample

.: VTL Team

: Medhi Village -Handpump

: Suitable Preservation

Report Date : 02/04/2025

: 28/03/2025-02/04/2025

Period of Analysis

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

Sample Quantity

: Grab : 2 Ltr.

Metho	Method of sampling : IS:3025		Coordinates		:	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-20	012,RA 2023
	8				Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.25		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable		Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	254.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	75.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	243.5	mg/L	200	600
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	129.4	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	16.25	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	620	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	32.46	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.33	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	14.27 @ Un/mag/	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.28	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge **Authorized Signato**



Page No. 1/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000766F

Report No.

· VTI /W/2503280019/A

sample	e Number: VTL/W/10		Report	No.	: VTL/W/25032	80019/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
	50				Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.38	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
27	E.Coli	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





Experience the unimaginable Sample Number: VTL/W/11

Name & Address of the Party : M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

: Water Sample

: Plant Pump House -Rawmill

: Suitable Preservation

ULR No.

: TC1122725000000767F

Report No.

: VTL/W/2503280020/A

Format No

: 7.8 F-01

Party Reference No ; NIL

Report Date

: 02/04/2025

: 28/03/2025-02/04/2025

Period of Analysis

: 28/03/2025

Receipt Date Sampling Date

Sampling Type

: 26/03/2025

: Grab

Sample Quantity

: 2 Ltr.

Method of sampling

Preservation

Sample Description

Sampling Location

Sample Collected By

: IS:3025

: VTL Team

Coordinates

: --

	grand the understanding	.3025	Coordin	1	T	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
	E .				Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.58	-	6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS : 3025: (P-10) : 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour .	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	242.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	70.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	256.3	mg/L	200	600
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	124.5	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	16.37	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	640	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	38.74	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.36	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	14.64	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.32	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signator



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000767F

Report No.

· VTI /W/2503280020/A

. 85	e Number: VTL/W/11		Report	No.	: VTL/W/25032	80020/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
53					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.47	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform .	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	n
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601



Name & Address of the Party



ULR No.

: TC1122725000000768F

Report No.

: VTL/W/2503280021/A

: M/s PRISM JOHNSON LIMITED

Format No

: 7.8 F-01 Party Reference No : NIL

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

: Water Sample : Borewell at Time Office Receipt Date

: 28/03/2025

Sampling Location Sample Collected By

Sampling Date

: 26/03/2025

Preservation

Sample Description

: VTL Team

Sampling Type Sample Quantity : Grab : 2 Ltr.

Method of sampling

: Suitable Preservation : IS:3025

Coordinates

	d of sampling : 15	:3025	Coordin	ates	:	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
	2 .				Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS : 3025 (P-11) : 2022	7.51		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour .	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable		Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	263.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P- 40): 2024	78.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	221.5	mg/L	200	600
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	119.7	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	16.62	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	750	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	36.52	mg/L	200	400
13	Fluoride (as F) .	APHA 24th Edition, 4500F-D: 2023	0.39	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	16.24	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.29	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signator



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601

3 0141-2954638

M bd@vibranttechnolab.com

www.vibranttechnolab.com





ULR No.

: TC1122725000000768F

Report No.

: VTL/W/2503280021/A

	e Number . VIL/W/12		Report	NO.	: VIL/VV/25032	00021/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
	ő.				Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.39	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0


^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report











Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000789F

Report No.

: VTL/W/2503280022/A

: M/s PRISM JOHNSON LIMITED

Format No Party Reference No : NIL

: 7.8 F-01

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

: Water Sample : PCL Limestone Mines Drinking Water (Site Office)

Receipt Date

: 28/03/2025

Sampling Location Sample Collected By

Sample Description

Sampling Date

: 26/03/2025

Preservation

: VTL Team

Sampling Type Sample Quantity : Grab : 2 Ltr.

Method of sampling

: Suitable Preservation : IS :3025

Coordinator

	d or sampling : IS	:3025	Coordin	ates	:-	
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
		.*			Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.53	-	6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odouř	IS : 3025 (P-5) : 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	216.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	60.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	220.3	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	95.6	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	16.11	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	660	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	33.15	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition; 4500F-D: 2023	0.37	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	18.76 e unimagi	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.28	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signator



Page No. 1/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000789F

Report No

· VTL/W/2503280022/A

	ample Number: VIL/W/13		Report No.		: VTL/W/2503280022/A		
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023		
	ž.		0.44		Acceptable Limit	Permissible Limit	
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.41	mg/L	5.0	15.0	
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5	
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3	
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation	
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023 ·	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation	
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05	
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation	
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample		
27	E.Coli	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	=	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation	
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation	
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	ng/L/	0.2	1.0	

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signatory



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





ULR No.

: TC1122725000000769F

Report No.

: VTL/W/2503280023/A

Name & Address of the Party : : M/s PRISM JOHNSON LIMITED Format No

: 7.8 F-01

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -Satna (M.P.)

: Water Sample

: Suitable Preservation

Party Reference No : NIL Report Date : 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

: 28/03/2025

Receipt Date

: Bagahai Lime Stone Drinking Water (Mine Site Office) Sampling Date

: 26/03/2025

Sampling Location Sample Collected By

Sample Description

: VTL Team

Sampling Type

: Grab

Preservation

Sample Quantity

: 2 Ltr.

Method of sampling

: IS:3025

Coordinates

S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.63		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity -	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	, 1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	_	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable	-	Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	236.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P- 40): 2024	52.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	221.5	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	114.2	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	25.82	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	580	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	36.78	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.37	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	13.42	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.25	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signatory



Page No. 1/2

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

bd@vibranttechnolab.com

www.vibranttechnolab.com





ULR No.

: TC1122725000000769F

Report No.

· VTL/W/2503280023/A

	e Number: VIL/W/14		Report	No.	: VTL/W/25032	80023/A
S.No.	Test Parameters	Test Method	Results	Units	IS:10500-2012,RA 2023	
	*	*	0.33		Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.33	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signator



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601



Name & Address of the Party

Sample Description

Sampling Location

Preservation

Sample Collected By

Method of sampling



ULR No.

: TC1122725000000770F

Report No.

: VTL/W/2503280024/A

: 7.8 F-01

Format No

Party Reference No : NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

: 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type Sample Quantity

: Grab

: 2 Ltr.

: IS:3025

Satna (M.P.)

: Water Sample

: VTL Team

: Truck Tippler Borewell

: Suitable Preservation

: M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Coordinates

		:3025	Coordin	iates	:-	
S.No.	Test Parameters	ameters Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.21		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable		Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	253.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	78.0	mg/L	75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	248.1	mg/L	200	600
9	Chloride (as CI)	IS: 3025 (P-32): 1988, RA 2019	125.4	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	14.19	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	780	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	63.4	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.51	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	25.16	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.25	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
8	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signator



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

≥ bd@vibranttechnolab.com

www.vibranttechnolab.com





ULR No.

: TC1122725000000770F

Report No.

: VTL/W/2503280024/A

	ample Number. VID/W/15		кероп по.		: VIL/VV/2503280024/A	
S.No.	Test Parameters	Test Parameters Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.37	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb) .	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	, 0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
27	E.Coli	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni .	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	mg/L	0.2	1.0


^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report











Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601





Sample Number : VTL/W/16 Name & Address of the Party

: M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. -

Satna (M.P.)

· : Water Sample

: Chulhi Village -Borewell

: Suitable Preservation

ULR No.

: TC1122725000000771F

Report No.

: VTL/W/2503280025/A

Format No

: 7.8 F-01

Party Reference No

: NIL

Report Date

: 02/04/2025

Period of Analysis

: 28/03/2025-02/04/2025

Receipt Date

; 28/03/2025

Sampling Date

: 26/03/2025

Sampling Type

Sample Quantity

: Grab : 2 Ltr.

Method	of sampli	ina

Preservation

Sample Collected By

Sample Description

Sampling Location

: VTL Team

: IS:3025 Coordinates : --

S.No.	Test Parameters	Test Parameters Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
1	pH (at 25°C)	IS: 3025 (P-11): 2022	7.32		6.5 to 8.5	No Relaxation
2	Colour	IS: 3025:(P-4): 2021	*BLQ(**LOQ-1.0)	Hazen	5	15
3	Turbidity	IS: 3025: (P-10): 2023	*BLQ(**LOQ-1.0)	NTU	1	5
4	Odour	IS: 3025 (P-5): 2018	Agreeable	-	Agreeable	Agreeable
5	Taste	IS :3025 (P-8): 2023	Agreeable		Agreeable	Agreeable
6	Total Hardness (as CaCO3)	IS: 3025 (P-21): 2009, RA 2019	231.0	mg/L	200	600
7	Calcium (as Ca)	IS: 3025 (P-40): 2024	79.0	mg/L	. 75	200
8	Total Alkalinity (as CaCO3)	IS: 3025 (P-23): 2023	254.1	mg/L	200	600
9	Chloride (as Cl)	IS: 3025 (P-32): 1988, RA 2019	132.5	mg/L	250	1000
10	Magnesium (as Mg)	IS: 3025 (P-46): 2023	8.24	mg/L	30	100
11	Total Dissolved Solids	IS :3025 (P-16): 2023	540	mg/L	500	2000
12	Sulphate (as SO4)	IS: 3025 (P-24): Sec : 1 : 2022	41.8	mg/L	200	400
13	Fluoride (as F)	APHA 24th Edition, 4500F-D: 2023	0.26	mg/L	1.0	1.5
14	Nitrate (as NO3)	IS 3025 (P-34) : Sec 1 : 2023 (Clause 6.4)	13.42	mg/L	45.0	No Relaxation
15	Iron (as Fe)	APHA 24th Edition 3111 B, 2023	0.29	mg/L	1.0	No Relaxation
16	Aluminium (as Al)	IS 3025 (P-55): 2003, RA 2019	*BLQ(**LOQ-0.03)	mg/L	0.03	0.2
17	Boron (as B)	APHA 24th Edition 4500B-C : 2023	*BLQ(**LOQ-0.2)	mg/L	0.5	2.4
18	Total Chromium (as Cr)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	No Relaxation







RK Yadav Lab Incharge Authorized Signator



Page No. 1/2

Approved & Certified

EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

≥ bd@vibranttechnolab.com





ULR No.

: TC1122725000000771F

Report No.

: VTL/W/2503280025/A

S.No.	Test Parameters	Test Parameters Test Method	Results	Units	IS:10500-2012,RA 2023	
					Acceptable Limit	Permissible Limit
19	Zinc (as Zn)	APHA 24th Edition 3111 B, 2023	0.47	mg/L	5.0	15.0
20	Copper (as Cu)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.02)	mg/L	0.05	1.5
21	Manganese (as Mn)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.05)	mg/L	0.1	0.3
22	Cadmium (as Cd)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.002)	mg/L	0.003	No Relaxation
23	Lead (as Pb)	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	No Relaxation
24	Arsenic (as As)	APHA 24th Edition 3114 C, 2023	*BLQ(**LOQ-0.005)	mg/L	0.01	0.05
25	Mercury (as Hg)	APHA 24th Edition 3112B: 2023	*BLQ(**LOQ-0.001)	mg/L	0.001	No Relaxation
26	Total Coliform	IS : 15185 : 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
27	E.Coli	IS: 15185: 2016 RA: 2021	Absent	per 100 ml	Shall not be detectable in any 100 ml sample	-
28	Sulphide (as H2S)	IS 3025 (P-29) : 2022 (Clause 7.0)	*BLQ(**LOQ-0.04)	mg/L	0.05	No Relaxation
29	Nickel as Ni	APHA 24th Edition 3111 B, 2023	*BLQ(**LOQ-0.01)	mg/L	0.02	No relaxation
30	Free Residual Chlorine	IS 3025 (P- 26): 2021 (Clause 7.0)	*BLQ(**LOQ-0.2)	7 (mg/L/	0.2	1.0

^{*}BLQ-Below Limit Of Quantification, **LOQ- Limit of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signator



Page No. 2/2

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

Vibrant Techno Lab Pvt. Ltd.

SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020

9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

M bd@vibranttechnolab.com





Sample Number:

Sample Collected By

Sample Description:

Name & Address of the Party:

VTL/WL/01-14

M/s PRISM JOHNSON LIMITED

Village- Mankahari, Tehsil- Rampur

Baghelan, Dist.- Satna (M.P.)

VTL Team

Ground Water Level Monitoring

Report No.:

VTL/WL/2503300001-14/B

Format No.:

7.8 F-01

Party Reference No.: Report Date:

NIL

Receipt Date:

02/04/2025 30/03/2025

Date of Monitoring

26-27/03/2025

S.No.	Location	Depth (In meter)
1.	Near Colony Gate	19.2
2.	Behind B Block colony	13.66
3.	Behind C Block colony	6.2
4.	Near Auto Work Shop	13.8
5.	In Front of Den	8.6
6.	Western Block Mines	10.25
7.	Near New Magazine Mines	11.03
8.	Rose Garden Near Road	16.33
9.	Mines near Ramprasan	16.4
10.	Medhi Mines	14.5
11.	Mankahari Mines	18.74
12.	Chulhi Majhiyar Mines	11.6
13.	Bagahai Mines	9.8
14.	Badarkha Mines	11.2





RK Yadav Lab Incharge Authorized Signatory

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified



Velocity (mm/s)

Date/Time Tran at 13:44:44 December 15, 2023 Geo: 0.500 mm/s, Mic: 2.000 pa.(L) **Trigger Source**

Range Geo: 254.0 mm/s

Record Time 2.0 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM.mmb

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client

User Name: PRISM JOHNSON LIMITED

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting **PSPL** 1.148 pa.(L) at 0.008 sec

ZC Freq 85 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1453 mv)

	Tran	Vert	Long	
PPV	1.994	0.733	0.567	mm/s
ZC Freq	57	>100	32	Hz
Time (Rel. to Trig)	0.011	0.008	0.017	sec
Peak Acceleration	0.107	0.076	0.021	g
Peak Displacement	0.101	0.104	0.064	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.7	7.1	Hz
Overswing Ratio	3.7	3.5	3.7	

Peak Vector Sum 2.039 mm/s at 0.011 sec

UM8131 V 10-76 Micromate ISEE Serial Number

Battery Level 3.8 Volts

Unit Calibration December 24, 2022 by UES New Delhi UM8131_20231215134444 IDFW File Name


Post Event Notes

MNK/66 NO/4TH BENCH/NDLS/SOUTH, No. of Holes 18 Nos,

DEPTH 7.79 m


Charge/delay- 52.21 Kg, Average Distance 250m

DGMS India (B)



Frequency (Hz) Tran: + Vert: x Long: Ø

a) Industrial buildings b)Domestic houses/structures



Time Scale: 0.10 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger ≈ ▶



Velocity (mm/s)

Date/Time **Trigger Source**

Tran at 11:57:24 December 29, 2023 Geo: 0.500 mm/s, Mic: 2.000 pa.(L)

Range Geo: 254.0 mm/s

Record Time 1.5 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM.mmb

Notes

Amalgamated Prism Cement and Bandarkha

Location: Client User Name:

PRISM JOHNSON LIMITED

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone

Linear Weighting

PSPL

1.117 pa.(L) at 0.006 sec

ZC Freq

>100 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1463 mv)

	Tran	Vert	Long	
PPV	1.568	2.065	0.528	mm/s
ZC Freq	85	N/A	73	Hz
Time (Rel. to Trig)	0.007	0.002	0.013	sec
Peak Acceleration	0.159	0.376	0.067	g
Peak Displacement	0.098	0.108	0.064	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.5	7.1	Hz
Overswing Ratio	3.7	3.5	3.8	

Peak Vector Sum 2.482 mm/s at 0.007 sec

N/A: Not Applicable

UM8131 V 10-76 Micromate ISEE Serial Number

Battery Level 3.8 Volts

Unit Calibration December 24, 2022 by UES New Delhi UM8131_20231229115724.IDFW


Post Event Notes

File Name

H-16/GRW/1ST/WR, No. of Holes 62 Nos. DEPTH 3 82 M


Charge/delay- 12:50 Kg, Average Distance 160m

DGMS India (B)



Tran: + Vert: x Long: Ø

a) Industrial buildings b)Domestic houses/structures



Time Scale: 0.10 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger = ▶

Sensor Check

Printed: May 14, 2024 (V 10.72 - 10.72)

Format © 1995-2014 Xmark Corporation



Velocity (mm/s)

Date/Time Vert at 11:49:50 January 9, 2024 Geo: 0.500 mm/s, Mic: 2.000 pa.(L) **Trigger Source**

Geo: 254.0 mm/s Range

1.509 sec (Auto=7Sec) at 1024 sps **Record Time**

Operator/Setup: Operator/BGM.mmb

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client

User Name PRISM JOHNSON LIMITED

General

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting

0.776 pa.(L) at -0.652 sec **PSPL**

ZC Freq 5.4 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1443 mv)

Tran Vert Long PPV 1.253 2.231 1.269 mm/s ZC Freq N/A N/A 43 Hz Time (Rel. to Trig) 0.004 0.003 0.005 sec **Peak Acceleration** 0.038 0.119 0.035 g Peak Displacement 0.118 0.125 0.067 mm Sensor Check Passed Passed Passed Frequency 7.3 7.7 7.1 Hz Overswing Ratio 3.6 3.5 3.9

Peak Vector Sum 2.758 mm/s at 0.003 sec

N/A: Not Applicable

UM8131 V 10-76 Micromate ISEE Serial Number

3.5 Volts **Battery Level**


Unit Calibration December 24, 2022 by UES New Delhi UM8131_20240109114950 IDFW File Name

Post Event Notes

H-16/GRW/1ST BENCH/WR, No. of Holes 80 Nos., DEPTH 4 01M


Charge/delay- 11.25 Kg, Average Distance 160m.

DGMS India (B)



Frequency (Hz) Tran: + Vert: x Long: Ø

a) Industrial buildings b)Domestic houses/structures



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger = ▶



Velocity (mm/s)

Date/Time Vert at 11:49:50 January 9, 2024 **Trigger Source** Geo: 0.500 mm/s, Mic: 2.000 pa.(L)

Range Geo: 254.0 mm/s

Record Time 1.509 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM.mmb

Notes Location:

Amalgamated Prism Cement and Bandarkha

Client: PRISM JOHNSON LIMITED User Name:

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting

PSPL 0.776 pa.(L) at -0.652 sec

ZC Freq 5.4 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1443 mv)

	Tran	Vert	Long	
PPV	1.253	2.231	1.269	mm/s
ZC Freq	N/A	N/A	43	Hz
Time (Rel. to Trig)	0.004	0.003	0.005	sec
Peak Acceleration	0.038	0.119	0.035	g
Peak Displacement	0.118	0.125	0.067	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.7	7.1	Hz
Overswing Ratio	3.6	3.5	3.9	

Peak Vector Sum 2.758 mm/s at 0.003 sec

N/A: Not Applicable

UM8131 V 10-76 Micromate ISEE Serial Number

3.5 Volts **Battery Level**


Unit Calibration December 24, 2022 by UES New Delhi UM8131_20240109114950 IDFW File Name

Post Event Notes

H-16/GRW/1ST BENCH/WR, No. of Holes 80 Nos. DEPTH 4 01M


Charge/delay- 11.25 Kg, Average Distance 160m.

DGMS India (B)



a) Industrial buildings b)Domestic houses/structures

Tran: + Vert: x Long: Ø



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger = ▶



Velocity (mm/s)

Vert at 13:39:44 January 22, 2024 Date/Time Geo: 0.500 mm/s, Mic: 2.000 pa.(L) **Trigger Source**

Geo: 254.0 mm/s Range

3.628 sec (Auto=7Sec) at 1024 sps **Record Time**

Operator/Setup: Operator/BGM mmb

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client:

User Name: PRISM JOHNSON LIMITED

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting

PSPL 0.543 pa.(L) at 0.005 sec

ZC Freq 73 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1502 mv)

	rran	vert	Long	
PPV	1.167	0.835	0.788	mm/s
ZC Freq	N/A	51	37	Hz
Time (Rel. to Trig)	0.004	0.012	0.018	sec
Peak Acceleration	0.046	0.048	0.035	g
Peak Displacement	0.103	0.144	0.068	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.7	7.1	Hz
Overswing Ratio	3.6	3.5	3.9	

Peak Vector Sum 1.292 mm/s at 0.013 sec

N/A: Not Applicable

UM8131 V 10-76 Micromate ISEE Serial Number

3.8 Volts **Battery Level**

Unit Calibration December 24, 2022 by UES New Delhi UM8131_20240122133944.IDFW File Name

Post Event Notes


MNK/66 NO./6TH BENCH/H MgO/NEAR PUMP,

No. of Holes 28 Nos.,

DEPTH 7.01 M


Charge/delay- 33.73 Kg, Average Distance 250m

DGMS India (B)



Frequency (Hz) Tran: + Vert: x Long: Ø

a) Industrial buildings b)Domestic houses/structures



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger = ▶



Velocity (mm/s)

Date/Time Vert at 13:36:02 February 7, 2024
Trigger Source Geo: 0.500 mm/s, Mic: 2.000 pa.(L)

Range Geo: 254.0 mm/s

Record Time 3.5 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM.MMB

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client:

User Name: PRISM JOHNSON LIMITED

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting 2.079 pa.(L) at 0.006 sec

ZC Freq 85 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1407 mv)

	Tran	Vert	Long	
PPV	1.395	1.884	2.097	mm/s
ZC Freq	64	47	64	Hz
Time (Rel. to Trig)	0.033	0.049	0.034	sec
Peak Acceleration	0.053	0.076	0.073	g
Peak Displacement	0.108	0.123	0.055	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.5	7.1	Hz
Overswing Ratio	3.6	3.4	3.7	

Peak Vector Sum 2.480 mm/s at 0.033 sec

Serial Number UM8131 V 10-76 Micromate ISEE

Battery Level 3.8 Volts

Unit Calibration
File Name
January 29, 2024 by UES New Delhi
UM8131_20240207133602.IDFW


Post Event Notes

MNK/66 NO./6TH BENCH/H MgO/SOUTH, No. of Holes 41 Nos.

,DEPTH 7.21 M


Charge/delay- 30.94 Kg, Average Distance 250m.

DGMS India (B)



Frequency (Hz)
Tran: + Vert: x Long: ø

a) Industrial buildingsb)Domestic houses/structures



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger =



Velocity (mm/s)

Date/Time Vert at 13.55.54 February 17, 2024
Trigger Source Geo: 0.500 mm/s, Mic: 2.000 pa.(L)

Range Geo: 254.0 mm/s

Record Time 3.5 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM MMB

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client:

User Name: PRISM JOHNSON LIMITED

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting

PSPL 1.707 pa.(L) at -0.001 sec

ZC Freq 85 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1387 mv)

Vert Tran Long PPV 2.774 2.341 2.215 mm/s ZC Freq 64 57 64 Hz Time (Rel. to Trig) 0.034 0.027 0.032 sec **Peak Acceleration** 0.114 0.081 0.081 g **Peak Displacement** 0.077 0.080 0.037 mm Sensor Check Passed Passed Passed Frequency 7.3 7.7 7.1 Hz Overswing Ratio 3.6 3.4 3.7

Peak Vector Sum 3.652 mm/s at 0.034 sec

Serial Number UM8131 V 10-76 Micromate ISEE

Battery Level 3.8 Volts

Unit Calibration January 29, 2024 by UES New Delhi UM8131_20240217135554 IDFW


Post Event Notes

MNK/GRW/4TH BENCH/NDLS/WEST, No. of Holes 33 Nos

,DEPTH 7.73 M


Charge/delay- 42.42 Kg, Average Distance 250m

DGMS India (B)



Frequency (Hz)
Tran: + Vert: × Long: Ø

a) Industrial buildingsb)Domestic houses/structures



Time Scale: 0 20 sec/div Amplitude Scale: Geo: 2 000 mm/s/div Mic: 1 000 pa (L)/div Trigger = ▶ · · · · · · · · ◀



Velocity (mm/s)

Date/Time Long at 13:29:59 March 11, 2024 Trigger Source Geo: 0.500 mm/s, Mic: 2.000 pa.(L)

Range Geo: 254.0 mm/s

Record Time 3.5 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM.MMB

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client:

User Name: PRISM JOHNSON LIMITED

General

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

MicrophoneLinear WeightingPSPL2.141 pa.(L) at 0.016 sec

ZC Freq 85 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1317 mv)

	Tran	Vert	Long	
PPV	1.955	3.909	2.191	mm/s
ZC Freq	27	64	51	Hz
Time (Rel. to Trig)	0.031	0.023	1.707	sec
Peak Acceleration	0.077	0.153	0.081	g
Peak Displacement	0.063	0.037	0.027	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.7	7.3	Hz
Overswing Ratio	3.6	3.2	3.6	

Peak Vector Sum 4.175 mm/s at 0.023 sec

Serial Number UM8131 V 10-76 Micromate ISEE

Battery Level 3.8 Volts

Unit Calibration January 29, 2024 by UES New Delhi File Name UM8131_20240311132959.IDFW


Post Event Notes

MNK/5TH BENCH/L MgO/WEST, No. of Holes 30 Nos

,DEPTH 9.89 M


Charge/delay- 64.2 Kg, Average Distance 250m.

DGMS India (B)



Frequency (Hz)
Tran: + Vert: × Long: Ø

a) Industrial buildingsb)Domestic houses/structures



Time Scale; 0.20 sec/div Amplitude Scale; Geo: 2.000 mm/s/div Mic: 1.000 pa.(L)/div Trigger =

Sensor Check

Printed: May 14, 2024 (V 10.72 - 10.72)

Format © 1995-2014 Xmark Corporation



Event Report

Velocity (mm/s)

Date/Time MicL at 13:49:33 March 27, 2024 Trigger Source Geo: 0.500 mm/s, Mic: 2.000 pa.(L)

Range Geo: 254.0 mm/s

Record Time 5.0 sec (Auto=7Sec) at 1024 sps

Operator/Setup: Operator/BGM.MMB

Notes

Location: Amalgamated Prism Cement and Bandarkha

Client:

User Name: PRISM JOHNSON LIMITED

General:

Extended Notes

Amalgamated Prism Cement and Bandarkha Limestone Mine

Microphone Linear Weighting

PSPL 4.577 pa.(L) at 0.006 sec

ZC Freq >100 Hz

Channel Test Passed (Freq = 19.7 Hz Amp = 1317 mv)

Tran	vert	Long	
2.215	4.973	3.712	mm/s
57	51	57	Hz
0.077	0.020	0.040	sec
0.098	0.154	0.137	g
0.114	0.052	0.040	mm
Passed	Passed	Passed	
7.3	7.7	7.1	Hz
3.5	3.3	3.6	
	2.215 57 0.077 0.098 0.114 Passed 7.3	2.215 4.973 57 51 0.077 0.020 0.098 0.154 0.114 0.052 Passed Passed 7.3 7.7	2.215 4.973 3.712 57 51 57 0.077 0.020 0.040 0.098 0.154 0.137 0.114 0.052 0.040 Passed Passed Passed 7.3 7.7 7.1

Peak Vector Sum 5.009 mm/s at 0.020 sec

Serial Number UM8131 V 10-76 Micromate ISEE

Battery Level 3.8 Volts

Unit Calibration January 29, 2024 by UES New Delhi File Name UM8131_20240327134933.IDFW


Post Event Notes

MNK/66 NO./5TH BENCH/L MgO/SOUTH, No. of Holes 29 Nos

DEPTH 9.52 M


Charge/delay- 59.5 Kg, Average Distance 250m.

DGMS India (B)



Frequency (Hz)
Tran: + Vert: × Long: Ø

a) Industrial buildingsb)Domestic houses/structures



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 2.000 pa.(L)/div Trigger =

Sensor Check

Digital Processing of Mining Leases- ML 772.067 Ha, 99.416 Ha, & 117.594 Ha, using Remote Sensing Technique for fulfillment of EC Compliance of Cement Unit Plant II and Intregrated Mines for Prism Johnson Ltd. in Satna, Madhya Pradesh.

Final Report- 772.067 Ha, 99.416 Ha, & 117.594 Ha.



PO No.: 3100210446-P027, dated 13.07.2023



Submitted By:

SPA GEO TECHNOLOGIES PVT LIMITED

8A, 3rd Floor, Mahaluxmi Metro Tower, C2, Sector -4, Vaishali, NCR, Ghaziabad - 201012

URL: www.spageo.co.in

Email: info@spageo.co.in; alok@spageo.co.in;

Tel: 91-120-4996793





Contents

1.1. Scope of Work 4 1.2. Objectives 4 1.3. Software 4 1.4. Study Area 4 1.5. Location Map 6 1.6. Satellite Image of Study Area 8 1.6.1. Satellite Image of 2021 8 1.6.2. Satellite Image of 2022 9 1.6.3. Satellite Image of 2023 10 2. APPROACH & METHODOLOGY 11 2.1. Flow Chart 12 2.2. Data Procurement 12 2.3. Satellite Data Processing 12 2.4. Rectification & Geo-referencing 12 2.4. Rectification & Geo-referencing 12 2.5. Image enhancement 12 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 18 <td colsp<="" th=""><th>1.</th><th>Int</th><th>rodu</th><th>uction</th><th>3</th></td>	<th>1.</th> <th>Int</th> <th>rodu</th> <th>uction</th> <th>3</th>	1.	Int	rodu	uction	3
1.3. Software 4 1.4. Study Area 4 1.5. Location Map 6 1.6. Satellite Image of Study Area 8 1.6.1. Satellite Image of 2021 8 1.6.2. Satellite Image of 2022 9 1.6.3. Satellite Image of 2023 10 2. APPROACH & METHODOLOGY 11 2.1. Flow Chart 12 2.2. Data Procurement 12 2.3. Satellite Data Processing 12 2.4. Rectification & Geo-referencing 12 2.5. Image enhancement 12 2.5. Image enhancement 12 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 19 Fig		1.1		Scope of Work	4	
1.4. Study Area 4 1.5. Location Map 6 1.6. Satellite Image of Study Area 8 1.6.1. Satellite Image of 2021 8 1.6.2. Satellite Image of 2022 9 1.6.3. Satellite Image of 2023 10 2. APPROACH & METHODOLOGY 11 2.1. Flow Chart 12 2.2. Data Procurement 12 2.3. Satellite Data Processing 12 2.4. Rectification & Geo-referencing 12 2.4. Rectification and Accuracy assessment 12 2.5. Image enhancement 12 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10. Finding of Study 17 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 18		1.2		Objectives	4	
1.5.		1.3		Software	4	
1.6. Satellite Image of Study Area 1.6.1. Satellite Image of 2021 8 1.6.2. Satellite Image of 2022 9 1.6.3. Satellite Image of 2023 10 10 2.		1.4		Study Area	4	
1.6.1. Satellite Image of 2021 1.6.2. Satellite Image of 2022 1.6.3. Satellite Image of 2023 1.0 2. APPROACH & METHODOLOGY 1.1 2.1. Flow Chart 2.2. Data Procurement 1.2 2.3. Satellite Data Processing 1.2 2.4. Rectification & Geo-referencing 1.2 2.5. Image enhancement 1.2 2.6. Classification and Accuracy assessment 1.2 2.7. Area Calculation 1.2 2.8. Overlay of Vector data base 2.9. Field Survey Images 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2023		1.5		Location Map	6	
1.6.2. Satellite Image of 2022 1.6.3. Satellite Image of 2023 1.0 2. APPROACH & METHODOLOGY 1.1 2.1. Flow Chart 1.2 2.2. Data Procurement 1.2 2.3. Satellite Data Processing 1.2 2.4. Rectification & Geo-referencing 1.2 2.5. Image enhancement 1.2 2.6. Classification and Accuracy assessment 1.2 2.7. Area Calculation 1.2 2.8. Overlay of Vector data base 2.9. Field Survey Images 1.4 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion 19 Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021		1.6		Satellite Image of Study Area	8	
1.6.3. Satellite Image of 2023 2. APPROACH & METHODOLOGY 2.1. Flow Chart 2.2. Data Procurement 2.3. Satellite Data Processing 2.4. Rectification & Geo-referencing 2.5. Image enhancement 2.6. Classification and Accuracy assessment 2.7. Area Calculation 2.8. Overlay of Vector data base 2.9. Field Survey Images 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021				1.6.1. Satellite Image of 2021	8	
2. APPROACH & METHODOLOGY 11 2.1. Flow Chart 12 2.2. Data Procurement 12 2.3. Satellite Data Processing 12 2.4. Rectification & Geo-referencing 12 2.5. Image enhancement 12 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10. Finding of Study 17 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 18 Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23				1.6.2. Satellite Image of 2022	9	
2.1. Flow Chart 2.2. Data Procurement 2.3. Satellite Data Processing 12 2.4. Rectification & Geo-referencing 12 2.5. Image enhancement 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 2.9. Field Survey Images 14 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021				1.6.3. Satellite Image of 2023	10	
2.2. Data Procurement 12 2.3. Satellite Data Processing 12 2.4. Rectification & Geo-referencing 12 2.5. Image enhancement 12 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10. Finding of Study 17 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 19 Figure Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23	2.	API	PRO/	ACH & METHODOLOGY	11	
2.3. Satellite Data Processing 2.4. Rectification & Geo-referencing 2.5. Image enhancement 2.6. Classification and Accuracy assessment 2.7. Area Calculation 2.8. Overlay of Vector data base 2.9. Field Survey Images 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 3. Conclusion Figure Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.1		Flow Chart	12	
2.4. Rectification & Geo-referencing 12 2.5. Image enhancement 12 2.6. Classification and Accuracy assessment 12 2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10. Finding of Study 17 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 19 Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.2		Data Procurement	12	
2.5. Image enhancement 2.6. Classification and Accuracy assessment 2.7. Area Calculation 2.8. Overlay of Vector data base 2.9. Field Survey Images 14 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion 19 Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.3		Satellite Data Processing	12	
2.6. Classification and Accuracy assessment 2.7. Area Calculation 2.8. Overlay of Vector data base 2.9. Field Survey Images 14 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion 19 Figure Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.4		Rectification & Geo-referencing	12	
2.7. Area Calculation 12 2.8. Overlay of Vector data base 12 2.9. Field Survey Images 14 2.10. Finding of Study 17 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion 19 Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.5		Image enhancement	12	
2.8. Overlay of Vector data base 2.9. Field Survey Images 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.6		Classification and Accuracy assessment	12	
2.9. Field Survey Images 2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.7	•	Area Calculation	12	
2.10. Finding of Study 2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.8		Overlay of Vector data base	12	
2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha) 17 2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 18 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.9		Field Survey Images	14	
2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23		2.1	0.	Finding of Study	17	
99.416 Ha & 117.594 Ha). 3. Conclusion Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23				2.10.1. Lime stone Mine 2021, 2022 & 2023 (772.067 Ha, 99.416 Ha & 117.594 Ha)	17	
Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23				2.10.2. Land use/Land Cover Map Of Buffer Zone-2021, 2022 & 2023 (772.067 Ha,		
Figure Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23				99.416 Ha & 117.594 Ha).	18	
Figure 1. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021 20 Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23	3.	Cor	ıclus	ion	19	
Figure 2. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022 21 Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23				Figure		
Figure 3. 772.067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023 22 Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23	Figure	1. 7	772.	067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2021	20	
Figure 4. 117.594 Ha, Lime Stone Mine Area Map of 2021 23	Figure	2. 7	772.	067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2022	21	
·	Figure	3. 7	772.	067 Ha, 99.416 Ha Lime Stone Mine Area Map of 2023	22	
Figure 5. 117.594 Ha, Lime Stone Mine Area Map of 2022	Figure	4. 1	117.	594 Ha, Lime Stone Mine Area Map of 2021	23	
	Figure	5. 1	117.	594 Ha, Lime Stone Mine Area Map of 2022	24	
Figure 6. 117.594 Ha, Lime Stone Mine Area Map of 2023 25	Figure	6. 1	117.	594 Ha, Lime Stone Mine Area Map of 2023	25	
Figure 7. Land Use/Land Cover Map Of Buffer Zone with 10 Sq.km (2021) 26	_			•		
Figure 8. Land Use/Land Cover Map Of Buffer Zone with 10 Sq.km (2022)	•			• • • •		
Figure 9. Land Use/Land Cover Map Of Buffer Zone with 10 Sq.km (2023)	_					





1. Introduction

Prism Johnson Limited is professionally managed Company promoted by the Rajan Raheja Group. Prism Johnson Limited is India's largest integrated Building Materials Company with a wide range from cement, readymixed concrete, tiles, bath products to kitchens. The Company has three Divisions, viz. Prism Cement, H & R Johnson (India), and RMC Readymix (India). Prism Cement primarily caters to the demand in the Northern Region, mainly in the States of Uttar Pradesh, Bihar and Madhya Pradesh. The capacity expansion has established the Division's brand in new markets and to a larger consumer base. A team of experienced engineers and a dedicated workforce combined with a high level of automation and sophisticated control systems have placed the Division's products in the premium segment.

Prism Johnson Ltd commenced its production in August 1997 and manufactures Portland Pozzollana Cement (PPC) with the brand name 'Champion' and Ordinary Portland Cement (OPC). It has the highest quality standards due to efficient plant operations with automated controls. It caters mainly to markets of UP, MP and Bihar, with an average lead of 340–370 km of its plant at Satna, MP. It has a wide marketing network with about 2,000 dealers serviced from 46 stocking points.

Cement and mining is seventh of the core industries that contribute significantly to the economic development of India . As for environment point of view, Line stone mining and installation of cement plant is a major habitat transforming activity is lead to change in land Use/Land cover. The change have been described as the most significant regional anthropogenic disturbance to the environment and are consistently with mining of natural resources.

Remote sensing and geographic information system (GIS) are important tool for studying the land use pattern and their dynamic . The change detection in Land use /land cover due to natural and human activities can be monitored by using multi date image to evaluate difference in land cover . The mapping of land use of classes and monitoring their changes with time has been widely recognized. The change detection in Land use/ Land cover due to natural and human activities can be monitored by using multi date images to evaluated differences in land cover where lime stone mines **Hinouti & Sijhatta ML 772.067 Ha, 99.416 Ha and Mendhi ML 117.594 Ha** and Cement Unit II are under operation by using multi temporal remote sensing data.

The concept, method and application of land use/land cover studies are introduced to mining area in order to find the land use change and give support to land management and ecological reconstruction. its prerequisite for planning, policy making and developmental program that land use /land cover information its spatial distribution and change in land use pattern is commonly used.





1.1 Scope of work

- 1. Collection of Primary data Raw satellite data to be obtained from NRSC.
- **2**. Base map to be prepared with help of survey of India Toposheet G44U14, G44V2 and other details.
 - 3. Data processing including following steps with the help of application software
 - a. Geometric correction, rectification and Geo referencing.
 - b. Image enhancement.
 - c. Training set selection.
 - d. Signature generation and classification.
 - e. Validation of classification image.
 - f. Final thematic map preparation.
 - 4. The map to be prepared on scale of 1:50000.
 - **5.** Comparative study with respect to land use change in the last three years.

1.2. Objectives

The main objective of present study is to understand land use /land cover change in the time and space , with special reference to the cement & mining activities being carried by M/s Prism Johnson Ltd, which is also one of the special condition of the environment clearance issued.

1.3. Software Used

- 1. ArcGIS 10.3
- 2. ERDAS Imagine
- 3. Microsoft Office

1.4. Study Area

The study area lies in Tehsil-Rampur baghelan and kotar, Satna district (MP) where cement Plant. The area is well connected to broad gauge line of central railway Linking ,satna with Rewa. The nearest major railhead is Satna on the jabalpur- Allahabad board guge section of central railway and is well connected to the major cities of the country. There is a good network of roads, there is an all weather motor able road up to project site. Location of Integrated Plant is 22 km from Satna City. from Satna city and 3 Km. from Satna - Rewa highway.





The details of the Mine lease areas are listed in the Table 1:

Table - 1


Details	Hinouti, Sijhatta and Mendhi Limestone Mine:	Integrated Cement Plant	Limestone Mine 772.067 Ha, 99.416 and 117.594		
Village	Hinouti, Sijhatta and Mendhi	Mankhari	Hinouti & Sijhatta	Mendhi	Baghai
Tehsil	Kotar	Rampur,Baghelan	Rampur,Baghelan	Rampur,Baghe lan	Rampur,Bag helan
District	Satna	Satna	Satna	Satna	Satna
State	Madhya Pradesh	Madhya Pradesh	Madhya Pradesh	Madhya Pradesh	Madhya Pradesh

Toposheet No.	G44U14 &G44V2	G44U14 &G44V2	G44V2	G44V2	
National	N.H 39 Gwalior to Rewa				
Highway					
Nearest River	Tamas River 2.15	Adjecnt to the	Tamas River 3.5	Tamas River:	
	Km.	boundary (In NW	Km. (NW of	4 Km. (NW of Baghai)	
		direction)	Baghai)		
Latitude	24°33'32.3"N	24°33'20.71"N	24°34'15.3."N	24°33'20.71"N	
Longitude	80°59'34.12"E	80°59'20"E	81°02'26.1"E	81°04'47.8"E	
Nearest Town	Satna (21 km)	Satna (18 Km)	Satna (24 Km)	Satna (23 Km)	
		Towards west	Towards west	Towards west	
Nearest Railway	Satna railway	Satna on the	Satna on the	Satna on the jabalpur-	
station	station (20Km.)	jabalpur-	jabalpur-	Allahabad board gauge	
		Allahabad board	Allahabad	section of west central	
		gauge section of	board gauge	Railway (20 KM.)	
		west central	section of west		
		Railway (18 KM.)	central Railway		
			(22 KM.)		
Nearest Airport	Khajuraho (120	Khajuraho (120			
	Km.)	Km.)			



1.5. Location Map


LOCATION MAPS OF Hinouti & Sijhatta ML 772.067 Ha, 99.416 Ha and Mendhi ML 117.594 Ha







ML BOUNDARY MAP: Hinouti & Sijhatta ML 772.067 Ha, 99.416 Ha and Mendhi ML 117.594 Ha









1.6. False Color Composites-FCC- Satellite Image of Study Area-2021-2022 and 2023

1.6.1 Satellite Image data-2021




1.6.2 Satellite Image data-2022





1.6.3 Satellite Image data-2023







2. APPROACH & METHODOLOGY

Indian remote sensing satellite LISS-III MSS & PAN geocoded data were used to analyze the land use/land cover pattern. The present study utilizes multi-spectral/multi-temporal data of the Indian remote sensing satellite LISS-III MSS & PAN for thematic mapping. Survey of India toposheet G44U14 & G44V2 on scale 1:50,000 were used for preparation of base map which was overlay on the LISS-III for land use /land cover mapping through visual interpretation. Visual interpretation of satellite imagery lead to the identification of fifteen land use/land cover categories. The ground troth verification was carried out in the key areas to rectify the errors in generated maps and then land use/land cover maps were finalized.

Data available gives uniform spectral and radiometric characteristics and minimize the seasonal variation. The survey of India topographic sheets No. G44U14 & G44V2 on scale 1:50,000 were used for preparation of base map. Secondary data obtained from published material. Visual interpretation is the effective method for classifying land use/land cover especially when the analyst is familiar with the area being classified from satellite data.


These categories were identify on the basis of visual interpretation of satellite data and ground truth verification were done in the key areas for editing and authentication. On screen digitization technique has been carried out to digitize the maps using Arc Map 10.3 software for land use analysis.

There are number of steps involved between RAW satellite data procurement and preparation of final maps. National Remote sensing Centre (NRSC). Hyderabad, being the nodal agency for satellite data supply in India, Provides only RAW digital satellite data, which needs further digital image processing for extracting the information and map preparation before uploading the same in the website. Methodology for land reclamation is given table no.2

With the invent of remote sensing and Geographical Information System (GIS) techniques, land use/cover mapping has given a useful and detailed way to improve the selection of areas designed to agricultural, urban and/or industrial areas of a region. Application of remotely sensed data made possible to study the changes in land cover in less time, at low cost and with better accuracy in association with GIS that provides suitable platform for data analysis, update and retrieval. The advent of high spatial resolution satellite imagery and more advanced image processing and GIS technologies, has resulted in a switch to more routine and consistent monitoring and modeling of land use/land cover patterns. Remote-sensing has been widely used in updating land use/cover maps and land use/cover mapping has become one of the most important applications of remote sensing.











2.2. Data Procurement:

After browsing the data quality and date of pass on internet, supply order for data is placed to NRSC. Secondary data like leasehold boundary, Toposheet are procured for creation of vector database.

2.3. Satellite Data Processing:

Satellite data are processed using *DIGITAL IMAGE PROCESSING SOFTWARE*. Mythology involves the following major steps.

2.4. Rectification & Geo-referencing:

Inaccuracies in digital imagery may occur to *systematic errors* attributes to earth curvature and ration as well as *non systematic errors* attributes to satellite receiving station itself. RAW digital contain geometric distortions, which make them unusable as maps. Therefore, Geo-referencing is required for correction of image data using ground control points (GCP) to make it compatible to SOI toposheet.

2.5. Image enhancement:

To improve the interpret-ability of the raw data, image enhancement is necessary. Local operations modify the value of each pixel based on brightness pixels using *DIGITAL IMAGE PROCESSING SOFTWARE* and enhance the image quality for interpretation.

2.6. Classification and Accuracy assessment:

Image classification is carried out using the maximum likelihood algorithm. The classification proceeds through the following steps :

(A) calculation of statistics for the identified training area, and correlation matrix. After evaluating the statistical parameters of the training sets is conducted by measuring the statistical separation between the classes that resulted from computing divergence matrix. The overall accuracy of the classification was finally reference to ground truth data.

2.7. Area Calculation:

The area of each land use class in the leasehold is determined using DIGITAL IMAGE PROCESSING SOFTWARE.

2.8. Overlay of Vector data base:

Vector data base created based on secondary data. Vector layer like drainage, railway line, Lease boundary, mines area, forest boundary water body etc.





2.9. Field Survey:

Field survey was carried out by taking selective traverses in order to collect the ground information (or reference data).









Digital Processing of Lease Area of Prism Johnson Ltd., Satna, Madhya Pradesh









Digital Processing of Lease Area of Prism Johnson Ltd., Satna, Madhya Pradesh





2.10. Finding of Study:

2.10.1. Hinouti & Sijhatta Lime Stone Mine (772.067 Ha, 99.416 ha).

Land use /land cover information derived from IRS LISS-III 2021, 2022 & 2023 (Table 2). Area statistic of each land use /land cover category were generated in GIS software and has been determined to analyze change in their spatial distribution. By comparing the land use/land cover maps, a change detection map has been generated in smart GIS software to assess the major changes in the Mines area **Hinouti & Sijhatta Lime Stone Mine (772.067 Ha, 99.416 ha).**

Table - 2 Hinouti & Sijhatta Lime Stone Mine Land use Details (772.067 Ha, 99.416 ha) (Fig.1,2 & 3)				
Description	2021 (Area In Ha)	2022 (Area In Ha)	2023 (Area In Ha)	
Crop Land	4.4034	6.9873	6.9873	
Agriculture-Fallow	632.2615	627.3555	625.4855	
Built up Land	53.8391	54.7602	54.9121	
Dumping Land	6.3650	6.9400	7.3158	
Limestone Quarry	114.4890	115.5595	116.0687	
Solar Power Panel	21.2207	21.2207	21.2207	
Water Body	8.7948	8.7948	9.2059	
Afforestation Land	30.1095	29.8650	30.2870	
Total	871.483	871.483	871.483	

2.10.2. Mendhi Lime Stone Mine (117.594 Ha).

Land use /land cover information derived from IRS LISS-III 2021, 2022 & 2023 (Table 2). Area statistic of each land use /land cover category were generated in GIS software and has been determined to analyze change in their spatial distribution. By comparing the land use/land cover maps, a change detection map has been generated in smart GIS software to assess the major changes in the Mines area **Mendhi Lime Stone Mine (117.594 Ha).**

Table - 3 Mendhi Lime Stone Mine Land use Details (117.594 Ha). (Fig.4, 5 & 6)				
Description	2021 (Area In Ha)	2022 (Area In Ha)	2023 (Area In Ha)	
Crop Land	4.0231	3.6853	3.6808	
Agriculture-Fallow	99.0252	100.0569	99.3934	
Built up Land	4.5268	4.5819	4.7912	
Dumping Land	0.7238	0.81327	0.9733	
Limestone Quarry	3.6971	3.9429	4.2416	
Afforestation Land	5.598	4.5137	4.5137	
Total	117.594	117.594	117.594	





2.10.3. Land Use/Land Cover Map Of Buffer Zone with 10 Sq.km. (772.067 Ha, 99.416 ha & 117.594 ha)

Land use /land cover information derived from IRS LISS-III 2020, 2021 & 2023 (Table 2). Area statistic of each land use /land cover category were generated in GIS software and has been determined to analyze change in their spatial distribution. By comparing the land use/land cover maps, a change detection map has been generated in smart GIS software to assess the major changes in the Mines area.

Table - 3 Land Use Details of Buffer Zone Hinouti & Sijhatta Mines 772.067 Ha, 99.416 ha & 117.594 ha (Fig. 7, 8 & 9)				
Description	2021 (Area in Ha)	2022 (Area in Ha)	2023 (Area in Ha)	
Cement plant unit II Boundary	116.8283	116.8283	116.8283	
Agriculture Fallow	39046.7118	38935.7413	38858.3309	
Dense Forest	1696.36692	1696.3669	1696.3669	
Lime Stone Quarry	118.1862	119.5024	124.9645	
Open Scrub	2056.7392	2103.0081	2138.6382	
Plantation	364.4824	367.2455	370.0884	
River/Water Body	1,258.9811	1273.6135	1268.4563	
Waste Land	15.3318	15.3318	15.3318	
Solar Power Panel Area	33.77038	33.7703	33.7703	
Crop Land	207.2149	246.8293	253.8772	
Plant Area	17.5111	17.5111	17.5111	
Reserved Forest	336.5917	336.5917	336.5917	
Open Mix Jungle	136.7960	136.7960	136.7960	
Other Quarry Land	361.5830	361.5830	373.6997	
Afforestation	34.132653	34.4534	34.950145	
BUILT UP LAND	3687.7487	3693.1390	3707.8936	
Road	49.5155	49.5155	49.5155	
Dumping Land	96.58963	97.25415	101.4707	
TOTAL	49635.0813 Ha	49635.0813 Ha	49635.0813 Ha	





3. Conclusion

The Present study reveals that mining and industrial activities around Prism Johnson Ltd. are the main forces responsible for land use land cover change during years from commencement of their operation. The mining has increased manifold that has resulted in change land use in terms of cultivated land and water bodies in the area.

Exploitation on natural resource in the area is going on due to the expansion of limestone mining activities, and other industrial activities. This report focuses on LU/LC changes in the Mine lease areas and buffer areas in and around to Prism Johnson Limited, Satna India, using remote sensing data and GIS technology. Our results clearly show that LU/LC changes were summarized during the period of **2021**, **2022 & 2023 in the Table no-3.** On the other hand there is minor change in agricultural area, water spread area, and forest areas. This study clearly indicates the significant impact of environmental and its development activities on LU/LC change. This study proves that integration of GIS and remote sensing technologies is effective tool for change detection. The quantification of LU/LC changes of Prism Johnson Ltd. area is very useful for environmental management groups, policy makers and for public to better understand the surrounding.






Fig:- 1 Hinouti & Sijhatta Lime stone Mine Land use Details 2021 (772.067 Ha, 99.416 ha)






Fig:-2 Hinouti & Sijhatta Lime stone Mine Land use Details 2022 (772.067 Ha, 99.416 Ha)






Fig:- 3 Hinouti & Sijhatta Lime stone Mine Land use Details 2023 (772.067 Ha, 99.416 Ha)






Fig:- 4 Mendhi Lime stone Mine Land use Details 2021 (117.594 Ha)






Fig:- 5 Mendhi Lime stone Mine Land use Details 2022 (117.594 Ha)






Fig:- 6 Mendhi Lime stone Mine Land use Details 2023 (117.594 Ha)






Fig: 7 Hinouti & Sijhatta and Mendhi Land use/Land Cover Map Of Buffer Zone-2021 (772.067 Ha, 99.416 Ha, 117.594Ha)




Fig: 8 Hinouti & Sijhatta and Mendhi Land use/Land Cover Map Of Buffer Zone-2022 (772.067 Ha, 99.416 Ha, 117.594Ha)






Fig: 9 Hinouti & Sijhatta and Mendhi Land use/Land Cover Map Of Buffer Zone-2023 (772.067 Ha, 99.416 Ha, 117.594Ha)





STATUS OF COMMITMENTS MADE DURING PUBLIC HEARING ON 22.05.2008


S.No	Name of Candidate	Suggestions & Points Raised	Reply of Project proponent	Present Status
1	Mrs. Guddi Devi, Chairperson "Garib Sangh Samiti" Bamhauri,	a) Admission on merit and free of fee for admission.	Provision for proper facilities will be considered.	Admission is given to the students of surrounding villages as per availability of seats and guidelines of the company. 25% seats have been reserved in the School for local villagers. Present strength of local students from surrounding villigages is 37%
	Satna	b) Plantation to be done from plant gate to Mahuracch Junction.	Agreed, plantation will be done during rainy season.	Plantation has been done on road side and around the Mankahari pond. Every year we distribute plantation to villagers and also do planation in surrounding areas. Photographs of roadside plantation is given below:
		c) Street light facility from plant gate to Mahuracch junction.	Work will be taken up by the management as per financial position of the company.	10 nos of Street lights up to Mahuracch junction is installed. Photographs of the solar lights are given Below

			Fino Permits and P	
		d) Permanent employment to affected person.	Employment will be granted as per rules and regulations of company.	Employment and other facilities are being provided to affected persons as per a requirement and eligible criteria
2	'Sarpanch' village Panchayat - Bathia, Satna	Employment to local villagers of Bamhauri	Employment will be granted as per rules and regulations of company.	Currently More than 80% employment has been given to local residents of MP. Preference is being given to the locals based of their eligibility and skills. Moreover, company conducts skill development programs in area of driving, beautician, stitching, bag making, agarbatti making, candle making etc. The company extends support for formation self help groups & in obtaining benefit of Govt/ Non Govt. schemes.
3	Mithilesh - (Student) Bamhauri, Satna	Appeal of Pollution Control Industry	All pollution control acts will be complied with	All due provisions have been made to combat pollution likely to be caused. Details of APCE's are as under 1. Raw mill/kiln - RABH (1) 2. Cooler - ESP (1)
				3. Coal Mill - Bag House (1)4. Cement mills - Bag House (2)5. 114 Bag filters installed to cover all the transfer points.
				6. Arrangement of water sprinkling at crusher hopper and limestone conveyor belt.

4	Mr. Triloki Singh Baghel, Village - Bamhauri, Satna	a) Priority to employment for eligible persons.	Employment will be granted as per rules and regulations of company.	7. Water Sprinkling on haul roads through tankers. 8. Greenbelt_plantation has been done as per EC condition Employment is being given to eligible persons as per the reqirement. Moreover, company conducts skill development programs in area of driving, beautician, stitching, bag making, agarbatti making, candle making etc. The company extends support for formation self help groups & in obtaining benefit of Govt/ Non Govt. schemes.
		b) Construction of stadium in the ground of Higher Secondary School.	Action will be taken.	The construction Stadium is complete now and the a photograph is enclosed below. Apart from that all the play groungs of the nearby villages has been developed. Fewo pictures of the stadium is enclosed below







[[
				3. Coal Mill - Bag House (1)
				4. Cement mills - Bag House (2)
				5. 114 Bag filters installed to cover all the transfer points.
				6. Arrangement of water sprinkling at crusher hopper and limestone conveyor belt.
				7. Water Sprinkling on haul roads through tankers. 8. Greenbelt_plantation has been done as per EC condition
7	Mr. Shankar Singh, Rtd. Commissioner, (Milk & Dairy Dept), 31 Rachna Nagar, Bhopal	Employment should be provided to effected villagers.	Employment will be granted as per rules & regulations of company.	Currently More than 80% employment has been given to local residents of MP. Preference is being given to the locals based of their eligibility and skills. Moreover, company conducts skill development programs in area of driving, beautician, stitching, bag making, agarbatti making, candle making etc. The company extends support for formation self help groups & in obtaining benefit of Govt/ Non Govt. schemes.
8	Mr. Ramadhar Prasad, Sarpanch, Village - Hinauti, Satna	Necessary assistance & help will be extended by him for the establishment of industry with the protection of environment from pollution	Thanks & All pollution control acts will be complied with	
9	Sarpanch, Village Panchayat - Mankahari, Satna	Expressed his consent to establish the industry	Thanks & Agreed	
10	Sarpanch, Village Panchayat - Sijahata, Satna	Expressed his consent to establish the industry	Thanks & Agreed	
11	Sarpanch, Village Panchayat - Sijahata, Satna	Suggested to plant 10000 saplings, seek help to improve health, sanitation facilities in villages and employment for educated persons.	Agreed, Plantation will be done during rainy season, health, sanitation and employment will be considered as per rules and regulation of company.	Improving green cover in and around plant premises is always company's utmost priority. Saplings are also distributed to village students to promote plantation & to make awareness. 608130 nos of plantation has been done in plants and mines, in addition to this 439422 nos of plant has been planted and distributed in surrounding villages and available barren areas. Villagers seeking medical attention also have easy access to medical centre of Prism Cement Plant free of cost. Apart from this, free medical camps are

				also being regularly organised in nearby villages.
				Employment is given as per eligibility and requirement. At presesnt at the beginning of this financial year more than 50% work force is local.
12	Mr. Diwakar Pd. Mishra , Mr Shankhadhar Mishra Panch - Village Bamhauri, Satna	Expressed his consent to establish the industry	Thanks & Agreed	
13	Mr. Sobha Nath Tiwari, Village - Bamhauri, Satna	Plantation to be done on road side & water spraying on roads.	Agreed.	Plantation is in continuous practice. Saplings are also distributed to villagers. Dedicated water tanker has been engaged on regular basis for water sprinking roads with higher traffic density
14	Mr. Tejpal Singh Parihar & Mr Shankhadhar Mishra, Village - Hinauti, Satna	Eradication of diseases & pollution from village Hinauti.	Best efforts and assistance will be extended.	Medicals camps and other awareness programmes are being organised by the company.
15	Mr. Ramesh Kumar Tiwari & Sarpanch Village Mankahari, Satna	Expressed his consent to establish the industry	Thanks & Agreed	
16	Mr. Girija Prasad Tiwari & Others, Village Panchayat Baghai.	Improvement in tree plantation, health, education, drinking water, employment & setting up of worship places.	All demands will be considered as per rules and regulations of company.	Plantation is in continuous practice. Saplings are also distributed to villagers. Villagers seeking medical attention also have easy access to medical centre of Prism Cement Plant. Apart from this, free medical camps are also being regularly organised in nearby villages. Study materials, bags, uniforms etc. are being distributed to the students of nearby villages. Free drinking water is being supplied through tankers during summer season as per requirement. Renovation of Jabala Baba Temple, construction of Ghat and Yagya Shala has been done by the company.





दिनॉक: 15.02.2022

सरपंच महोदय ग्राम पंचायत मनकहरी रामपुर बाघेलान, जिला सतना (म0 प्र0)

विषयः सामाजिक उत्तरदायित्व के तहत सरदार वल्लभभाई पटेल स्टेडियम मनकहरी मे कराये गये निर्माण कार्यों की सुपुर्दगी बावत।

प्रिज्म जॉनसन लिमिटेड मनकहरी द्वारा सामाजिक उत्तरदायित्व के तहत ग्राम पंचायत मनकहरी में स्थित सरदार वल्लभभाई पटेल में निम्न निर्माण कार्य कराये गये है-

- 1. पवेलियन का निर्माण (मंच, प्रसाधन एवं हाल)
- 2. 02 मिनी गैलरी का निर्माण
- 3. स्वागत गेट मय दरवाजा का निर्माण
- 4. मैदान के चारो तरफ बाउण्ड्रीवाल का निर्माण
- 5. पीने के पानी हेतु बोरवेल सबमर्सिबल पम्प के साथ

प्रिज्म जॉनसन लिमिटेड द्वारा उक्त निर्मित सुविधायें आज से ग्राम पंचायत मनकहरी को सुपूर्द की जाती हैं। कृपया प्राप्ति विवरण प्रदान करें।

धन्यवाद

ग्राप किया

वास्ते प्रिज्म जॉन्सन लिमिटेड

ग्राम पंचायत मनकहरी ज.पं. रामपुर वाघे; जिला सतना (म.प्र.)

देवेन्द्र मिश्रा एजीएम . सीएसआर एंड पब्लिक रिलेशन

PRISM JOHNSON LIMITED

(FORMERLY PRISM CEMENT LIMITED)

Works: Village Mankahari, P.O.-Bathia, Dist. Satna - 485 111 (M.P.) India T: +91-07672-275301 / 302600 Corres. Add.: 'Rajdeep', Rewa Road, Satna - 485 001 (M.P.) India. T: +91-07672-402726 Registered Office: Prism Johnson Limited, 305, Laxmi Niwas Apartments, Ameerpet. Hyderabad - 500 016, India. w:www.prismjohnson.in, www.cement.prismjohnson.in, E:info@prismjohnson.in

CIN-1 26942TG1992PLC014033

कार्यालय ग्राम पंचायत - मनकहरी

जनपद पंचायत- रामपुर बाघेलान, जिला - सतना (म.प्र.)

श्री रामनाथ साकेत

मोबा. : 8982629350, 9685700159



निवास : ग्राम- मनकहरी पोस्ट- बठिया (रामवन) तहसील-रामपुर बाघेलान जिला - सतना (म.प्र.)

दिनॉक: 23.02.2022

प्रिज्म जॉनसन लिमिटेड मनकहरी, सतना (म0 प्र0)

विषयः सामाजिक उत्तरदायित्व के तहत सरदार वल्लभभाई पटेल स्टेडियम मनकहरी में कराये गये निर्माण कार्यों की सुपूर्दगी बावत।

प्रिज्म जॉनसन लिमिटेड मनकहरी द्वारा सामाजिक उत्तरदायित्व के तहत ग्राम पंचायत मनकहरी में स्थित सरदार वल्लभभाई पटेल में निम्न निर्माण कार्य कराये गये है-

- 1. पवेलियन का निर्माण (मंच, प्रसाधन एवं हाल)
- 2. 02 मिनी गैलरी का निर्माण
- 3. स्वागत गेट मय दरवाजा का निर्माण
- 4. मैदान के चारो तरफ बाउण्ड्रीवाल का निर्माण
- 5. पीने के पानी हेतु बोरवेल सबमर्सिबल पम्प के साथ

ग्राम पंचायत मनकहरी प्रिज्म जॉनसन लिमिटेड का उक्त सुविधायों के निर्माण के लिये हृदय से आभारी है। आशा करता है भविष्य में भी ऐसे समाजोपयोगी कार्यों हेतू कंपनी का सहयोग प्राप्त होता रहेगा।

भवदीय



M.P. Pollution Control Board



E-5, Arera Colony Paryavaran Parisar, Bhopal - 16 MP Tele: 0755-2466191, Fax-0755-2463742

Consent Order

RED-LARGE CCA-Renewal PCB ID: 13880

OuTward No:122570,17/04/2025 The Occupier,

Consent No: AW-62064

M/s. Prism Johnson Ltd. (Cement Division Unit- II),

Village - Mankahari, P O Bathia, Mankahari,

Tal: Rampur Baghelan, Dist: Satna (M.P) - 485111.

Subject: Grant of Renewal of Consent to Operate under section 25 of the Water (Prevention & Control of Pollution) Act,1974

under section 21 of the Air (Prevention & Control of Pollution) Act,1981

Ref: Renewal of Consent to Operate Application R. No. 1403298 Dt. 05/03/2025 and last communication received on Dt.

25/03/2025.

With reference to your above application for renewal of consent to operate has been considered under the aforesaid Acts and existing rules therein. The M. P. Pollution Control Board has agreed to grant consent up to 30/06/2026, subject to the fulfillment of the terms & conditions, enclosed with this letter and-

SUBJECT TO THE FOLLOWING CONDITIONS :-

a. Location: Village - Mankahari, P O Bathia, Mankahari, Tal: Rampur Baghelan, Dist: Satna (M.P) - 485111.

SIDC: I/A Bamori Mankahari, Latitude: 24.5642 Longitude: 80.9991

b. The capital investment in Crs: Rs. 1426.44

c. Product & Production Capacity Per Year:

Product	Production Capacity
Cement	6.70 million TPA
	(Six point Seven million ton per year)
Clinker	3.0 million TPA
	(Three million metric ton per year)
Electricity From DG Set (1 X 6 MW)	6.0 MWH

Note --

- For any change in above industry shall obtain fresh consent from the board. 1.
- The Industry is permitted for Co-Processing of Hazardous wastes (in cement kiln as per the Guidelines and SOP issued by the CPCB) of such type, quantity and conditions mentioned in authorization issued to the industry under Rule -9 of Hazardous and other Waste (Management & Transboundary movement) Rules 2016, granted vide this office order outward no 115350 dated 15-12-2023.
- 3. Housekeeping near fly ash handling area and raw material handling area shall be improved & a system evolved to ensure good housekeeping inside the plant premises on continuous basis.

The Validity of the consent is up to 30/06/2026 and has to be renewed before expiry of consent validity. Online application through XGN with annual license fees in this regard shall be submitted to this office 6 months before expiry of the consent. Board reserves the right to amend/cancel / revoke the above condition in part or whole as and when required.

Enclosures:-

- * Conditions under Water Act, 1974
- * Conditions under Air Act, 1981
- * General conditions.

By the order of Chairman, MPPCB

ACHYUT ANAND MISHRA Member Secretary

(Organic Authentication on AADHAR from UIDAI Server) TPAV # 9EXNV43MUF

CONDITIONS PERTAINING TO WATER (PREVENTION & CONTROL OF POLLUTION) ACT 1974 :-

1. The daily quantity of trade effluent of the unit shall be Nil, and the daily quantity of sewage of the unit shall not exceed 200 KLD.

For other parameters general standards of discharge as notified under EP Act 1986 shall be applicable.

2. Sewage Treatment: The applicant shall O&M Sewage Treatment System properly to achieve following standards-

рН	Between	5.5 – 9.0	
Suspended Solids	Not exceed	100 mg/l.	
BOD ₃ Days 27 °C	Not exceed	30 mg/l.	
COD	Not exceed	250 mg/l.	
Oil and grease	Not exceed	10 mg/l.	
fecal coliform	Not exceed	1000 MPN/100 ml	

* The operator of the STP shall comply with the standards notified vide G.S.R. 1265(E) under sections 6 and 25 of the Environment (Protection) Act, 1986 by the Ministry of Environment, Forest and Climate Change New Delhi dated 13th October, 2017 as per Hon'ble NGT Directions or Guidelines.

- 3. The effluent shall be treated up to prescribed Standards and reuse in the process, for cooling and for green belt devolvement/gardening within premises. Hence zero discharge condition shall be practiced. In no case treated effluent shall be discharged outside of industry/unit premises.
- 4. Water meter preferably electromagnetic/ultrasonic type with digital flow recording facilities shall be installed separately for category wise consumption of water for Industrial cooling, mine spray, process & domestic purposes and data shall be submitted online through XGN monthly patrak/statements.

Sr	Water Code (Qty in KLPD)	WC: 1540	WWG: 200.000	Water Source	Remark
1	Cooling Water	1000	0.0	Mine Water	
2	Domestic Purpose	290	200	Borewell	Treated though STP
3	Plantation / Horticulture	250	0.0	Mine Water	Rain water stored in
					abonded mine pit

- 5. Any change in production capacity, process, raw material used etc. and for any enhancement of the above prior permission of the Board shall be obtained. All authorized discharges shall be consistent with terms and conditions of this consent. Facility expansions, production increases or process modifications which result new or increased discharges of pollutants must be reported by submission of a fresh consent application for prior permission of the Board.
- 6. All treatment/control facilities/systems installed or used by the applicant shall be regularly maintained in good working order and operate effectively/efficiently to achieve compliance of the terms and conditions of this consent.
- 7. The Consent does not authorize or approve the Construction of any physical structures or facilities or the undertaking of any work in any water course or within its high flood level (HFL) area.
- 8. The specific effluent limitations and pollution control systems applicable to the discharge permitted herein are set forth as above conditions.

9. Compilation of Monitoring data-

i. Samples and measurements taken to meet the monitoring requirements specified above shall be representative of the volume and nature of monitored discharge. ii. Following promulgation of guidelines establishing test procedures for the analysis of pollutants, all sampling and analytical methods used to meet the monitoring requirements specified above shall conform to such guidelines unless otherwise specified sampling and analytical methods shall conform to the latest edition of the Indian Standard specifications and where it is not specified the guidelines as per standard methods for the examination of Water and Waste latest edition of the American Public Health Association, New York U.S.A. shall be used.

10. Recording of Monitoring Activities & Results-

- i. The applicant shall make and maintain online records of all information resulting from monitoring activities by this Consent.
- ii. The applicant shall record for each measurement of samples taken pursuant to the requirements of this Consent as follows:
 - (i) The date, exact place and time of sampling
 - (ii) The dates on which analysis were performed
 - (iii) Who performed the analysis?
 - (iv)The analytical techniques or methods used and
 - (v)The result of all required analysis
- iii. If the applicant monitors any Pollutant more frequently as is by this Consent he shell include the results of such monitoring in the calculation and reporting of values required in the discharge monitoring reports which may be prescribed by the Board. Such increased frequency shall be indicated on the Discharge Monitoring Report Form.
- iv. The applicant shall retain for a minimum of 3 years all records of monitoring activities including all records of Calibration and maintenance of instrumentation and original strip chart regarding continuous monitoring instrumentation. The period of retention shall be extended during the course of any unresolved litigation regarding the discharge of pollutants by the applicant or when requested by Central or State Board or the court.

11. Reporting of Monitoring Results:-

Monitoring Information required by this Consent shall be summarized and reported by submitting a Discharge Monitoring report on line to the Board.

12. Limitation of discharge of oil Hazardous Substance in harmful quantities:-

The applicant shall not discharge oil or other hazardous substances in quantities defined as harmful in relevant regulations into natural water course. Nothing in this Consent shall be deemed to preclude the institution of any legal action nor relive the applicant from any responsibilities, liabilities, or penalties to which the applicant is or may be subject to clauses.

13. Limitation of visible floating solids and foam:

During the period beginning date of issuance the applicant shall not discharge floating solids or visible foam.

14. Disposal of Collected Solid waste/sludge-

All hazardous waste/sludge shall be disposed of as per the Authorization issued under Hazardous & other waste (M&TM) Rules 2016. And/other Solids Sludges, dirt, silt or other pollutant separated from or resulting from treatment shall be disposed of in such a manner as to prevent any pollutant from such materials from entering any such water Any live fish, Shall fish or other animal collected or trapped as a result of intake water screening or treatment may be returned to eaters body habitat.

15. Provision for Electric Power Failure-

The applicant shall assure to the consent issuing authority that the applicant has installed or provided for an alternative electric power source sufficient to operate all facilities utilized by the applicant to maintain compliance with the terms and conditions of the Consent.

16. Prohibition of By pass system of treatment facilities-

The diversion or by-pass of any discharge from facilities utilized by the applicant to maintain compliance with the terms and conditions of this Consent in prohibited except :

- i. where unavoidable to prevent loss of life or severe property damage, or
- ii. Where excessive storm drainage or run off would damage any facilities necessary for compliance with the terms and conditions of this Consent. The applicant shall immediately notify the consent issuing authorities in writing of each such diversion or by-pass in accordance with the procedure specified above for reporting non-compliance.
- 17. Industry management shall submit the information online through XGN in reference to compliance of consent conditions.
- 18. In case of any discharge found outside of unit premises the unit may be liable to pay environmental compensation as per NGT orders O.A. no 593/2017dated 22.02.2021 and the industry shall be punishable or court case may be filed by the Board under provisions of the Water (Prevention & Control of Pollution) Act, 1974.
- 19. The industry shall obtain PLI policy under provisions of PLI Act, 1991; if applicable.
- 20. The storm water shall not be allowed to mix with effluent, treated sewage, scrubber water and/ or floor washing. The storm water within boundary limits of industry shall be channelized through separate drains as per natural gradient passing through high density polyethylene pits each having holding capacity of 10 minutes of rainfall for its catchment.

CONDITIONS PERTAINING TO AIR (PREVENTION & CONTROL OF POLLUTION) ACT 1981 :-

1. The applicant shall operate and maintain air pollution control system to achieve the level of pollutants to the following standards:-

Name of section	Stack	Fuel	Control equipment to be	P.M, SO ₂ , NO _X (mg/Nm3)
	height(mtrs)	3	installed	
Cement Mill	49		Bag Filter,	30,NA,NA
Coal Mill	65		Bag Filter,	30,NA,NA
Clinker Cooler Exit	50		E.S.P,	30,NA,NA
D.G. Sets (1x6 MWH)	58	F.O	acoustic enclosure,	As per MoEF, CC notification &CPCB guidelines
Raw Mill Kiln	110	Coal/Petcoke	Bag Filter,	30,700,800

- 2. The Ambient air quality norms are prescribed in MoEF gazette notification no. GSR/826(E), dated: 16/11/09. Some of the parameters are as follows:
- a. Particulate Matter (less than 10 micron) 100 µg/m³ (PM10 µg/m³ 24 hrs. basis)
- b. Particulate Matter (less than 2.5 micron) 60 μg/m³ (PM2.5 μg/m³ 24 hrs. basis)
- c. Sulphur Dioxide [SO2] (24 hrs. Basis) 80 µg/m³
- d. Nitrogen Oxides [NOx] (24 hrs. Basis) 80 μg/m³
- e. Carbon Monoxide [CO] (8 hrs. Basis) 2000 µg/m3
- 3. The industry shall take adequate measures for control of noise level generated from industrial activities within the premises less than 75 dB(A) during day time and 70 dB(A) during night time.
- 4. Industry/Unit shall provide with each stack port hole with safe platform of 1 meter width with support & spiral ladder/ Stepped ladder with hand rail up to monitoring platform as per specifications given in part-III emission regulation of CPCB. In no case monkey ladder shall be allowed as stack monitoring facility.
- 5. The industry/unit shall make the necessary arrangements for control of the fugitive emission from any source of emission/section/activities.
- 6. All other fugitive emission sources such as leakages, seepages, spillages etc shall be ensured to be plugged or sealed or made airtight to avoid the public nuisance.
- 7. The industry/ unit shall ensure all necessary arrangements for control of odour nuisance from the industrial activities or process within premises.

- 8. All the internal roads shall be made pucca to control the fugitive emissions of particulate matter generated due to transportation and internal movements. Good housekeeping practices shall be adopted to avoid leakages, seepages, spillages etc.
- 9. Industry shall take effective steps for extensive tree plantation preferably the local tree species within or around the industry/unit premises for general improvement of environmental conditions.
- 10. Industry shall write name of the industry on stack with heat resistant paint.
- 11. The industry shall install Pneumatic Ash Handling System with Silo and proper Air Pollution Control Devices to ensure effective handling of Ash without causing any air pollution.
- 12. The industry shall install and maintain Online Continuous Emission Monitoring System (OCEMS) for particulate matter PM, SO₂, NOx with Raw mill kiln, Clinker cooler exit & cement mill stack with remote caliberation facility and connect the same with ESC, MPPCB Bhopal and CPCB for remote surveillance.
- 13. In case of emission found exceeding prescribed standards, the unit may be liable to pay environmental compensation as per NGT orders O.A. no 593/2017dated 22.02.2021 and the industry shall be punishable or court case may be filed by the Board under provisions of the Air (Prevention & Control of Pollution) Act, 1981.
- 14. The industry shall obtain PLI policy under provisions of PLI Act, 1991; if applicable.
- 15. The industry shall provide pneumatic system for the handling of AFR and permitted the use of non hazardous waste as AFR/raw material with annual maximum quantity as follows (as per CTE outward no 115822 dated 20-06-2022)

Sr. No.	Name of AFR	Quantity F Annum	er	Sr. No.	Name of AFR	Quantity Per Annum
1.	Biomass	792000 MT		11.	ETP Bio solids from soft drink industry	2000MT
2.	Dolachar	10000 MT		12.	Spent carbon from soft drink ind	15000 MT
3.	FGD Gypsum	130000 MT		13.	Waste mix liquid	30000MT
4.	Jarosite (Non-Hazardous)	6000 MT		14.	WTP sludge from soft drink Industry	7500MT
5.	MSW/RDF waste	20000 MT		15.	Waste Mix Solid	10000MT
6.	Non-Haz FMCG waste	3500 MT		16.	Synthetic Gypsum	12000MT
7.	Rice Husk	396000 MT		17.	Carbon Black	18000 MT
8.	Tire Chips	26400MT		18.	Polythene /Plastic Waste/Pouches	2105 MT
9.	Waste cloths cotton waste	20000 MT		19.	Chemical Gypsum	75000 MT
10.	Carbide lime sludge	20650MT		20.	Chemical waste Gypsum	36000 MT

- 16. The industry is permitted to use Pet Coke-210000 MT/Annum as feed stock or in the manufacturing process.
- 17. The industry shall Update regularly & furnish the online monthly patrak through XGN separately for indigenous /imported pet coke showing the balance quantity at the start of month, quantity procured during the month, the quantity consumed during the month as feedstock or in the manufacturing Process and the balance quantity in the end of the month.
- 18. Arrangements shall be made for the covered storage of Coal/ Pet coke, laterite/bauxite/Red Ochre, Fly ash, Gypsum, Clinkers and AFR. In no case these raw materials shall be stored in open.
- 19. The industry shall maintain the record of co-processing, generation and disposal of the hazardous wastes in the pass book provided by the Board and same shall be produced before the officers of Pollution Control Board during inspection or visit.
- 20. The industry shall dispose the hazardous waste through co-processing as mentioned in the authorization as per SOPs of CPCB guidelines limited to the quantity authorised by the Board.
- 21. The industry shall strictly comply with directions issued by CPCB/SPCB/MoEFCC/Hon'ble NGT from time to time.

GENERAL CONDITIONS:

1. The non hazardous solid waste arresting in the unit premises sweeping, etc. be disposed off scientifically so as not to cause any nuisance/pollution. The applicant shall take necessary permission from civic authorities for disposal to dumping site. If required.

Non Hazardous Solid wastes:-

Type of waste	Quantity	Disposal
Scrap/ Plastic packing material wood, card board, gunny bags etc (if any)	Record should be maintained	Re-Use/Sale to M.P. Pollution Control Board's authorized party

- 2. The applicant shall allow the staff of Madhya Pradesh Pollution Control Board and/or their authorized representative, upon the representation of credentials:
 - a. To inspect raw material stock, manufacturing processes, reactors, premises etc to perform the functions of the Board.
- b. To enter upon the applicant's premises where an effluent source is located or in which any records are required to be kept under the terms and conditions of this Consent.
 - c. To have access at reasonable times to any records required to be kept under the terms and conditions of this Consent.
 - d. To inspect at reasonable times any monitoring equipment or monitoring method required in this Consent: or,
 - e. To sample at reasonable times any discharge or pollutants.
- 3. This consent is transferable in nature, in case of any change in ownership / management, the new owner / partner / directors / proprietor shall immediately apply for the consent with new requisite information.
- 4. The issuance of this Consent does not convey any property rights in either real or personal property or any exclusive privileges, nor does it authorise any invasion of personal rights, nor any infringement of Central, State or local laws or regulations.

- 5. Industry shall install separate electric metering arrangement for running of pollution control devices and this arrangement shall be made in such fashion that any non functioning of pollution control devices shall immediately stop electric supply to the production and shall remain tripped till such time unless the pollution control device/devices are made functional.
- 6. This consent is granted in respect of Water pollution control Act 1974 and Air Pollution Control act, 1981 only and does not relate to any other Department/Agencies. License required from other Department/Agencies have to be obtained by the unit separately and have to comply separately as per there Act / Rules.
- 7. Balance consent fee, if any shall be recoverable by the Board even at a later date.
- 8. The applicant shall submit such information, forms and fees as required by the board not letter than 180 day prior to the date of expiration of this consent.
- 9. The industry/unit shall establish a separate environmental cell, headed by senior officer of the unit for reporting the environmental compliances. The industry/ Unit shall submit environmental statement for the previous year ending 31st March on or before 30th September every year to the Board.
- 10. Industry shall obtain membership of Emergency Response Center of the Board if needed.
- 11. Knowingly making any false statement for obtaining consent or compliance of consent conditions shall result in the imposition of criminal penalties as provided under the section 42(g) of the Water Act or section 38 (g) of the Air Act.
- 12. After notice and opportunity for the hearing, this consent may be modified, suspended or revoked by the Board in whole or in part during its term for cause including, but not limited to, the following:
 - (a) Violation of any terms and conditions of this Consent.
 - (b) Obtaining this Consent by misrepresentation of failure to disclose fully all relevant facts.
 - (c) A change in any condition that requires temporary or permanent reduction or elimination of the authorized discharge.
- 13. On violation of any of the above-mentioned conditions the consent granted will automatically be taken as canceled and necessary action will be initiated against the industry.
- 14. The industry/unit shall also monitor the treated wastewater flow and report the same online through monthly patrak/statements.
- 15. The applicant shall take samples and measurement to meet the monthly requirements specified above and report online through XGN the same to the Board.
- 16. Ambient air quality at the boundary of the industry/unit premises shall be monitored and reported to the Board regularly on quarterly basis
- 17. The record of electricity consumption for running of pollution control equipment shall be maintained and submitted to the Board every month.
- 18. The industry shall operate the Outdoor HD Industrial grade IP (Internet Protocol) Cameras with pan-Tilt-Zoom (PTZ) feature, minimum focal length 30X with night vision facility and temper proof mechanism at suitable location to display all emission sources and effluent discharge point shall be kept operational & in working order and connect the same with Environment Surveillance Centre of MP Pollution control board Bhopal for remote surveillance.
- 19. Industry shall ensure regular operation and maintenance of canyons water foggers installed in the plant. They must be kept in working condition at all times.

Advisory conditions:-

- 1. The management shall obtain valid NOC from Central Ground Water Board for extraction of ground water.(if applicable)
- The management shall install Digital Water meter with digital flow recording facilities for measurement of ground water consumption
 and provide its connectivity with server of Environment Surveillance Centre, M P Pollution Control Board Bhopal for remote
 surveillance
- 3. The management shall provide Rain water harvesting for ground water conservation and recycle treated waste water for plantation and flushing in consultation with expert agency if find suitable).
- 4. Potable drinking water shall be used for drinking purposes only.
- 5. Appropriate legal action shall be initiated in case of violation of above mentioned conditions by the competent authority.

Renewal of Consent as required under the Water (Prevention & Control of Pollution) Act, 1974, The Air (Prevention & Control of Pollution) Act, 1981 is granted to your industry subject to fulfillment of all the conditions mentioned above. For renewal purpose you shall have to make an application to this Board through XGN at least Six months before the date of expiry of this consent. The applicant without valid consent (for operation) of the Board shall not bring in to use any outlet for the discharge of effluent and gaseous emission.

By the order of Chairman, MPPCB

M.P Scharl mishing pard

ACHYUT ANAND MISHRA Member Secretary

Seeding from UIDAI
201101
Dipitally Sign with Andham

(Organic Authentication on AADHAR from UIDAI Server) TPAV # 9EXNV43MUF

Ambient Air Quality Monitoring Report Month -March 2025

NAME & ADDRESS OF FACTORY

PRISM JOHNSON LIMITED

VILLAGE: MANKAHARI POST : BATHIA

DISTT: SATNA (M.P.)

NAME OF PERSON SENDING THE REPORT AMBIENT AIR QUALITY MONITORING

Ankita Singh Parihar

I. DURATION

8*3 = 24 HRS

LOCATION (1) - GUEST HOUSE

500 M 650 M

II. DISTANCE FROM FACTORY

LOCATION (2) - NEAR STACKER LOCATION (3) - NEAR ADMIN BUILDING LOCATION (4) - NEAR STEEL YARD

400 M 450 M

III. WIND DIRECTION

MENTIONED IN TABLE

	Location -1			Location -2				Location -3			Location -4										
Date	PM 10	PM2.5	SO2	NOX	СО	PM 10	PM2.5	SO2	NOX	co	PM 10	PM 2.5	SO2	NOX	со	PM 10	PM2.5	SO2	NOX	СО	Wind Direction
	µg/М3	цд/М3	дд/М3	μg/М3	µg/М3	μg/M3	μg/ M3	μg/M3	μg/M3	µg/М3	μд/М3	μg/ M3	µg/М3	дд/М3	μg/М3	цд/М3	дд/М3	µg/М3	цд/М3	цд/М3	
01.03.2025	58.53	26.63	14.17	23.53	BDL	54.30	28.42	15.19	25.42	BDL	60.46	28.87	13.88	22.92	BDL	59.48	27.39	12.15	20.22	BDL	SE
03.03.2025	53.69	25.51	13.50	22.06	BDL	55.85	27.36	14.58	25.00	BDL	5548	27.85	13.25	24.27	BDL	54.65	26.31	11.04	21.57	BDL.	SE
05.03.2025	43.84	22.05	12.15	21.57	BDL	49.94	24.69	15.46	24.27	BDL	44.98	25.00	14.17	23.53	BDL	44.95	28.73	12.15	20.80	BDI.	SE
07.03.2025	58.49	25.06	13.88	24.27	BDL	53.10	27.50	14.17	26.24	BDL	62.01	31.36	13.50	22.06	BDL	56.40	28.12	13.25	22.24	BDL	SE
09.03.2025	55.33	27.29	11.04	21.03	BDL	59.60	30.95	13.88	25.42	BDL	57.90	31.67	12.15	23.11	BDI.	55.05	24.23	13.25	24.27	BDL	NE
11.03.2025	52.32	28.42	13.50	23.11	BDL	50.09	29.70	15.19	25.00	BDL	56.45	32.09	12.15	22.24	BDL	56.75	23.30	11.04	20.80	BDL.	SE
13.03.2025	59.18	29.49	14.17	24.27	BDL	58.11	30.76	14.58	25.17	BDL	64.05	31.42	13.88	23.53	BDL	61.00	29.81	13.25	22.65	BDL.	SE
15.03.2025	61.10	33.41	13.88	23.37	BDL	51.03	34.82	14.17	26.29	BDL	65.52	35.08	13.25	22.92	BDL	63.00	32.66	12.15	21.57	BDL	SE
17.03.2025	49.30	31.48	15.19	25.42	BDL	57.26	33.31	15.46	27.73	BDL	53.10	34.88	14.17	24.27	BDL.	51.08	32.20	13.50	23.53	BDL	SE
19.03.2025	54.96	32.18	14.58	25.00	BDL	52.28	33.85	16.25	26.96	BDL	59.63	33.98	13.88	23.11	BDL	55.54	33.27	13.25	22.92	BDL.	SE
21.03.2025	44.91	35.17	14.17	24.27	BDL	51.66	36.17	14.58	27.50	BDI.	50.05	37.83	13.50	23.92	BDL.	45.80	35.91	12.15	23.53	BDL.	NE
25.03.2025	50.58	34.57	13.25	22.92	BDI.	56.16	35.89	15.19	25.62	BDI.	55.28	36.24	14.17	23.37	BDL.	51.25	35.17	13.50	21.57		
27.03.2025	64.06	21.18	13.88	23.53	BDL	58.81	22.98	15.46	25.88	BDL	66.22	23.34	14.17	24.27	BDL.	67.40	21.36			BDL	SE
31.03.2025	61.22	20.01	14.58	25.17	BDL	58.56	24.27	16.20	26.29	BDL	64.06	24.89	13.88	23.53	BDL	63.29	21.36	13.25	23.11	BDL BDL	NE SE

Sumitabh Dwivedi Asst.General Manager- Environment Prism Johnson Ltd. Satna (M.P.)

Manoj Kumar Vice President

Prism Johnson Ltd. Satna (M.P.)





Ref: PJL/ENV/2025/F03/938

Date: 09.04.2025

To,
The Member Secretary
M.P. Pollution Control Board
Paryavaran Parisar
Sector E-5, Arera Colony
Bhopal – 462016 (M.P.)

Sub: Monthly Air / Water Quality Monitoring Reports of Prism Johnson Ltd Unit-II

Dear Sir,

We are herewith submitting monthly Air Quality Monitoring Report for Plant, Treated Effluent (from Sewage Treatment Plant) Quality Monitoring Report, Water Consumption, Noise Monitoring report & Performance Report of main air pollution control equipment & Sewage Treatment Plant, for the month of March'2025.

Thanking You
Yours Faithfully,
For PRISM JOHNSON LIMITED

Manoj Kumar Vice President

Encl: As above,

CC: Regional Officer, MPPCB, Satna

PRISMJOHNSON LIMITED

(Cement Division)





STACK MONITORING REPORT FOR CEMENT PLANT (UNIT-II) MONTH - MARCH 2025

PRISM JOHNSON LIMITED NAME & ADDRESS OF FACTORY ż

VILLAGE: MANKAHARI POST : BATHIA

DISTT: SATNA (M.P.)

Ankita Singh Parihar

NAME OF PERSON SENDING THE REPORT B.

BIG SIZE BAG FILTER ATTACHED APCE **BAG HOUSE** STACK No. STACK 2 STACK 3 STACK 1 STACK DETAILS RAW MILL + KILN COAL MILL SECTION COOLER

CEMENT MILL - 1 CEMENT MILL - 2

STACK 4 STACK 5

BAG HOUSE

BAG HOUSE

Level of PM (Monitored by Isokinetic sampling) Mg/Nm3 18.74 21.78 14.33 15.77 16.21 (Monitered by continuous dust (CEMS) Monthly Avg. monitor)* Mg/Nm3 14.70 13.14 12.77 6.21 14.91 (CEMS) Monthly Avg. (CEMS) Monthly Avg. Mg/Nm3 NOx* 377.94 Not Applicable Mg/Nm3 92.05 **SO2*** STACK No. STACK- 4 STACK-3 STACK-5 STACK-1 STACK-2 12.03.2025 12.03.2025 16.03.2025 20.03.2025 20.03.2025 Date SI. No.



Sumitabh Dwivedi Asst.General Manager- Environment Prism Johnson Ltd. Satna (M.P.)

30

Manoj Kumar Vice President Prism Johnson Ltd. Satna (M.P.)

TEST REPORT





ULR No.

: TC1122725000000790F

Report No.

: VTL/WW/2503280011/A

M/s PRISM JOHNSON LIMITED

Format No

: 7.8 F-01

Village- Mankahari, Tehsil- Rampur Baghelan, Dist. - Party Reference No : NIL Satna (M.P.)

Report Date

: 02/04/2025

Sample Description

Name & Address of the Party

Period of Analysis

: 28/03/2025-02/04/2025

Sampling Location

: Waste Water : Mines Workshop

: Suitable Preservation

Receipt Date

: 28/03/2025

Sampling Date

: 27/03/2025

Sample Collected By

Preservation

: VTL Team

Sampling Type Sample Quantity : Grab

Method of sampling

: IS:3025

Coordinates

: 2 Ltr.

	. 15 .5025		Coordinat	es	
S.No.	Test Parameters	Test Method	Result	Unit	Limits
1	рН	IS: 3025 (P-11): 2022	7.49	-	5.5 to 9.0
2	Total Suspended Solids (TSS)	IS: 3025 (P-17): 2022	23.2	mg/L	100
3	Total Dissolved Solids (TDS)	IS:3025 (P-16): 2023	894.0	mg/L	2100
4	Oil & Grease	IS:3025 (P-39): 2021	*BLQ(**LOQ-4.0)	mg/L	10
5	Biochemical Oxygen Demand (BOD) (3 days @ 27°C)	IS: 3025 (P-44): 2023	11.0	mg/L	30
6	Chemical oxygen Demand (COD)	IS: 3025 (P-58): 2023	50.0	mg/L	250
7	Faecal coliform	APHA 24th Edition 9221 C: 2023	47	MPN/100 ml	

^{*}BLQ-Below Limit OF Quantification, **LOQ- Limit Of Quantification

End of Report







RK Yadav Lab Incharge Authorized Signate



Page No. 1/1

Approved & Certified EPA 1986 Recognised, ISO:9001 and OHSAS:45001 Certified

- SC-40, 3rd Floor, Narayan Vihar S, Ajmer Road, Jaipur Raj. 302020
- 9929108691, 9810205356, 8005707098, 9549956601

2 0141-2954638

bd⊚vibranttechnolab.com

www.yibranttechnolab.com

DeotaleDiagnost Diagnostics Health Check-Ups Immunization.

Consultation

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chouk Nagpur For any assistance call at . 9860204241, 0712-2424868

Email ID: deotaledeepak19577@gmail.com

MEDICAL CHECK-UP F	REPORT	
SR NO.	4	
Certificate No	7	
EMP CODE	102178	
Work Station / Grade	G	
Designation	Mines Foreman	
MOB NO	8109339836	
CHECK-UP DATE	11-12-24	

EMPLOYEES NAME: Ashok Kumar Tiwari Rishi Dev Tiwari

Wt: 83 Kg BMI: 28.06 Ht: 172 cms Gender: MALE Age: 52 Yrs

Company Address: PRISM JOHNSON LIMITED,

MPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.)

	MANKAHARI,PO: E	DAUTIELITY DE	GUTKHA: NO	
Personal H/O:	ALCOHOL: NO	TABACCO: NO	SMOKING: NO	PLUSE: 95 mm/hr
General Exam:-	Healthy	BP .: 162/89 m	IIIIII	SP/LIVER:N/P
C.V.S.: N	R/S: N	CNS :N	V	SP/LIVER III/

Abdomen: soft

BLOOD TEST			00012			Normal Range	
Test			Result			70-160 mg/dl	
Blood Sugar			200 mg/dl			12.5 to 16.5 gm/dl	
Hemoglobin			12.8 gm/dl 7300 Cumm			4000-11000 /Cumm	
Total Leukocyte Cour	ıt		75 %			40-80 %	
Neutrophils			20 %			20-40 %	
Lymphocyte			3 %			1-6 %	
Eosinophils			2 %			2-10 %	
Monocytes			8 mm/hr			< 20 mm/hr	
ESR			169 mg/dl			< 220 mg/dl	
Cholesterol			153 mg/dl		-	> 200 mg/dl	
Triglycerides			43 mg/dl			35 TO 50 mg/dl	
HDL							
LDL			95.4 mg/dl				
VLDL			30.6 mg/dl				
CHO/HDL Ratio:			3.9			10-50	
Urea		23 mg/dl					
Creatinine			0.9 mg/dl			0.8-1.3	
			30 U/L			0-40	
SGPT			23 U/L			0-40	
SGOT		NEGATIVE					
S[UTUM AFB		NEGATIVE					
STOOL		NO					
Colour Blindness		WNL					
ECG		WNL		Spiron	netry	WNL	
X-Ray		RT: WNL]	LF. WNL		
AUDIOMETRY	Unaided - Dis				Dist. Lf		
Vision:	Unaided - Nea				Near Lf		
	With Spect Di					ect Dist . Lf -	
	With Spect Ne					ect Near . Lf -	
MEDICAL CHECK - UP:-	NORMAL.					A Designation of the Assessment of the Conference of the Conferenc	
Opinion Ha/Shais nh	vsically & ment	ally fit . He/She is	s not suffering f	rom any	infectiou	s or contagious diseases	
Opinion. Inclosio is bas						92	

Dr. DEEPAK P. DEOTALE M.B.B.S. A.F.I.H.(Reg. No. 48366)



(FORM – 0) (See rule 29F (2) and 29L)
Report of medical examination under rule 29B (To be issued in triplicate)

** Certificate No Certified that Shri/Shrimati* . Ashak . Kuman . Tiwan examination. He/she* appears to be..... years of age.

The findings of the examining authority are given in the attached sheet. It is considered that Shri/Shrimati* Ashok .. Kuman .Tiwari.....

- (a)* is medically fit for any employment in mines.
- (b)* is suffering from..... and is medically unfit for

- (i) any employment in mine; or(ii) any employment below ground; or
- (iii) any employment or work......

(c)* is suffering from..... is should get this disability* cured/controlled and should be again examined within a period ofmonths. He/She will appear for re-examination with the result of test of and the opinion of Specialist from He/She may be permitted/not* permitted to carry on his duties during this period.



Place: PCL Date:

DR. DEEPAK P. DEOTALE Signature of the examining authority Name and designation in Block letters

* Delete whatever is not applicable. One copy of the certificate shall be handed over to the person concerned and another copy shall be sent to the manager of the mine concerned by registered post; and the third copy shall be retained by the examining authority,

Report of the examining authority

(to be filled in for every medical examination whether initial or periodical or reexamination or after cure/control of disability).

Identification Mark Scan on face left side

Left thumb impression of the candidate

1. General development- Good/Pain/Poor
2. Height
3 Weightkg.
4 Eyes : (i) Visual acuity-Distant vision (with or without glasses).
Right eye6.19 Left eye6.19
(ii) any organic disease of eyes (90
(iii) night blindness $\sqrt[6]{0}$
(iv) Colour blindness $\rho \sigma$
(v) Squint (* to be tested in special cases) Inserted vide notification No.GSR 656 dated 5.6.1980
5 Ears: Hearing: Right ear
Any organic diseases.
6.Respiratory system. Chest measurement : (i) After full inspirationcms. (ii) After full expirationcms.
7. Circulatory system: (i) Blood Pressure
8. Abdomen: Tendemess 56 Liver. Spleen. Tumour. 100
9. Nervous system: History of fits or epilepsy Paralysis Mental health.
10.Locomotory system :
11. Skin. :
12. Hydrocele
13. Hernia. :
14. Any other abnormality:
15. Urine : Reaction
16. Skiagram of chest.: WPL
17. Any other test considered necessary by the examining authority. : NO
18. Any opinion of specialist considered necessary.
Signature of the examining authority
Place:

Report of Medical Examination under Mines Rule 29B (To be used in continuation with Form O)

Certificate No.

Name: AshoK Kumar Tiwari

Identification Marks: Scar on face left 81'de

Result of Lung Function Test (Spirometry)

	1 = 11 4 - d Value	Performed Value	% of Predicted
Parameters	Predicted Value	2 11	696
Forced Vital Capacity (FEV)	3.47	3.0	109
Forced Vital Capacity FEV1	1-/116	3,01	121.
FEV 1/ FVC	86.00	96 91	878
Peak Expiratory Flow	8.17	1 2.11	

Spirometry Report enclosed.

Signature of the Examination Authority

Report of Medical Examination as per the recommendations of National Safety Conferences in Mines (To be used in continuation with Form O)

Certificate No. 7

Name: Ashok kuman Tiwari

Identification Marks: SCar on bace light si'de

1. Cardiological Assessment

Auscultation	S ₁	N	Performed Value	% of Predicted
Auscultation	S ₂	N		
	Additiona	al Sound No		
FEV1/FVC			96:47	2
Electrocardiogra	ph(12leads) fi	ndings	Normal/Abnormal	

Enclosed ECG

2. Neurological Assessment

Dr. Deepakagoibtifie	Normal/Abnormal	
Superficial Reflexes WITA 288M	Mosmal	
Deep Reflexes	10	
Peripheral Circulation	N	
Vibrational Syndromes	, b	

3. ILO Classification of Chest Radiograph

Profusion of Pneumoconiotic Opacities	Grades	Types
Present /Absent		

Enclosed Chest Radiograph

4. Audiometry Findings:

		Dight For
Condution Type	Left Ear	Right Ear
Ear Conduction	Normal/Abnormal	-Normal/Abnormal
Bone Conduction	Normal/Abnormal	Normal/Abnormal

Enclosed Audiometry Report

5. Pathological/Microbiological Investigations:

S No. Tests		Findings
S.No.		WNL/Abnormal
1.	Blood-Tc,Dc,Hb,ESR,Platelets	WNL/Abnormal
2.	Blood Suger-Fasting & P.P.	
3.	Lipid Profile	WNL/Abnormal
4	Blood Urea, Creatimine	WNL/Abnormal
<u>4.</u>	Urine Routine	WNL/Abnormal
5.	Stool Routine	WNL/Abnormal
6.	Stool Routine	

Enclosed Investigation Reports

6. Special Tests for Mn Exposure:

Reha	avioral Disturbances	Present/Not Present
	Speech Defect	Present/Not Present /
Neurological Disturbances	Tremor	Present/Not Present
	Adiadocokinesia	Present/Not Present
	Emotional Changes	Present/Not Present

Enclosed ECG

7. Any other Special Tests Required: 100

Signature of the Examination Authority
Seal


JK KUMAR TIWARI


RECORDERS -12-2024 10:50:29


Age : 47 Years Height : 172 Cms

Weight: 83 Kgs ID: PR 07 Gender : Male Smoker : No Eth. Corr: 100 Temp : degrees











		FVC R	esults					
Parameter		Pred	M. Pre	Pred	M. Post	%Pred	%Imp	
FVC	(L)	03.45	03.12	090				
FEV1	(L)	02.76	03.01	109				
FEV1/FVC	(%)	80.00	96.47	121				
FEF25-75	(L/s)	03.66	03.77	103				
PEFR	(L/s)	08.75	05.11	058				
FIVC	(L)		01.17					
FEV.5	(L)		02.17					
FEV3	(L)	03.35	03.12	093				
PIFR	(L/s)		03.33					
FEF75-85	(L/s)		01.94					
FEF.2-1.2	(L/s)	06.52	04.69	072				
FEF 25%	(L/s)	07.81	05.11	065				
FEF 50%	(L/s)	05.46	04.01	073				
TEF 75%	(L/s)	02.46	02.45	100				
FEV.5/FVC	(%)		69.55					
FEV3/FVC	(%)	97.10	100.00	103				
FET (Sec)			01.19					
	(Sec)		00.15					

Pre Medication Report Indicates
Early Small Airway Obstruction as FEF 25-75 %Pred or PEFR %Pred < 70
Spirometry within normal limits as (FEV1/FVC)%Pred >95 and FVC%Pred >80.







Deotale Diagnostic Centre (we care)

Consultation — Diagnostics — Health Check- Up: — Immunization.

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chowk Nagpur


(Clinic Reg. No. 699)

For any assistance call at . 9860204241, 0712-6610595

Date: 11-12-24

AUDIOLOGICAL EVALUATION

2. CERTIFICATE NO: 7 1. SR. NO. 4 3. EMPLOYEES NAME: Ashok Kumar Tiwari Rishi Dev Tiwari 4. Employee Mob No : 8109339836 7. AGE: 52 yrs 6. SEX: MALE 8. ADDRESS: PRISM JOHNSON LIMITED, MANKAHARI,PO: BATHIA, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.) RT.: WNL 9. DIAGNOSIS LT.: WNL



Air O = LEFT EAR : •	WNL WNL
Masking No Response: Audiologists Remarks	

Dr. DEEPAK P. DEOTALE M.B.B.S. A.F.I.H. Reg. No. 48366

DeotaleDiagnosticCentre

Consultation

Diagnostics

Health Check- Ups

Immunization.

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chouk Nagpur

For any assistance call at . 9860204241, 0712-2424868

Email ID: deotaledeepak19577@gmail.com

Patient Name:	Ashok Kumar Tiwari Rishi Dev Tiwari
Age:	52 yrs.
Gender:	MALE
Req. Doctor:	
Reg . Number:	8109339836
Collection Date:	11-12-24
Reporting Date :	11-12-24

SPUTUM EXAMINATION

ZEIHL NEELSEN STAIN: AFB Not seen

DR .DEEPAR DEVATALE
M.B.B.S A.F.I.H(REG NO.48366)
Dr. Deepak Deotale
MBBS, AFIH
Reg. No. 48366

SR. No.

4

Certificate No.

7

Emp Code

102178



MAYA HOSPITAL

& RESEARCH INSTITUTE

Add.: Plot .P 78, Opposite State Bank of India , M.I.D.C.

Butibori (Nagpur)

Ph 07103-684885

Deotale Diagnostic Center We Care

_ Consultation _ Diagnostics Health _ Check-Ups _ Immunization

Dr. Deepak P. Deotale M.B.B.S., A.F.I.H.

(Associated fellow Of industrial health)

Certifying Surgeon Reg .No. 48366

Clinic: Vinayak Apt. 3rd floor Dhantoli,

Lokmat Chowk , Nagpur (Clinic Reg. No. 699)

Mob. No. 9860204241 /8007771341

Phone No: 0712-2424868

Email Id:deotaledeepak19577@gmail.com

Name	Ashok Kumar Tiwari Rishi Dev Tiwari
Age	52 YRS.
Gender	MALE
Check Up Date	11-12-24
MOB NO	8109339836

Company Name: PRISM JOHNSON LIMITED,

MANKAHARLPO: EATHEL, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.)

Deotale Diagnostic Centre Well Diagnostics Health Check-Ups Immunization.

Consultation

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chouk Nagpur For any assistance call at . 9860204241, 0712-2424868

Email ID: deotaledeepak19577@gmail.com

MEDICAL CHECK-UP REPORT

MEDICAL CHECK-OI	TEL ORY
SR NO.	157
Certificate No	166
EMP CODE	102702
Work Station / Grade	BAGHAI MINES
Designation	ASST. MANAGER
MOB NO	9584460761
CHECK-UP DATE	13-12-24
LHELK-UF DAIL	

EMPLOYEES NAME: ATUL KUMAR TIWARI

Wt: 65 Kg BMI: 25.39 Ht: 160 cms Gender: MALE Age: 57 Yrs

Company Address: PRISM JOHNSON LIMITED,

MANKAHARI,PO: BATHIA, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.)

	MANKAHARI,PO: E	BATHIA, TEHSIL: RAMPUR	SMOKING: NO	GUTKHA: NO
Personal H/O:	ALCOHOL: NO	IADACCO, NO		PLUSE: 100 mm/hr
General Exam:-	Healthy	BP .: 150/100	IIIIIII	SP/LIVER:N/P
C.V.S.: N	R/S: N	CNS :N		
41 1 0				

Abdomen: soft

2	T	0	0	n	T	EST
2	ш	v	U	v	A	101

LOOD TEST			Result		Normal Range
Test			Tangara Comment		70-160 mg/dl
Blood Sugar			123 mg/dl		12.5 to 16.5 gm/dl
Hemoglobin		15	12.9 gm/dl 7900 Cumm		4000-11000 /Cumm
Total Leukocyte Count			68 %		40-80 %
Neutrophils			30 %		20-40 %
Lymphocyte			1%		1-6 %
Eosinophils			1%		2-10 %
Monocytes			5 mm/hr		< 20 mm/hr
ESR			187 mg/dl		<220 mg/dl
Cholesterol	- Frank To		166 mg/dl		> 200 mg/dl
Triglycerides			42 mg/dl		35 TO 50 mg/dl
HDL			111.8 mg/dl		
LDL			33.2 mg/dl		
VLDL			4.5		
CHO/HDL Ratio:			30 mg/dl		10-50
Urea			1 mg/dl		0.8-1.3
Creatinine			24 U/L		0-40
SGPT			28 U/L		0-40
SGOT			20 U/L		
S[UTUM AFB	No.	NEGATIVE			
STOOL		NEGATIVE			
Colour Blindness		NO			
ECG		WNL		Spirometry	WNL
X-Ray		WNL		LF. WNL	
AUDIOMETRY		RT: WNL			f-6/18
Vision:	Unaided - D	ist. Rt - /18			Lf - N/36
VISIOIN	Unaided - N	Unaided - Near Rt - N/36			Spect Dist . Lf - 6/6
	With Spect I	Dist. Rt - 6/6			Spect Near . Lf - N/6
		Near.Rt-N/6		- TO ALLE	
MEDICAL CHECK - UF	:- NORMAL			nam any infacti	ous or contagious disease
Opinion: He/She is I	hysically & men	ntally fit . He/She is	not suffering i	rom any miecu	ous or contagious disease
Opinion Alejana				D= DE	EDAK D DEOTALE

Dr. DEEPAK P. DEOTALE M.B.B.S. A.F.I.H.(Reg. No. 48366)

(FORM – O)
(See rule 29F (2) and 29L)
Report of medical examination under rule 29B (To be issued in triplicate)

- (a)* is medically fit for any employment in mines.
- (b)* is suffering from...... and is medically unfit for
 - (i) any employment in mine; or
 - (iii) any employment below ground; or (iii) any employment or work......



Place: Pc L Date: 13/12/24 DR. DEEPAK P. DEOTALE

Signature of the examining authority Name and designation in Block letters

* Delete whatever is not applicable.

** One copy of the certificate shall be handed over to the person concerned and another copy shall be sent to the manager of the mine concerned by registered post; and the third copy shall be retained by the examining authority,

Report of the examining authority

(to be filled in for every medical examination whether initial or periodical or reexamination or after cure/control of disability).

Identification Mark Male on face Right side

Left thumb impression of the candidate

General development- Good/Fair/Poor
2. Height
3 Weight65 kg.
4 Eyes : (i) Visual acuity-Distant vision (with or without glasses).
Right eye6/18 Left eye6/18
(ii) any organic disease of eyes No
(iii) night blindness
(iv) Colour blindness
(v) Squint (* to be tested in special cases) Inserted vide notification No.GSR 656 dated 5.6.1980 √ ○
5 Ears : Hearing : Right ear
Any organic diseases.
6.Respiratory system. Chest measurement : (i) After full inspirationcms. (ii) After full expirationcms.
7. Circulatory system: (i) Blood Pressure
8. Abdomen : Tendemess
9. Nervous system: History of fits or epilepsy Paralysis Mental health.
10.Locomotory system: Normal
10.Locomotory system: Normal 11. Skin: hormal
12. Hydrocele. :
13. Hemia. :
14. Any other abnormality:Moxwd
15. Urine : Reaction
16. Skiagram of chest.: WNL
17. Any other test considered necessary by the examining authority. : No
18. Any opinion of specialist considered necessary. No
Signature of the examining authority

Report of Medical Examination under Mines Rule 298 (To be used in continuation with Form 0)

Certificate No. 166			
Name: Atul Trock	^		
Identification Marks: male	e on face	Right sid	4
Result of Lung Function Test			
Parameters	Predicted Value	Performed Value	9/4
Forced Vital Capacity (FEV)	02-71	03.20	+
Forced Vital Capacity FEV1	02.07	03.14	
101000	06.01		+
FEV 1/ FVC	76.38	98.12	-

FEV 1/ FVC Peak Expiratory Flow Spirometry Report enclosed.

Signature of the Examination Authority

of Predicted 118 152

061

Report of Medical Examination as per the recommendations of National Safety Conferences in Mines (To be used in continuation with Form O)

Certificate No. 166

Name: Atul Tiwan'

1 Cardiological 1

1. Cardiological Assessment

10	./	Performed Value	% of Predicted
S1	N	Ferrormed value	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
S ₂	N		
Additional Sound	No	401	15 (2)
		10	128
oh(12leads) findings	CA	LNormal/Abnormal	
	Additional Sound	S2 N Additional Sound No	S ₂

Enclosed ECG

Dr. 00 2. Neurological Assessment

Findings	Normal/Abnormal
Superficial Reflexes	Normal
Deep Reflexes	N
Peripheral Circulation	N
Vibrational Syndromes	N

3. ILO Classification of Chest Radiograph

Profusion of Pneumoconiotic Opacities	Grades	Types	
Present /Absent			

Enclosed Chest Radiograph

4. Audiometry Findings:

Condution Type	Left Ear	Right Ear	
Ear Conduction	Normal/Abnormal	Normal/Abnormal	
Bone Conduction	Normal/Abnormal	Normal/Abnormal	

Enclosed Audiometry Report

5. Pathological/Microbiological Investigations:

S.No.	Tests	Findings
1.	Blood-Tc,Dc,Hb,ESR,Platelets	WNL/Abnormal
2.	Blood Suger-Fasting & P.P.	WNL/Abnormal
3.	Lipid Profile	WNL/Abnormal
4.	Blood Urea, Creatimine	WNL/Abnormal
5.	Urine Routine	WNL/Abnormal
6.	Stool Routine	WNL/Abnormal

Enclosed Investigation Reports

6. Special Tests for Mn Exposure:

Beh	avioral Disturbances	Present/Not Present
Neurological	Speech Defect	Present/Not Present
Disturbances	Tremor	Present/Not Present -
	Adiadocokinesia	Present/Not Present
	Emotional Changes	Present/Not Present

Enclosed ECG

7. Any other Special Tests Required:

No

Signature of the Examination Authority Seal

it: ATUL KUMAR TIWARI

. By:

d. Eqns: RECORDERS


te: 13-12-2024 10:54:24


: 57 Years Age Height: 160 Cms Weight: 65 Kgs ID: PR 166


: Male Gender : No Smoker Eth. Corr: 100

Temp : degrees











	FVC R	esults			e.Drod	%Imp	
4 - 14	Pred	M. Pre	Pred	M.Post	gried	025	
arameter		03.20	118				
VC (L)	02.71	03.20	152				
EV1 (L)	02.07	98.12	128				
EV1/FVC (%)	76.38	03.94	132				
EF25-75 (L/s)	02.98	04.59	061				
EFR (L/s)	07.54	01.23					
IVC (L)		02.07					
EV.5 (L)	02.63	03.20	122				
EA3 (T)	02.03	02.42					
IFR (L/s)		02.45					
EF75-85 (L/s)	05.22	03.98	076				
EF.2-1.2(L/s)	07.19	04.28	060				
EF 25% (L/s)	04.85	04.22	087				
EF 50% (L/s)	01.88	02.92	155				
EF 75% (L/s)		64.69					
EV.5/FVC (%)	97.05	100.00	103				
EV3/FVC (%)		01.14					
ET (Sec) xplTime (Sec)		00.14					

Early Small Airway Obstruction as FEF 25-75 %Pred or PEFR %Pred < 70 Spirometry within normal limits as (FEV1/FVC) %Pred >95 and FVC%Pred >80.





Deotale Diagnostic Chille

(we care)

Consultation Diagnostics Health Check- Up: Immunization.

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chowk Nagpur

(Clinic Reg. No. 699)

For any assistance call at . 9860204241, 0712-6610595

Date: 13-12-24

AUDIOLOGICAL EVALUATION

1. SR. NO. 157

2. CERTIFICATE NO: 166

3. EMPLOYEES NAME: ATUL KUMAR TIWARI

4. Employee Mob No: 9584460761

6. SEX: MALE

7. AGE: 57 yrs

8. ADDRESS: PRISM JOHNSON LIMITED, MANKAHARI,PO: BATHIA, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.)

9. DIAGNOSIS LT.: WNL

-10 -10

Air O = LEFT EAR : ♥ WNL

Y = RIGHT EAR : ♥ WNL

Masking

No Response: Audiologists Remarks

Dr. DEEPAK P. DEOTALE M.B.B.S. A.F.I.H. Reg. No. 48366

DeotaleDiagnosticCentre

Consultation

Diagnostics

Health Check- Ups

Immunization.

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chouk Nagpur

For any assistance call at . 986^204241, 0712-2424868

Email ID: deotaledeepak 19577@gmail.com

ATUL KUMAR TIWARI
57 yrs
MALE
9584460761
13-12-24
13-12-24

SPUTUM EXAMINATION

ZEIHL NEELSEN STAIN: AFB Not seen

DR .DEEFAK DEVATALE
M.B.B.S A.F.I.H(REG NO.48366)
Dr. Deepak Deotale
MBBS, AFIH
Reg. No. 48366

SR. No.

157

Certificate No.

ト の

Emp Code

102702

TAYN HOSDIN

& RESEARCH INSTITUTE

Add.: Plot .P 78, Opposite State Bank of India , M.I.D.C.

Butibori (Nagpur)

Ph 07103-684885

Deotale Diagnostic Center We Care

Mab. No. 9860204241 /8007771341 Phone No: 0712-2424868			(£ssociated fellow Of industrial health)	W.B.B.S., A.F.I.H.	Dr. Deepak P. Dectale	Consultation Diagnostics Health Check-Ups Immunization
Company Name	MOB NO .	Check Up Date	Gender	Age	Name	ics Health _ Chec
Company Name: PRISM JOHNSON LIMITED, MANKAHARI,PO: BATHIA, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.)	9584460761	13-12-24	MALE	57 YRS.	ATUL KUMAR TIWARI	k-Ups _ Immunization

Deotale Diagnostic Centre 1868 Diagnostics Health Check-Ups Immunization.

Consultation

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chouk Nagpur For any assistance call at . 9860204241, 0712-2424868

Email ID: deotaledeepak19577@gmail.com

MEDICAL CHECK-UP REPORT

SR NO.	112
Certificate No	121
EMP CODE	103728
Work Station / Grade	Bandarkha
Designation	Mines Mgr
MOB NO	9109171029
CHECK-UP DATE	11-12-24

EMPLOYEES NAM	AE: Santosh Kui	mar Chaudha	ri Late I	RamKhelawa	n Chaudhari		
Gender: MALE	Age	: 48 Yrs	Ht:	172 cms	BMI:	22.65	Wt: 67 Kg
Company Addre	MANKAHAI	RI,PO: BATHL	A, TEHS				NA,PIN:485111 (M.P.)
Personal H/O:	ALCOHOL: N	O TA	TABACCO: NO SMOKING: NO				
General Exam:-	Healt	thy	BP .: 122/82 mmHg		mHg	PLUSE: 78 mm/hr	
C.V.S.: N	R/S:	N	CNS :N			SP/LIVER :N/P	

Abdomen: soft

					POR VINE SALES
		Result	The bollen		Normal Range
		mg/dl			70-160 mg/dl
	1	2.8 gm/dl			12.5 to 16.5 gm/dl
	90	600 Cumm			4000-11000 /Cumm
		78 %			40-80 %
		19 %			20-40 %
		2 %			1-6 %
					2-10 %
		7 mm/hr			< 20 mm/hr
	1	.83 mg/dl			< 220 mg/dl
	1	.62 mg/dl			> 200 mg/dl
7		49 mg/dl			35 TO 50 mg/dl
Ī	10	01.6 mg/dl			
	3	2.4 mg/dl			
		3.7			
		30 mg/dl			10-50
		0.8 mg/dl			0.8-1.3
		29 U/L			0-40
		22 U/L			0-40
	NEGATIVE				
	NEGATIVE				
	NO				
	WNL				1 2
	WNL	S	A		WNL
	RT: WNL			-	
Unaided - Dis	st. Rt - 6/6		-		
Unaided - Ne	ar Rt - N/6		and the second name of the second		
				With Spect Dist . Lf -	
With Spect Ne	ear.Rt-		Wit	th Spec	t Near . Lf -
NORMAL					
	Unaided - Ne With Spect Di With Spect Ne	NEGATIVE NEGATIVE NO WNL WNL RT: WNL Unaided - Dist. Rt - 6/6 Unaided - Near Rt - N/6 With Spect Dist. Rt - With Spect Near . Rt -	12.8 gm/dl 9600 Cumm 78 % 19 % 2 % 1 1% 7 mm/kr 183 mg/dl 162 mg/dl 49 mg/dl 101.6 mg/dl 32.4 mg/dl 32.4 mg/dl 3.7 30 mg/dl 0.8 mg/dl 29 U/L 22 U/L NEGATIVE NO WNL NEGATIVE NO WNL WNL RT: WNL Unaided - Dist. Rt - 6/6 Unaided - Near Rt - N/6 With Spect Dist. Rt - With Spect Near . Rt -	mg/dl 12.8 gm/dl 9600 Cumm 78 % 19 % 2 % 19 % 2 % 1 % 7 mm/kr 183 mg/dl 162 mg/dl 49 mg/dl 101.6 mg/dl 32.4 mg/dl 32.4 mg/dl 3.7 30 mg/dl 29 U/L 22 U/L NEGATIVE NEGATIVE NEGATIVE NO WNL WNL WNL WNL WNL Spirometry RT : WNL LF, W Unaided - Dist. Rt - 6/6 Dist. Rt - 6/6 Unaided - Near Rt - N/6 With Spect Dist. Rt - With With Spect Near . Rt -	mg/di

Opinion: He/She is physically & mentally fit . He/She is not suffering from any infectious or contagious diseases

Dr. DEEPAK P. DEOTALE M.B.B.S. A.F.I.H.(Reg. No. 48366)

(See rule 29F (2) and 29L)
Report of medical examination under rule 29B (To be issued in triplicate)

- Certificate No. 121 ... Certified that Shri/Shrimati* Santosh Kuman chaudhau examination. He/she* appears to be years of age.

The findings of the examining authority are given in the attached sheet. It is considered that Shri/Shrimati*... Romfosh. Kumasa. Chaudhasu......

- (a)* is medically fit for any employment in mines.
- (b)* is suffering from..... and is medically unfit for

- (i) any employment in mine; or(ii) any employment below ground; or
- (iii) any employment or work......

(c)* is suffering from..... is should get this disability* cured/controlled and should be again examined within a period ofmonths. He/She will appear for re-examination with the result of test of and the opinion of Specialist from He/She may be permitted/not* permitted to carry on his duties during this period.



Place : PCL Date: 11/12/2024 DR. DEEPAK P. PEOTALE Signature of the examining authority Name and designation in Block letters

* Delete whatever is not applicable. ** One copy of the certificate shall be handed over to the person concerned and another copy shall be sent to the manager of the mine concerned by registered post; and the third copy shall be retained by the examining authority,

Report of the examining authority

(to be filled in for every medical examination whether initial or periodical or reexamination or after cure/control of disability).

Annexure to Certificate No. 121 as result of medical examination on

Identification Mark Male on chest

Left thumb impression of the candidate

General development- Good/Fair/Poor
2. Height
3 Weight6.4 kg.
4 Eyes : (i) Visual acuity-Distant vision (with or without glasses).
Right eye6/9 Left eye6/.9
(ii) any organic disease of eyes √
(iii) night blindness
(iv) Colour blindness
(v) Squint (* to be tested in special cases) Inserted vide notification No.GSR 656 dated 5.6.1980
5 Ears: Hearing: Right ear
Any organic diseases.
6.Respiratory system. Chest measurement : (i) After full inspirationcms. (ii) After full expirationcms.
7. Circulatory system: (i) Blood Pressure 122/82 (ii) Pulse 7.
8. Abdomen : Tenderness (N
9. Nervous system: History of fits or epilepsy Paralysis Mental health.
10.Locomotory system :
11. Skin. :
12 Hydrocele:
13. Hernia. :
14. Any other abnormality :
15. Urine : Reaction
16. Skiagram of chest. : WNL
17. Any other test considered necessary by the examining authority.: /V O
18. Any opinion of specialist considered necessary.
Signature of the examining authority

Place:

Report of Medical Examination under Mines Rule 29B (To be used in continuation with Form O)

Certificate No. 121

Name: 59 ntosh kumon chaudhord

Identification Marks: mole on chest

Result of Lung Function Test (Spirometry)

Parameters	Predicted Value	Performed Value	% of Predicted
Forced Vital Capacity (FEV)	03.44	03.17	092
Forced Vital Capacity FEV1	02.74	03.07	112_
FEV 1/ FVC	79.65	96.85	122
Peak Expiratory Flow	08.71	04.73	054

Spirometry Report enclosed.

Signature of the Examination Authority

Report of Medical Examination as per the recommendations of National Safety Conferences in Mines (To be used in continuation with Form O)

Certificate No. 121

Name: 597/108/ Kumay chaudhari

Identification Marks: male on chest-

1. Cardiological Assessment

Auscultation	S ₁	Ν.	Performed Value	% of Predicted
	S ₂	N		
	Additional Sound	No	96.85	122
FEV1/FVC		1,0		
Electrocardiograp	oh(12leads) findings		Normal/Abnormal	

Enclosed ECG

2. Neurological Assessment 10

Findings	Normal/Abnormal
Superficial Reflexes	Normae!
Deep Reflexes	
Peripheral Circulation	AINO
Vibrational Syndromes	(V _N)

3. ILO Classification of Chest Radiograph

Profusion of Pneumoconiotic Opacities	Grades	Types	1
Present /Absent		The second secon	

Enclosed Chest Radiograph

4. Audiometry Findings:

Candi			
Condution Type	Left Ear		Right Ear
Ear Conduction			
	Normal/Abnormal	L	Normal/Abnormal
Bone Conduction	Normal/Abnormal	-	Normal/Abnormal

Enclosed Audiometry Report

5. Pathological/Microbiological Investigations:

S.No.	Tests		Findings
1.	Blood-Tc,Dc,Hb,ESR,Platelets	2 W	/NL/Abnormal
2.	Blood Suger-Fasting & P.P.		/NL/Abnormal
3.	Lipid Profile		/NL/Abnormal
4.	Blood Urea, Creatimine	W	/NL/Abnormal
5.	Urine Routine	W	/NL/Abnormal
6.	Stool Routine	V N	/NL/Abnormal

Enclosed Investigation Reports

6. Special Tests for Mn Exposure:

			The same of the sa
Beh	avioral Disturbances	Present/Not Present	V
Neurological	Speech Defect	Present/Not Present	1
Disturbances	Tremor	Present/Not Present	v
	Adiadocokinesia	Present/Not Present	1
	Emotional Changes	Present/Not Present	-

Enclosed ECG

7. Any other Special Tests Required:

No

Signature of the Examination Authority Seal

ent: SANTOSH KUMAR CHAUDHARI

.d. By:

red.Eqns: RECORDERS

Date: 11-12-2024 10:39:50


Age : 48 Years Height: 172 Cms

Weight : 67 Kgs ID: PR 121


Gender : Male Smoker : No Eth. Corr: 100


Temp : degrees






This report is not to b





		FVC R	esults				
Parameter		Pred	M.Pre%	Pred	M. Post	%Pred	%Imp
FVC	(L)	03.44	03.17	092			
FEV1	(L)	02.74	03.07	112			
FEV1/FVC	(%)	79.65	96.85	122			
FEF25-75	(L/s)	03.62	03.78	104			
PEFR	(L/s)	08.71	04.73	054			
FIVC	(L)		01.17				
FEV.5	(L)		01.96				
FEV3	(L)	03.33	03.17	095			
PIFR	(L/s)		03.44				
FEF75-85	(L/s)		02.18				
FEF.2-1.2	(L/s)	06.45	03.97	062			
FEF 25%	(L/s)	07.79	04.23	054			
FEF 50%	(L/s)	05.43	03.80	070			
FEF 75%	(L/s)	02.42	02.76	114			
FEV.5/FVC	(8)		61.83				
FEV3/FVC	(%)	96.80	100.00	103			
FET (Sec)			01.27				
ExplTime	(Sec)		00.14				

Pre Medication Report Indicates Early Small Airway Obstruction as FEF 25-75 %Pred or PEFR %Pred < 70 Spirometry within normal limits as (FEV1/FVC) %Pred >95 and FVC%Pred >80.



Consultation Diagnostics Health Check- Up: Immunization. Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chowk Nagpur


(Clinic Reg. No. 699)

For any assistance call at . 9860204241, 0712-6610595

Date: 11-12-24


AUDIOLOGICAL EVALUATION

2. CERTIFICATE NO: 121 1. SR. NO. 112 3. EMPLOYEES NAME : Santosh Kumar Chaudhari Late RamKhelawan Chaudhari 4. Employee Mob No : 9109171029 7. AGE: 48 yrs 6. SEX: MALE 8. ADDRESS: PRISM JOHNSON LIMITED, MANKAHARI, PO: BATHIA, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA, PIN: 485111 (M.P.) RT.: WNL 9. DIAGNOSIS LT.: WNL



TEST FREQUENCY WNL = LEFT EAR : 0 Air O WNL = RIGHT EAR : 0 Y Masking No Response: Audiologists Remarks

> Dr. DEEPAK P. DEOTALE M.B.B.S. A.F.I.H. Reg. No. 48366



DeotaleDiagnosticCentre

Consultation Diagnostics Health Check- Ups Immunization.

Clinic: Vinayak Apt. 3rd floor Dhantoli Lokmat Chouk Nagpur

For any assistance call at . 9860204241, 0712-2424868

Email ID: deotaledeepak19577@gmail.com

Patient Name:	Santosh Kumar Chaudhari Late RamKhelawan Chaudhari
Age:	48 yrs.
Gender:	MALE
Req. Doctor:	
Reg . Number:	9109171029
Collection Date:	11-12-24
Reporting Date :	11-12-24

SPUTUM EXAMINATION

ZEIHL NEELSEN STAIN: AFB Not seen

DR .DEEPAK DEVATALE M.B.B.S A.F.I.H(REG NO.48366)

112

Certificate No.

Emp Code 103728

MAYA HOSPITAL

& RESEARCH INSTITUTE

Add.: Plot .P 78, Opposite State Bank of India , W.I.D.C.

Butibori (Nagpur)

Ph 07103-684885


Deotale Diagnostic Center We Care

Phone No: 0712-2424868 Email id:deotaledeepak19577@gmail.com	Moh No 9860204241 (Clinic Reg. No. 699)	Clinic : Vinayak Apt. 3" floor Dhantoli,	Certifying Surgeon Reg .No. 48366	(Associated fellow Of industrial health)	M.B.B.S., A.F.I.H.	Dr. Deepak P. Deotale	ConsultationDiagnostics HealthCheck-Ups
Company Name	MOB NO	Check Up Date	Gender	Age		Name	rics Health _ Chec
Company Name: PRISM JOHNSON LIMITED, MANKAHARI,PO: BATHIA, TEHSIL: RAMPUR BAGHELAN, DIST: SATNA,PIN:485111 (M.P.)	9109171029	11-12-24	MALE	48 YRS.	RamKhelawan Chaudhari	Santosh Kumar Chaudhari Late	k-Ups Immunization

S.N.	Category under Schedule VII	Description of Activity		Budget A	mount Rs	. In Crore		Spent Rs
			Q-1	Q-2	Q-3	Q-4	Total	in Crore
1	Availability of drinking water Schedule VII (i))	Availability of potable water through installation of hand pumps with bore well, supply through water tankers	0.02	0.02	0.00	0.01	0.05	0.03
2	Environment, water Conservation and Promoting renewable energy Schedule VII (iv)	Plantation and survival, construction of water harvesting structures, deepening of ponds, development of social forestry	0.09	0.17	0.03	0.04	0.33	0.14
3	Health & Hygiene Schedule VII (i)	Free medical facility, camps and free ambulance service	0.03	0.04	0.05	0.04	0.16	0.07
4	Promoting Education Schedule VII (ii)	Repairing & maintenance of school buildings, slogan writing, Construction of boundary wall	0.04	0.07	0.08	0.06	0.25	0.02
5	Rural Infrastructure Development Schedule VII (X)	Renovation of community centers, Construction of drainage in villages	0.01	0.08	0.08	0.00	0.17	0.04
6	Social Welfare Schedule VII (iii, iv & vi)	Support to old age home, animal Welfare and other assistance required as per development activity	0.04	0.03	0.02	0.01	0.10	0.06
7	Vocational Skill Development Schedule VII (ii)	Vocational skill development trainings, livelihood support	0.00	0.00	0.04	0.01	0.05	0.00
	Total		0.23	0.41	0.30	0.17	1.11	0.36

Prism Johnson Limited

ENVIRONMENT MANAGEMENT CELL



SI. No.	CSR Project Name/ Activities Undertaken	Item from the list of activities in Schedule VII of the Act	L	ocation of the Pr	oject	lm	plementatio	n Schedule in crore	during FY 20	24-25	Amount Spent In the Project or Programs (Rs. in	Mode of Implementati on Direct:	Mode of Implementation - 1 Agend	
	Undertaken	Scriedule VII of the Act	Local Area (Yes/No)	State	District	Q1	Q2	Q3	Q4	Total	Crore)	Yes/No		CSR Registration No.
A.	Availability of drinking water Sch	edule VII (i))												
1	Supplied 166 trip Drinking water supply through Water Tanker at Mankahari	Availability of Safe Drinking Water Schedule VII (i)	Yes	Madhya Pradesh	Satna	0.02	0	0	0.01	0.03	0.03	Yes	-	-
2	Drilling of a 300-foot bore well with 1 HP submersible water pump installation at Khambha Baba Mankahari	Availability of Safe Drinking	Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.01	Yes	-	-
3	Installation of new Hand pump with bore well at nearby villages Baghai		Yes	Madhya Pradesh	Satna	0	0.01	0	0	0.01	0.01	Yes	•	-
4	Installation of new hand pump at Bathiya	Availability of Safe Drinking Water Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0.01	0	0	0.01	0.01	Yes	-	-
5	Providing of Water Cooler and Water Purifier Machine at Government Higher Secondary School Bamhauri FY 24-25	Availability of Safe Drinking	Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.01	Yes	-	-
6	Providing 7680 no's packaged water for safe drinking water distribution at Rampur Baghelan		Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.00	Yes	-	-
7	Drilling of 400 ft. bore well at Mahurachh Turning for availability of drinking water	Availability of Safe Drinking Water Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.01	Yes	-	-
			Sub Total			0.02	0.02	0.00	0.01	0.05	0.08			
В.	Environment, water Conservation energy	and Promoting renewable												
8	Road side plantation with 65 tree guards at Baghai and Medhi	Plantation for Environment Conservation Schedule VII (iv)		Madhya Pradesh	Satna	0	0.02	0	0	0.02	0.02	Yes	-	-
9	Survival of 53000 saplings at Khamhariya Forest Land plantation	Plantation for Environment Conservation Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0.04	0.03	0.03	0.04	0.14	0.12	Yes	-	-
10	Survival of 20000 saplings at Chulhi Jamodi Forest Land plantation under CSE/CSR redencification Scheme			Madhya Pradesh	Satna	0.03	0	0	0	0.03	0.03	No	Divisional Forest Officer Satna	CSR00033247

SI. No.	CSR Project Name/ Activities Undertaken	Item from the list of activities in Schedule VII of the Act	L	ocation of the Pr	oject	lm	plementatio	n Schedule in crore	during FY 20	24-25	Amount Spent In the Project or	Mode of Implementati on Direct:	Mode of Implementation - Agend	
	Undertaken	Schedule VII of the Act	Local Area (Yes/No)	State	District	Q1	Q2	Q3	Q4	Total	Programs (Rs. in Crore)	Yes/No	Name	CSR Registration No.
11	Distribution of 5200 Fruit Plants to villagers at Mankahari, Malgaon, Mahurachh, Bahelia Bhat, Baghai, Narsinghpur, Hinauti, Ghunghunchihai, Sajjanpur, Bairiha, Sijahata, Bathiya, Municipal Corporation Rampur Baghelan	Plantation for Environment Conservation Schedule VII (iv)		Madhya Pradesh	Satna	0	0.01	0	0	0.01	0.02	Yes	-	-
12	Desilting of 145 M waterways channel at Bamhauri	Conservation of Natural Resources Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0.01	0.02	0	0	0.03	0.02	Yes	-	-
13	Construction of a Single Bore shaft water harvesting structures at Selhana Baijanaha	Water Conservation Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0.01	0	0	0	0.01	0.01	Yes	-	-
14	Construction of a Single Bore shaft water harvesting structures at Padkhuri	Water Conservation Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0	0.02	0	0	0.02	0.02	Yes	-	-
15	Construction of 50 perforated drum based water harvesting structures at Tapa	Water Conservation Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0	0.02	0	0	0.02	0.03	Yes	-	-
16	Construction of 50 perforated drum based water harvesting structures at Bairiha		Yes	Madhya Pradesh	Satna	0	0.02	0	0	0.02	0.03	Yes	-	-
17	Construction of 50 perforated drum based water harvesting structures at Bathiya	Water Conservation Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0	0.03	0	0	0.03	0.03	Yes	-	-
			Sub Total			0.09	0.17	0.03	0.04	0.33	0.33			
C.	Health & Hygiene Schedule VII (i)													
18	Free consultation & medicine distribution to 16435 patients from Apr to Mar 25 at PCL Medical Centre Out door patient to nearby villagers from Mankahari, Hinauta, Hinauti, Pithaipur, Badarakha, Sijahata, Medhi, Jhanjhar, Mugwari, Baghai, Bathiya, Bamhauri, Mahurachh, Narsinghpur, Chulhi, Majhiyar, Bairiha & Chormari		Yes	Madhya Pradesh	Satna	0.01	0.01	0.01	0.01	0.04	0.07	Yes	-	-

SI. No.	CSR Project Name/ Activities	Item from the list of activities in	L	ocation of the Pro	oject	lm	plementatio	n Schedule in crore	during FY 20	24-25	Amount Spent In the Project or	Mode of Implementati	Mode of Implementation - Agend	
	Undertaken	Schedule VII of the Act	Local Area (Yes/No)	State	District	Q1	Q2	Q3	Q4	Total	Programs (Rs. in Crore)	on Direct: Yes/No	Name	CSR Registration No.
19	Providing of free ambulance services to 1027 patients from Apr 24 to Mar 25, from Mankahari, Hinauta, Hinauti, Pithaipur, Badarakha, Sijahata, Medhi, Jhanjhar, Mugwari, Baghai, Bathiya, Bamhauri, Mahurachh, Narsinghpur, Chulhi, Majhiyar, Bairiha & Chormari	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0.02	0.02	0.02	0.02	0.08	0.08	Yes	-	-
20	Door to Door Health Services to 1486 villagers through Mobile Health Van at Sijahata, Baghai, Malgaon, Narsinghpur, Badarkha, Chulhi and Majhiyar	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.00	Yes	-	-
21	Organisation of Mega Medical Camps at Katra Narsinghpur (Attended 326 Pts)	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0	0.01	0	0.01	0.01	Yes	-	-
22	Organisation of Mega Medical Camps at Jhanjhar Sijahata (Attended 235 patients	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0	0.01	0	0.01	0.01	Yes	-	-
23	Organisation of Mega Medical Camps at Bairiha (Attended 284 patients)	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0	0	0.01	0.01	0.01	Yes	-	-
24	The organisation of Mega Medical Camps at Malgaon (Attended 235 patients)	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0	0	0	0	0	0.01	Yes	-	-
25	Operation & Maintenance of Sulabh Complex at Mahurachh Turning (12 months)	Health & Hygiene Schedule VII (i)	Yes	Madhya Pradesh	Satna	0.00075	0.00075	0.00075	0.00075	0	0.00	Yes	-	-
26	Providing 03 sanitary pad vending machines at Govt High School Bamhauri, Bairiha and Sijahata villages	Health & Hygiene Schedule	Yes	Madhya Pradesh	Satna	0	0.01	0	0	0.01	0.00	Yes	-	-
			Sub Total			0.03	0.04	0.05	0.04	0.16	0.19			
D.	Promoting Education Schedule V	II (ii)												
27	Renovation of Government Middle School Chulhi	Promoting Education Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0.01	0.02	0	0.03	0.04	Yes	-	-
28	Painting of Government Degree College Rampur Baghelan	Promoting Education Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0.01	0.01	0	0.02	0.02	Yes	-	-

SI. No.	CSR Project Name/ Activities Undertaken	Item from the list of activities in Schedule VII of the Act	L	ocation of the Pro	oject	Im	plementatio	n Schedule in crore	during FY 20	24-25	Amount Spent In the Project or Programs (Rs. in	Mode of Implementati on Direct:	Mode of Implementation - Agend	
	Officertaken	Scriedule VII of the Act	Local Area (Yes/No)	State	District	Q1	Q2	Q3	Q4	Total	Crore)	Yes/No	Name	CSR Registration No.
29	Renovation of Government Primary School Bardadih	Promoting Education Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0	0.01	0.01	0.02	0.02	Yes	-	-
30	Construction of 58 M Boundary wall at Government Primary School Medhi	Promoting Education Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0.03	0.03	0.02	0.04	0.12	0.04	Yes	-	-
31	Renovation and support to Anganvadi-1 at Bamhauri village	Promoting Education Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0	0.01	0.01	0.02	0.03	Yes	-	-
32	200 Awareness Wall paintings and slogans writing pertaining to different social themes at Mahurachh, Karmau, Bairiha and Tapa	Promoting Education	Yes	Madhya Pradesh	Satna	0.01	0	0	0	0.01	0.01	Yes	-	-
33	Distribution of stationery and Bag to 800 students from Govt Schools Hinauti, Sijahata, Medhi, Bamhauri, Chulhi, Malgaon, Majhiyar, Mankahari, Narsinghpur and Baghai	Promoting Education Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0.01	0.01	0	0.02	0.03	Yes	-	-
34	Scholarship to 36 Meritorious (1st, 2nd and 3rd rank holder) Students from Government Higher Secondary School Sijahata and Bamhauri, Government Girls Middle School Sijahata, Government Middle School Mankahari, Hinauti, Baghai, Malgaon and Chulhi	•	Yes	Madhya Pradesh	Satna	0	0.01	0	0	0.01	0.01	Yes	-	-
			Sub Total			0.04	0.07	0.08	0.06	0.25	0.20			
E.	Rural Infrastructure Development	t Schedule VII (X)												
35	Construction of 135 meters Pathway along with pond at Mankahari		Yes	Madhya Pradesh	Satna	0	0.01	0.02	0	0.03	0.04	Yes	-	-
36	Construction of 100 running meter drainage at Chulhi	(X)		Madhya Pradesh	Satna	0	0.02	0.02	0	0.04	0.03	Yes	-	-
37	Construction of 100 running meter drainage at Baghai	Rural Infrastructure Development Schedule VII (X)	Yes	Madhya Pradesh	Satna	0	0.02	0.02	0	0.04	0.03	Yes	-	-
38	Repairing and renewal of the Vindhya Club Community building badminton court flooring at Satna 24-25	Rurai intrastructure	Yes	Madhya Pradesh	Satna	0.01	0.01	0	0	0.02	0.02	Yes	-	-

SI. No.	CSR Project Name/ Activities Undertaken	Item from the list of activities in Schedule VII of the Act	Location of the Project			Implementation Schedule during FY 2024-25 in crore				24-25	Amount Spent In the Project or Programs (Rs. in	Mode of Implementati on Direct:	Mode of Implementation - Through Implementing Agency	
			Local Area (Yes/No)	State	District	Q1	Q2	Q3	Q4	Total	Crore)	Yes/No	Name	CSR Registration No.
39	Construction of river ghat near devimandir at Hinauti	Rural Infrastructure Development Schedule VII (X)		Madhya Pradesh	Satna	0	0.02	0.02	0	0.04	0.04	Yes	-	-
40	Repairing and renewal of the Cremation shed at Malgaon 24-25	Rural Infrastructure Development Schedule VII (X)		Madhya Pradesh	Satna	0	0	0	0	0.00	0.00	Yes	-	-
			Sub Total			0.01	0.08	0.08	0.00	0.17	0.16			
F.	F. Social Welfare Schedule VII (iii, iv & vi)													
41	Support to Old Age Home, Dr. Lalta Prasad Khare Charitable Trust, Nimi Babupur	Social Welfare Schedule VII (iii)	Yes	Madhya Pradesh	Satna	0.02	0.02	0.01	0.01	0.06	0.06		Dr. Lalta Prasad Khare Public Charitable Trust Chandrashaya Sakariya Road Nimi Satna	CSR00000455
42	Distribution of thermo cot innerwear to 200 Sr. Citizens at Satna FY 24-25	Facilities for Senior Citizen Schedule VII (iii)	Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.01	Yes	-	-
43	Assistance for Armed Forces Flag Day	Assistance Measures for development of societies, war widows, social weaker section of society, promoting art and culture Schedule VII (iii)	Yes	Madhya Pradesh	Satna	0	0	0.01	0	0.01	0.01	Yes	-	-
44	Distribution of 400 T-shirts to Women from Rewa under "Empowering Women" at Rewa	"Empowering Women" Schedule VII (iii) FY 24-25, Social welfare	Yes	Madhya Pradesh	Rewa	0	0	0	0	0.00	0.00	Yes	-	-
45	Fodder arrangement for 100 cows at Gaushala Mahurachh	Animal Welfare Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0.02	0.01	0	0	0.03	0.03	Yes	Jai Gurudev Group Of Social Welfare Organisation Nagod	CSR00015295

SI. No.	CSR Project Name/ Activities Undertaken	Item from the list of activities in Schedule VII of the Act	Location of the Project			Implementation Schedule during FY 2024-25 in crore				24-25	Amount Spent In the Project or Programs (Rs. in	Mode of Implementati on Direct:	Mode of Implementation - Through Implementing Agency	
			Local Area (Yes/No)	State	District	Q1	Q2	Q3	Q4	Total	Crore)	Yes/No	Name	CSR Registration No.
46	Assistance to Govansh Vikash Aum Anushandhan Kendra, Deendayal Research Institute, Chitrakoot FY 24-25	Animal Welfare Schedule VII (iv)	Yes	Madhya Pradesh	Satna	0	0	0	0	0.00	0.05	No	Deen Dayal Research Institute, 7-E, Swami Ramtirth Nagar, Rani Jhansi Road, New Delhi, DL01, DL, 110055 Tel.: 07670-265623, email: drichitrakoot.org.in, info@dri.org.in Website: www.dri.org.in	CSR00008614
			Sub Total			0.04	0.03	0.02	0.01	0.10	0.16			
G.	G. Vocational Skill Development Schedule VII (ii)													
	Training program for driver with license making for 50 persons from Rampur Baghelan Block	Vocational Skill Development Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0	0.01	0	0.01	0.01	Yes	-	-
48	Training program for Stitching for 33 persons from nearby villages. (Sijahata (15) and Baghai (18))	Vocational Skill Development Schedule VII (ii)	Yes	Madhya Pradesh	Satna	0	0	0.02	0.01	0.03	0.04	Yes	Pipra Sewa Dal Biradari Sansthan, Gram Pipra Kala, Post Maihar, Satna	CSR00067053
49	Training program for farmers for organic farming to 50 farmers from Baghai, Sijahata, Hinauti, Bathiya, Bairiha, Mahurachh, Malgaon, Narsinghpur		Yes	Madhya Pradesh	Satna	0	0	0.01	0	0.01	0.01	Yes	Pipra Sewa Dal Biradari Sansthan, Gram Pipra Kala, Post Maihar, Satna	CSR00067053
			Sub Total			0.00	0.00	0.04	0.01	0.05	0.06			
			Grand Total			0.23	0.41	0.30	0.17	1.11	1.18			

Oct-24 to Mar-25								
Particulars	Expenditure (Rs)							
r articulars	Unit-1	Unit-2	Total					
Maintenance cost for operating air pollution controlling equipment's	675827.66	10215619.11	10891446.77					
APCE power consumption Cost	32,295,065.60	47,446,393.17	79741458.77					
STP Operation & maintenance	2,309,	503.03	2309503.03					
House Keeping			0.00					
Plantation, Maintenance & survival	1,515,	070.50	1515070.50					
Environmental Study/Audit	531,0	00.00	531000.00					
Environmental monitoring & Compliance	688,017.50	1,948,935.00	2636952.50					
License/Permission	6,860	5,606	6866606.00					
Others (RWH structure maintenance, Poster/Slogan etc)	259,0	33.60	259033.60					
CEMS/ AAQMS Maintenance Cost	1,500,	00.000	1500000.00					
Expenditure from mines dept. (includes monitoring)	3,510,	500.00	3510500.00					
Total 109,761,571.17								

Note:

- 1. Digital processing of mining lease is already considered.
- 2. JM mines monitoring is included in "expenditure from mines dept. row". Kindly add further expenses done in mines, in the same row.
- 3. In housekeeping row, data is yet not shared by civil dept. (even after multiple reminders), will update once shared.
- 4. Unit-1 expense can be removed, if not required.



PRISM CEMENT LIMITED

Words: Vill-Mankelton, P.C., Jaffer, Drai, Sacra - 685; (1 on P.) Incita 8.1 - (0) 673; 275.00-5; 275.62; 2.1 Kay - 175.10; Corpp. Add. - Rayleny - Reyn Royd, Saina - 585.00; (M.P.) India 10.1 - (07672) 802726; Fax: +02710



Ref: PCU/ENV/2011/31/U2 Date: 11.04.2011

To, Regional Director, Ministry of Environment & Forests Regional Office, Western Region Ravishankar Nagar, Bhopal

Dear Sir,

Sub: Intimation of financial closure of the project Your Ref: I-11011/949/2007-IA-II (I) Date 22.09.2008

With reference to above mentioned subject and letter, we would like to inform you that the date of financial closure / commercial production is 01.01.2011. A certificate in this regard is attached.

Thanking you,

Yours faithfully, For PRISM CEMENT LIMITED

D.K.Singh Jt. General Manager (Environment)

Enc: as above

मध्यप्रदेश शासन जिला लापार एवं उद्योग केन्द्र, सतना

कमांक/जियालके-सत/बृहद लहांग/2011/

सतना दिनांक :-

उत्पादन प्रमाण पत्र

प्रमाणित किया जाता है कि पेसर्स प्रिज्म सीमेंट यूनिट- 2 (ए यूनिट आफ प्रिज्म सीमेंट लिए) ग्राम मनकहरी पोए विदया जिला—सत्तना (म०प्र०) को भारत सरकार उद्योग मंत्रालय से आईवईएएमए पार्ट की जारी किया गया है जिसका नं० 3406/ आईआईएम/ पीआरओडी/2011 न्यू देहली दिगांक 27-1-11 है । इसमें वर्णित उत्पाद का नाम वार्षिक स्थापित अमता एवं उत्पादन दिगांक निम्नानुसार है :--

母0	आइटम कोड	उत्पाद का नाम	स्टाल कैपिसिटी	व्यवसायिक उत्पादन दिनांक
t-	3242	आल वैसइटीज आफॅ पोर्टलैण्ड सीमेंट	3600000 टन	1-1-2011
2	3241	सीमेंट क्लिंकर	2300000 ਟਜ	1-1-2011

उपरोक्तानुसार एवं इकाई द्वारा प्रस्तुत किये गये अभिलेखों के आधार पर सीमेंट क्लिकर की वार्षिक उत्पादन क्षमता 2300000 टन एवं आल वैराङ्टीज आफ पोर्टलैण्ड सीमेंट की वार्षिक उत्पादन क्षमता 3600000 टन के लिये, व्यवसायिक उत्पादन दिनांक 1-1-2011 音!

---- ट्र महाप्रबंधक

जिला व्यापार एवं उद्योग केन्द्र,

सतना(म०प्र०)

सतना,दिनांक :- 31/3/11

कमांक/जिव्याउके-सत/बृहद उद्योग/2011/ 65/5-प्रतिलिपि :-

मेंसर्स प्रिज्य सीमेंट यूनिट- 2 (ए यूनिट आफ प्रिज्म सीमेंट लि0) ग्राम मनकहरी

पो0 विठया जिला-सतना (म०प्र०) ।

HERITER जिला व्यापार एवं नहींग केन्द्र, सर्विति (१०४०) जिला व्यापार एवं नहींग के व

लिस्वद्धा मिनाक 25.0°

आम सूचना

सर्वसाधारण को यह सूचित किया जाता है कि प्रिज्म सीमेंट (यूचिटे-II) क्लिंकर प्रोडक्शन 3.0MTPA; रूसीमेंट प्रोडक्शन 6.7MTPA और माइन्स (पेहनौती और सिजहटा 772.067 हे., हिनौती और सिजहटा 772.067 हे., हिनौती और सिजहटा 99.416 है. मेढी 117.594 हे. और लगहाई - 512.317 हे.) मृनुकहरी, पोस्ट-बठिया जिला सतना (म.प्रे.) का पर्यावरणीय क्लियरेंस हो गया है। पर्यावरणीय क्लियरेंस हो गया है। पर्यावरणीय क्लियरेंस हो गया है। पर्यावरणीय क्लियरेंस की प्रक्रि म.प्र. प्रदूषण नियंत्रण बोर्ड एवं पर्यावरण एवं वन मंत्रालय की वेव साइट Lttp://entor.nic.in पर उपलब्ध है।

(2) ary, EHNA)

आम सूचना

सर्व साधारण को यह सूचित किया जाता है कि प्रिज्य सीमेंन्ट (यूनिट-॥) क्लिकर प्रोडक्शन 3.0 एम टी पी ए, सीमेन्ट प्रोडक्शन 6.7 एम टी पी ए और माइन्स (हिनौती और सिजहटा 772.067 है., हिनौती और सिजहटा 99.416 हे., मेढ़ी 117.594 हे. और बगहाई 512.317 हे.) मनकहरी, पोस्ट बठिया जिला सतना (म.प्र.) का पर्यावरणीय क्लियरेंस की प्रति म.प्र. प्रदूषण नियंत्रण बोर्ड एवं पर्यावरण एवं वन मंत्रालय को बेव साइट http://entor.nic.in पर उपलब्ध है।

प्रबंधक प्रिन्म सीमेन्ट लि. मनकहरी, जिला सतना मुप्र 1. A state of the art ceramic membrane based automated Oil and Grease trapping unit with 5KLD capacity is installed for separation of oil and grease particles from water (ETP Photos)







2. For domestic wastewater, there is a sewage treatment plant with capacity of 600 KLD

